REQUEST FOR LEGISLATIVE ACTION

Completed by County Counselor's Office: Res/@mmbNo.: 19637

Sponsor(s): Date:

Alfred Jordan November 6, 2017

SUBJECT	Action Requested Resolution Ordinance Project/Title: Transferring \$45,939.04 from Non Departmental Health fund to Corrections for the purchase of emergency egress improvements at the Detention Center, Annex, and Albert Riederer Community Justice Complex					
BUDGET INFORMATION	Amount authorized by this legislation this fiscal year:	\$45,939.04				
To be completed	Amount previously authorized this fiscal year:	\$				
By Requesting	Total amount authorized after this legislative action:	\$45,939.04	THE PROPERTY OF THE			
Department and	Amount budgeted for this item * (including transfers):	\$45,939.04				
Finance	Source of funding (name of fund) and account code number; FROM / TO					
	FROM: Non Departmental Health Fund	FROM ACCT 002-5102-56790				
		\$45,939.04				
	Corrections: Facility Management/ Maintenance and Repair Buildings	TO ACCT 002-5102-56510				
	Kepali Bullungs	\$45,939.04				
	*If account includes additional funds for other expenses, total budgeted in the account is: \$ OTHER FINANCIAL INFORMATION: No budget impact (no fiscal note required) Term and Supply Contract (funds approved in the annual budget); estimated value and use of contract: Department: Estimated Use: \$					
	Prior Year Budget (if applicable): Prior Year Actual Amount Spent (if applicable):					
PRIOR LEGISLATION	Prior ordinances and (date):					
	Prior resolutions and (date):					
CONTACT INFORMATION	RLA drafted by (name, title, & phone): Craig Mosher, Corrections Facility Management Admin, (816) 881-4399					
REQUEST SUMMARY	Department of Corrections is requesting emergency egress improvements to specific doors at the Detention Center, Annex, and Albert Riederer Community Justice Complex					
	The improvements will be obtained from existing County contracted vendors Overhead Door and Ted Systems.					
CLEARANCE	Tax Clearance Completed (Purchasing & Department)					

ATTACHMENTS Memo dated 11/18/2015 by Craig Mosher regarding Plumbing Project					
EVIEW	Department Director			Date:	
	be between the beautiful the b			10.0	
	Finance (Budget App If applicable	proval):		Date: 1067	
	Division Manager:	1		Date:	
		00.7		1/20	
	County Counselor's	Office:		Date: / /	
is chargeal	de and there is a cash b	cumbered to the credit of the appropriat alance otherwise unencumbered in the t ient to provide for the obligation herein	reasury to the credit of th		
is chargeal payment is	to be made each suffic	alance otherwise unencumbered in the t	reasury to the credit of th authorized.		
is chargeab payment is Funds suff	to be made each suffice to be made each suffice icient for this expenditu	alance otherwise unencumbered in the ti ient to provide for the obligation herein	reasury to the credit of the authorized. nce #		
is chargeab payment is Funds suff	ele and there is a cash be to be made each suffic- icient for this expenditu- icient for this appropria	alance otherwise unencumbered in the talent to provide for the obligation herein are will be/were appropriated by Ordina	reasury to the credit of the authorized. nce #	e fund from which	

Fiscal Note: Jackson County, Missouri

Funds sufficient for this transfer are available from the sources indicated below.

Date:	October 27, 2017	C#			RES#	19637
Departn	nent / Division	Character/Description	Fron	m	То	
Health Fund - (002					
5102 - Non-Dep	partmental	56790 - Other Contractual Services	\$	45,940	\$	9 4 8
5102 - Non-Dep	partmental	56510 - Maint. & Repair - Buildings				45,940
			_			
-						
					-	
	= 12		-			
		-	8		_	
-			*			
		-				
			2			
<u> </u>		·	9:			
					_	
		:			_	
		:	-			
		-	-		_	
е —			-		_	
9		£			-	
			\$	45,940	\$	45,940

Budget Office



October 19, 2017

Craig Mosher Jackson County Missouri 1315 Locust Kansas City, MO. 64106

Re: 1315 Locust – Door Adds and Changes

Dear Mr. Mosher,

Pursuant to your request for pricing the addition of a Card Readers and Devices and Interfacing with Delayed Egress doors on the 1st and 2nd floors of 1315 Locust, I am pleased to offer the following proposal for your consideration. Project to Reference BID No. 21-14, Resolution 18810

Scope of Work:

Ted Systems will include equipment (Listed below) and **Prevailing Wage Installation labor** for the Scope of work listed below:

1st Floor

There is a set of Double doors leading to an Exit Corridor to the stairwell that will receive Delayed Egress locks (supplied by others). TED Systems will add a Card Reader, Door Position Switches, REX Motion Device and associated cabling for the door. TED Systems will also interface into the (customer supplied) Delayed Egress Locks for proper operation.

The New Card Reader and devices will connect to a NEW Dual Reader Board that will be installed in an existing enclosure located in the LAN Room on the same floor and be programmed.

2nd Floor

There is a single door leading to an Exit Corridor to the stairwell that will receive Delayed Egress locks (supplied by others). TED Systems will interface the existing card reader into the delayed egress locks (supplied by others) for proper operation when card is read to get through the door.

The Existing Door Intercom/Video Station on the exterior single door off the lobby will be removed and relocated to the entry into DIV 18, and marked for DIV31.

On the interior of the corridor is an entry leading into DIV 31. TED Systems will add a Card Reader, Door Position Switch, REX Motion Device, Electrified Strike and associated cabling for the door.

The New Card Reader and devices will connect to a NEW Dual Reader Board that will be installed in an existing enclosure located in the LAN Room on the first floor and be programmed.

Schedule of Equipment

QTY	MATERIAL DESC.	Part Number
7	Panel Equipment/1st floor	
1	Dual Reader Board	LNL-1320
	1st Floor Card Reader Door Add	
1	Prox Reader	5535BGN00
2	Door Contact	1078C-N
1	REX	DS 150i
1	Interface to Customer Supplied Delayed Egress Crash Bar and Magnetic Locks	TEDSYS
LOT	Composite Reader Cable	AC251822B
	2nd Floor Adds/Moves	
	Exterior Entry off Lobby	
1	Interface to Customer Supplied Delayed Egress Crash Bar and Magnetic Locks	TEDSYS
1	Relocate Video Intercom to Entry outside DIV 18	TEDSYS
1	Intercom Cabling	2C18G
	Interior Corridor Door DIV 31 Card Reader Add	
1	Prox Reader	5535BGN00
1	Door Contact	1078C-N
1	REX	DS 150i
1	Electric Strike HES 5000C	10190403
LOT	Composite Reader Cable	AC251822B

Equipment Investment: \$1,789.04

Engineering, Project Management and Prevailing Wage Installation Investment: \$4,851.00

Proposal Investment:

\$6,640.04 excludes Missouri Sales taxes

This quote excludes the following and anything not specifically listed on this quote:

- Excludes any Missouri Sales Taxes, will be added to invoice if applicable.
- Customer to supply Fire Alarm Tie in to meet safety requirements at the Delayed Egress Doors
- Customer or others to supply the Delayed Egress Crash Bar and Locks for the double doors on the 1st floor and the single door on the 2nd floor
- Allow 3 -4 weeks to order parts and installation scheduling

Acceptan Contractor	r: TED Systems, LLC	OWNER: Jackson County Missouri
Signed:		7 8
	Printed Name and Title	Printed Name and Title
	Date	Date

I always appreciate the opportunity to be of service and look forward to working with you on this project. Please feel free to contact me with any questions or if I can be further assistance with anything else.

Sincerely,

Jon Gann TED Systems, LLC

Res. 19637

Overhead Door Company of Kansas City

A Division of D.H.Pace Co. Inc.

1901 E 119th Street

Olathe, KS 66061

cell phone: 816-215-2661

email: scott.davis@dhpace.com

The Genuine. The Original.



Proposal #: SD-6409

PROPOSAL SUBMITTED Jackson County	TO:		Date 8/31/2017	Attention Craig Mosher
STREET 415 East 12th Street			Job Name 2017 Door U	pgrades at 1315 Locust & Jail Bldg
City Kansas City	State MO	ZipCode	Job Location 1315 Locust	& Jail
Phone Number 816-456-7479	Fax Num cmosh	_{ber} er@jacksongov.org	Job Phone 816-456-747	9

FURNISH AND INSTALL:

Overhead Door proposes the below door upgrades for selected openings located in the 1315 & Jail area buildings.

#1 - 1315 1st Floor Lobby

- 1 3070 16ga Steel Door
- 1 3070 16ga Steel Door
- 6 Ball Bearing Hinges
- 2 VonDuprin 9927L Chex-it SVR Panic w/Delayed Egress (Non-Keyed on Lever Side)
- 1 Power Supply
- 2 LCN 4040xp
- * Reuse Frame

Furnish & Installed = \$10,729.00

#2 - 1315 Lobby Bottom Ramp

- 1 3070 14ga Steel Frame, 90 Min Rated
- 1 3070 16ga Steel Door, 90 Min Rated
- 3 Ball Bearing Hinges
- 1 VonDuprin 99L Panic (Keyed on Lever Side)
- 1 Rim Cylinder (keyed to Customers Key)
- 1 LCN 4040xp

Furnish & Installed = \$4,132.00

#3 - 1315 2nd Floor Lobby

- 1 VonDuprin 99L Chex-it w/Delay Alarm (Non-Keyed on Lever Side)
- 1 VonDuprin PS914 Power Supply

Furnish & Installed = \$3,585.00

#4 - 1315 2nd Floor Stairwell

- 1 3070 16ga Steel Door, 90 Min Rated, 4" x 25" Laminated Wire
- 1 4" x 25" Lite Kit
- 1 4" x 25" Laminated Wire
- 3 Ball Bearing Hinges
- 1 VonDuprin 99L Panic
- 1 LCN 4040xp
- 1 Smoke Seal
- * Reuse Frame

Furnish & Installed = \$3,997.00

______ #9 - Jail Compactor Exterior Exit 1 - 3071 16ga Steel Door 1 - Continuous Hinge 3 - Frame Hinge Filler Plates 1 - VonDuprin 99L-NL Panic w/Alarm Kit 1 - Rim Cylinder (keyed to Customers Key) 1 - LCN 4040xp Cush Closer 1 - Weatherseal 1 - Saddle Threshold Furnish & Installed = \$4,241.00 _______ #12 - Stairwell 3rd Floor #1 1 - 996L-NL Lever Trim 1 - 99L Alarm Kit 1 - Rim Cylinder (keyed to Customers Key) Furnish & Installed = \$1,643.00 _________ #13 - Jail 3rd Floor Stairwell 1 - 99L-NL 1 - 99L Alarm Kit 1 - Rim Cylinder (keyed to Customers Key) Furnish & Installed = \$1.643.00 _______ #16 - Jail Bottom Lobby Stairwell 4 1 - 99L-NL 1 - Rim Cylinder (keyed to Customers Key) Furnish & Installed = \$1,208.00 ______ #17 - Jail Sally Port Southwest Exit Door 1 - 3070 16 ga Steel Door 1 - Full Length Continuous Hinge 1 - 99L-NL 1 - 99L Alarm Kit 1 - Rim Cylinder (keyed to Customers Key) 1 - Weatherseal 1 - Saddle Threshold Furnish & Installed = \$4,241.00 __________ #20 - Civil Process by 2nd Floor Elevator, 1 - 3070 16ga Steel Door, 90 Min Rated 3 - Ball Bearing Hinges 1 - VonDuprin 99L-NL Panic 1 - Rim Cylinder (keyed to Customers Key) 1 - LCN 4040xp Furnish & Installed = \$3,880.00 ________________________________ _______ Summary Total = \$39,299.00 Price Proposal for Jackson County by Overhead Door Company of Kansas City Proposal Number SD - 6409 Job Name: 2017 Door Upgrades at 1315 Locust & Jail Bldg

- * This job has been quoted being installed on Monday/Friday between the hours of 7am 5pm.
- Door openings with the Delayed Egress will require bringing 110volt electrical to above the opening.
- * Customer will have the opening(s) area ready for OHD to perform the installation.
- * Customer will be responsible for all building permits and fees if required.
- * Customer is responsible for all paint and stain work if required.
- * Customer to provide electrical power to a junction box located within 1 2 feet of the OHD specified location.
- * OHD to connect 110volt electrical power from the junction box that is located within 1 2 ft. of the OHD power supply.
- * If there are openings that are being questioned if it is a fire rated opening or not, it will be the responsibility of the customer to gather this information and provide to OHD/DH Pace.
- * This quote includes taking down existing job related material and hauling off.
- * If inadequate, structural damage or hidden internal issues are encountered during installation an additional cost could occur.
- * The above proposal is priced with NO state and local taxes included.
- * This proposal is contingent upon acceptance of a mutually agreed upon contract.
- * Please sign and return the proposal to me by email to scott.davis@ohdkc.com so we may proceed with your order

We hereby propose to complete in accordance with above specification, for the sum of:

See above for pricing!

Signature		
	Please call me at your convenience if I may be	Direct Dial: 816-215-2661
	of further assistance Scott Davis	

TERMS AND CONDITIONS

Payment to be made as follows:

* 50% Down and balance due at completion or 30 Days Net for customers with

approved credit.

Prices subject to change if not accepted in

30 days.

The proposal described herein, including all price(s) quoted, is made conditionally upon Buyer's continued credit status and must be accepted by Buyer as made by Seller. To accept this Proposal, Buyer must date, sign and return the original copy hereof to Seller within 30 days after the date hereof. Unless expressly disclosed and stated, the amount of any sales and use tax is not included in this proposal. Buyer acknowledges and agrees that each and all of the terms and conditions on the reverse side hereof are a part of this Proposal and that upon Buyer's acceptance of this Proposal shall constitute a valid and binding contract between the parties and all prior proposals, discussions and agreements respecting the subject matter hereof are canceled.

ACCEPTANCE: Terms, Price, and specifications or	n all pages of this proposal are hereby	y accepted and the work authorized.
Purchaser:		-
Signature	Title	Date of Acceptance

Ted Systems Overhead Door Quote Quote \$6,640.04 \$39,299.00

\$45,939.04