Completed by County Counselor's Office

Action Requested:	Ordinance	Res.Ord No.:	5743
Sponsor(s):	DaRon McGee	Legislature Meeting Date:	5/9/2023

Introduction

Action Items: ['Authorize', 'Appropriate']

Project/Title:

Authorizing the County Executive to amend an existing agreement with JE Dunn + Axiom for a designbuild contract for a new Jackson County Detention Center to establish a guaranteed maximum price (GMP) for the project at \$301,162,067; authorizing the County Executive a second amendment to the existing agreement with JE Dunn + Axiom for Component #1 in the amount of \$31,506,535; authorizing a third amendment to the same agreement for Component #2a in the amount of \$67,511,444; establishing Fund No 024 New Detention Center Fund in the financial records of the County; estimating \$77,017,979 in bond proceeds for the project; appropriating \$22 million from the Undesignated Fund Balance of the General Fund; and appropriating \$99,017,979 in the New Detention Center Fund for the first two components of the project; and declares the intent of Jackson County to reimburse itself from bond proceeds.

Request Summary

This ordinance requests the Legislature approve a contract amendment that establishes the guaranteed maximum price of \$301,162,067 for the design and construction by JE Dunn + Axiom of a new 1000 bed Jackson County Detention Center to be located on county-owned land at 7000 E US 40 Highway in Kansas City, Missouri. This ordinance further authorizes the County Executive to sign two additional amendments to begin construction of various components of the project. Component #1 details work that pertains to continuation of design documents, site demolition, site development and earthwork that is directly tied to the GMP submission. Component Package #1 totals \$31,506,535 With this Component Package, the project will move forward with early earthwork and some site infrastructure items to allow the building pad to become ready for additional scopes of work.

Component Package #2a details work that pertains to engineering, detailing, mockups, and early procurement of long lead material that are directly tied to the GMP submission. Component Package 2A totals \$67,511,444 and will allow the project to move forward with additional design and trade partner on-boarding to help mitigate cost escalation moving forward.

This ordinance also appropriates \$22 million in available General Fund reserves and anticipates the sale of \$77,017,979 in bond proceeds to provide sufficient funds to fully encumber Component #1 and Component #2a that have been authorized for sale by Ordinance #5732. This ordinance also establishes Fund No. 024 Jackson County Detention Center Poject Fund in the financial records of the County, and declares the intent of the County to reimburse itself from future bond proceeds that will be issued pursuant to Ordinance #5732.

Request for Legislative Action

Contact Information					
Department:	County Executive Office	Submitted Date:	5/3/2023		
Name:	Troy Schulte	Email:	TSchulte@jacksongov.org		
Title:	County Administrator	Phone:	816-881-1079		

Budget Information						
Amount authorized by th		\$99,017,979				
Amount previously authors	prized this fiscal year:			\$ 0		
Total amount authorized	after this legislative action	1:	\$99,017,979			
Is it transferring fund?			No			
Single Source Funding:						
Fund:	Department:	Line Item Account:	Amount:			
001 (General Fund)	9999 (*)	32810 (Undesignated Fund Balance)		\$22,000,000		
001 (General Fund)	9999 (*)	56105 (Operating Transfers Out)		\$22,000,000		
024 (Justice With Dignity Capital Project Fund)	9999 (*)	47070 (Inter Fund Transfers)		\$22,000,000		
024 (Justice With Dignity Capital Project Fund)	9999 (*)	48010 (Sale of Bond Proceeds)		\$77,017,979		
024 (Justice With Dignity Capital Project Fund)	9999 (*)	32810 (Undesignated Fund Balance)		\$99,017,979		
024 (Justice With Dignity Capital Project Fund)	1214 (Fac. Mgmt. New Detention Center)	58020 (Buildings & Improvements)		\$99,017,979		

Prior Legislation				
Prior Ordinances				
Ordinance:	Ordinance date:			
5732	April 17, 2023			
5621	April 25, 2022			
Prior Resolution				
Resolution:	Resolution date:			

Purchasing

Request for Legislative Action

Does this RLA include the purchase or lease of	Yes
supplies, materials, equipment or services?	
Chapter 10 Justification:	Formal Bid
Core 4 Tax Clearance Completed:	Yes
Certificate of Foreign Corporation Received:	Yes
Have all required attachments been included in	Yes
this RLA?	

Compliance					
Certificate of Compliance					
In Compliance					
Minority, Women and Ve	teran Owne	d Business Program			
Reviewed for Goals:					
MBE:	17.50%	Vendor committed goal			
WBE:	11.00%	Vendor committed goal			
VBE:	.50%	Vendor committed goal			
Prevailing Wage					
Construction projects over	r \$75000	['Separate bid']			

Fiscal	Fiscal Information						
•	Funds sufficient for this appropriation and/or transfer are available from the source indicated on the budget information tab.						

History

Submitted by County Executive Office requestor: Troy Schulte on 5/3/2023. Comments:

Approved by Department Approver Sylvya Stevenson on 5/3/2023 2:03:01 PM. Comments:

Approved by Purchasing Office Approver Barbara J. Casamento on 5/3/2023 2:08:12 PM. Comments:

Approved by Compliance Office Approver Jaime Guillen on 5/3/2023 3:16:06 PM. Comments:

Approved by Budget Office Approver Mark Lang on 5/3/2023 4:27:57 PM. Comments:

Approved by Executive Office Approver Sylvya Stevenson on 5/3/2023 8:50:38 PM. Comments:

Approved by Counselor's Office Approver Theresa E. Bullington on 5/4/2023 8:31:32 AM. Comments:

Supplemental Appropriation Request Jackson County, Missouri

Funds sufficient for this appropriation are available from the source indicated below.

Date:	May 3, 2023				Ord # eRLA ID #:	_5	5743 905
Org Co	ode/Description	Object	Code/Description	Fr	om	То	
001	General Fund						
9999		32810	Undesignated Fund Balance	\$	22,000,000	\$	-
9100	Operating Transfers	56105	Operating Transfers Out				22,000,000
				\$	22,000,000	\$	22,000,000
024	New Detention Center C/P Fund						
9999	<u> </u>	47070	Inter Fund Transfers	\$	22,000,000	\$	
9999	<u> </u>	48010	Bond Proceeds		77,017,979		
9999	<u> </u>	32810	Undesignated Fund Balance				99,017,979
				\$	99,017,979	\$	99,017,979
9999		32810	Undesignated Fund Balance	\$	99,017,979		
1214	Fac Mgmt - New Detention Center	58020	Buildings & Improvements				99,017,979
			·				
				\$	99,017,979	\$	99,017,979
APPR By Mark	OVED (Lang at 4:27 pm, May 03, 2023						

Budget Office

JE DUNN • AXIOM • DLR GROUP

DESIGN-BUILD TEAM

May 14th, 2023 Mr. Troy Schulte Jackson County, Missouri Kansas City, MO 64106

Re: Jackson County Detention Center Component Package 1

Dear Troy,

Having submitted our Guaranteed Maximum Price (GMP) under separate cover on March 14th, 2023, we are submitting the following for consideration of Component Package 1. This Component Package 1 details work that pertains to continuation of design documents, site demolition, site development and earthwork that is directly tied to our GMP submission. Component Package 1 totals to **\$31,506,535** (Thirty-One Million, Five Hundred Six Thousand, Five Hundred Thirty-Five Dollars).

With this Component Package the project will move forward with early earthwork and some site infrastructure items to allow the building pad to become ready for additional scopes of work. This Component Package does not include a complete foundation package; however, this will be presented in a forthcoming Component Package.

Upon receiving written approval of this Component Package JE Dunn + Axiom will forward the formal contract amendment for execution, obtain insurance, procure payment and performance bonds, begin issuing subcontracts to our trade partners, and begin onsite mobilization.

Sincerely,

Jeffer Jentin

Jeff Jenkins

Project Director, JE Dunn + Axiom

Cc: Vance McMillan, JE Dunn + Axiom Daniel Felder, JE Dunn + Axiom Brian Dietz, JE Dunn + Axiom Paul Neidlein, JE Dunn + Axiom Rob Cleavinger, JE Dunn + Axiom Tom Bartelli, JE Dunn + Axiom Nick Tuggle, JE Dunn + Axiom Martin Berglund, DLR Group Dan Wehmueller, JCDC Partners Dan Musser, JCDC Partners Rick Davidson, JCDC Partners Cameron Glass, JCDC Partners Babette Macy, JCDC Partners

JE DUNN • AXIOM • DLR GROUP

DESIGN-BUILD TEAM

Jackson County, Missouri

County Executive (Signature)

County Counselor (*Signature*)

(Printed Name)

(Printed Name)

Clerk of the County Legislature (Signature)

(Printed Name)

Component Package 1 Funding	Escalation Mitigation Strategy	Trade	Partner ROM
Kissick Construction	Lump Sum (See attached for additional narrative)	\$	10,118,488
Design Contingency		\$	-
Construction Contingency		\$	-
Escalation Allowance		\$	-
Owner Contingency		\$	-
Design		\$	11,081,596
GC's		\$	1,552,419
Permits, Insurance		\$	8,090,899
Fee		\$	663,133
Total		\$	31,506,535

*Note - Component Package 1 does not include a complete foundation package. This package will be brought forward and introduced in a future Component Package 2B.

*Note - Some numbers above are not all-inclusive of the full GMP pricing included in Exhibit 1 of the GMP.

Component Package 1 Funding	Escalation Mitigation Strategy Kissick Construction (Lump-Sum) is responsible for the Earthwork Scope of Work and their Component Packag
	1 funding includes the entirety of their scope of work noted below:
	Erosion Control: \$424,927 Site Demolition: \$1,025,000
	Wick Drain Installation: \$4,070,561 Earthwork (Early footings/foundations prep included): \$4,598,000
Kissick Construction	
Component Package 2A Funding Reference	
	Enterprise Precast (Lump-Sum) contract amount of \$17,674,402 includes the furnishing the architectural and structural precast, hollow-core and solid core roof members for the project. Scope of work includes project management, shop drawings/engineering, BIM coordination, materials (i.e. reinforcing steel, concrete, and
	conduit). This amount has been included in the funding of Component Package 2A.
Enterprise Precast	
Flynn Midwest	Flynn Midwest (Lump-Sum) is responsible for the roofing/sheet metal scope of work. Component package 2A funding includes the cost of \$5,955,715 in materials that would be stored in an insured warehouse in Kansas City. This is to help mitigate approx. \$1M in escalation. Materials to be purchased are singly ply TPO membrance, fasteners, accessories, insulation, etc. Excludes labor that will be added in a future component package.
	Midland Marble and Granite (Lump-Sum) is responsible for the tile scope of work in the amount of \$357,198. Their scope of work is included with Component Package 2A - Funding to capitalize on their Veteran Owned
At dead Markin and Creater	Business status, which greatly helps achieve the teams goals for VBE participation.
Midland Marble and Granite	CML Security's (Lump Sum) Component Declare 24 - Funding amount is appropriated for billings offer official
	CML Security's (Lump-Sum) Component Package 2A - Funding amount is appropriated for billings after official award, CML would bill from Notice-to-Proceed until November for preconstruction services, project management, engineering services, and submittal development. CML would prepare to bill for \$2.7MM on Development and doors as a result of preconstruction efforts that would be needed by Q1 of 2024.
CML Security (DEC)	
	The Cornerstone/Axiom Detention, JV (Lump-Sum) is responsible for the pre-fabricated cell module scope of
	work. Component Package 2A Funding includes the following definable features of work: Shop Drawings/Engineering: \$730,000
	Cornerstone General Conditions (Project management/temporary offices): \$565,000
	Pre-Fab Site Setup/Equipment Mobilization: \$1,200,000
	- Includes making pre-fab site ready for cell module production (i.e. working slabs)
	Onsite Mockup: \$300,000
	- For product quality review/approval
	Mold fabrication, setup and begin cell module production: \$4,860,000
	Interior Fitout/Finish Materials Procurement: \$1,870,000
	 Materials include, detention hollow metal doors/frames, detention furniture, security fixtures (lights and plumbing), epoxy paint, etc.
Cornerstone/Axiom Detention (Modular Cells)	plumbing, epoxy paint, etc.
	American Fire Protection (GMP) is responsible for the Fire Protection scope of work and to lock in pricing and
	manage escalation American Fire Proteciton plans to procure/issue PO's for the following by the end of 2023
	witin the Component Package 2A funding:
	14 Wet Systems
	1 pre-action system
	2 clean agent
	3100' of Feed Main piping
	500' of Piping into the blocks 6850' of main piping within the cell blocks
	2672 heads within the cell/day-use areas.
	1851 heads in Hallways, Mechanical, BOH, Support, Court, facility areas
American Fire Protection	2500' of main piping in Hallways, Mechanical, BOH, Support, Court, facility areas
	US Engineering (GMP) is responsible for the Mechanical (HVAC/Plumbing) Scope of Work. Their component
	package 2A funding includes the following definable features of work:
	USE General Conditions (Project management/temporary offices): \$548,559
	Shop Drawings/Detailing/UG and Precast Module BIM Coordination: \$1,509,029 Fee: \$538,888, Permit: \$182,000 UG Piping: \$3,501,571 Drains and Piping: \$425,654
	Precast Material (Security Bars):\$183,887
	Mock-up for Precast Module/Seismic Planning: \$71,162
	Temperature Controls (Subcontractor detailing/shop drawings): \$100,000
	Long Lead Central Plant Equipment (Chillers, Boilers, Pumps): \$1,225,000
	Plumbing Equipment: \$615,000 Security Plumbing Fixtures (non-modular locations): \$1,200,000
JS Engineering	Long Lead Smoke Exhaust Fans and Louvers: \$1,900,000
	Mark One Electric (GMP) is responsible for the Electrical Scope of Work and their Component Package 2A
	funding includes \$683,604 of labor per month for 3 months which includes detailing/shop drawings, UG
	coordination, BIM Coordination/modeling and also procurement of long lead equipment noted below. Early Procurement Quote: \$7,328,626
	- Equipment slated for early procurement includes: Switchgear, paralleling gear, lights, lighting controls,
	emergency generators, UPS, Fire Alarm, wire/conduit, etc.

*Note - some numbers above are not all-inclusive of the full GMP pricing included in Exhibit 1 of the GMP.

JE DUNN • AXIOM • DLR GROUP

DESIGN-BUILD TEAM

May 14th, 2023 Mr. Troy Schulte Jackson County, Missouri Kansas City, MO 64106

Re: Jackson County Detention Center Component Package 2A

Dear Troy,

Having submitted our Guaranteed Maximum Price (GMP) under separate cover on March 14th, 2023, we are submitting the following for consideration of Component Package 2A. This Component Package 2A details work that pertains to engineering, detailing, mockups, and early procurement of long lead material that are directly tied to our GMP submission. Component Package 2A totals to **\$67,511,444** (Sixty-Seven Million, Five Hundred Eleven Thousand, Four Hundred Forty-Four Dollars).

With this Component Package the project will move forward with additional design and trade partner on boarding to help mitigate escalation moving forward. Subsequently the project schedule and budget are based off Component Package 1 and 2A being approved simultaneous. It this does not occur there will be a schedule and cost impact incurred by the project.

Upon receiving written approval of this Component Package JE Dunn + Axiom will forward the formal contract amendment for execution, obtain insurance, procure payment and performance bonds, begin issuing subcontracts to our trade partners, and begin onsite mobilization.

Sincerely,

fer Jentin

Jeff Jenkins

Project Director, JE Dunn + Axiom

Cc: Vance McMillan, JE Dunn + Axiom Daniel Felder, JE Dunn + Axiom Brian Dietz, JE Dunn + Axiom Paul Neidlein, JE Dunn + Axiom Rob Cleavinger, JE Dunn + Axiom Tom Bartelli, JE Dunn + Axiom Nick Tuggle, JE Dunn + Axiom Martin Berglund, DLR Group Dan Wehmueller, JCDC Partners Dan Musser, JCDC Partners Rick Davidson, JCDC Partners Cameron Glass, JCDC Partners Babette Macy, JCDC Partners

JE DUNN • AXIOM • DLR GROUP

DESIGN-BUILD TEAM

Jackson County, Missouri

County Executive (Signature)

County Counselor (*Signature*)

(Printed Name)

(Printed Name)

Clerk of the County Legislature (Signature)

(Printed Name)

Component Package 2A Funding	Escalation Mitigation Strategy	Trad	e Partner ROM
Enterprise Precast	Lump Sum (See attached for additional narrative)	\$	17,674,402
Flynn Midwest	Lump Sum (See attached for additional narrative)	\$	5,955,715
Midland Marble and Granite	Lump Sum (See attached for additional narrative)	\$	357,198
CML Security (DEC)	Lump Sum (See attached for additional narrative)	\$	2,860,000
Cornerstone/Axiom Detention (Modular Cells)	Lump Sum (See attached for additional narrative)	\$	9,525,000
American Fire Protection	GMP (See attached for additional narrative)	\$	3,097,297
US Engineering	GMP (See attached for additional narrative)	\$	11,514,962
Mark One Electric	GMP (See attached for additional narrative)	\$	9,379,438
Cornerstone Detention (SEC)	Lump Sum (See attached for additional narrative)	\$	2,400,000
Kissick Construction	Lump Sum (See attached for additional narrative)	\$	-
Design Contingency		\$	-
Construction Contingency		\$	-
Escalation Allowance		\$	-
Owner Contingency		\$	-
Design		\$	-
GC's		\$	3,326,486
Permits, Insurance		\$	-
Fee		\$	1,420,946
Total		\$	67,511,444

*Note - Some numbers above are not all-inclusive of the full GMP pricing included in Exhibit 1 of the GMP.

*Note - The balance of Component Package 2 shell and core package of the project will be delivered as Component Package 2C.

Common ant Declares 1 Funding Poforo	nce Only Dellars not include in CD2A Excelsion Mitigation Statemer
Component Package 1 Funding Refere	Ince Only Dollars not include in CP2A Escalation Mitigation Strategy Kissick Construction (Lump-Sum) is responsible for the Earthwork Scope of Work and their Component Package 1 funding includes the entirety of their scope of work noted below: Erosion Control: \$424,927 Site Demolition: \$1,025,000
	Wick Drain Installation: \$4,070,561 Earthwork (Early footings/foundations prep included): \$4,598,000
Kissick Construction Component Package 2A Funding	Escalation Mitigation Strategy
Enterprise Precast	Enterprise Precast (Lump-Sum) contract amount of \$17,674,402 includes the furnishing the architectural and structural precast, hollow-core and solid core roof members for the project. Scope of work includes project management, shop drawings/engineering, BIM coordination, materials (i.e. reinforcing steel, concrete, and conduit). This amount has been included in the funding of Component Package 2A.
	Flynn Midwest (Lump-Sum) is responsible for the roofing/sheet metal scope of work. Component package 2A funding includes the cost of \$5,955,715 in materials that would be stored in an insured warehouse in Kansas City. This is to help mitigate approx. \$1M in escalation. Materials to be purchased are singly ply TPO membrance, fasteners, accessories, insulation, etc. Excludes labor that will be added in a future component package.
Flynn Midwest	Midland Marble and Granite (Lump-Sum) is responsible for the tile scope of work in the amount of \$357,198.
	Their scope of work is included with Component Package 2A - Funding to capitalize on their Veteran Owned Business status, which greatly helps achieve the teams goals for VBE participation.
Midland Marble and Granite	
	CML Security's (Lump-Sum) Component Package 2A - Funding amount is appropriated for billings after official award, CML would bill from Notice-to-Proceed until November for preconstruction services, project management, engineering services, and submittal development. CML would prepare to bill for \$2.7MM on Dec 2023 for detention hollow metal frames and doors as a result of preconstruction efforts that would be needed by Q1 of 2024.
CML Security (DEC)	The Cornerctone (Axiem Detention, 11/ (Lump Sum) is responsible for the are fabricated call module scene of
	The Cornerstone/Axiom Detention, JV (Lump-Sum) is responsible for the pre-fabricated cell module scope of work. Component Package 2A Funding includes the following definable features of work: Shop Drawings/Engineering: \$730,000 Cornerstone General Conditions (Project management/temporary offices): \$565,000 Pre-Fab Site Setup/Equipment Mobilization: \$1,200,000 - Includes making pre-fab site ready for cell module production (i.e. working slabs) Onsite Mockup: \$300,000 - For product quality review/approval Mold fabrication, setup and begin cell module production: \$4,860,000 Interior Fitout/Finish Materials Procurement: \$1,870,000 - Materials include, detention hollow metal doors/frames, detention furniture, security fixtures (lights and plumbing) aconus paint etc.
Cornerstone/Axiom Detention (Modular Cells)	plumbing), epoxy paint, etc.
	American Fire Protection (GMP) is responsible for the Fire Protection scope of work and to lock in pricing and manage escalation American Fire Proteciton plans to procure/issue PO's for the following by the end of 2023 witin the Component Package 2A funding: 14 Wet Systems 1 pre-action system 2 clean agent 3100' of Feed Main piping 500' of Piping into the blocks 6850' of main piping within the cell blocks 2672 heads within the cell/day-use areas. 1851 heads in Hallways, Mechanical, BOH, Support, Court, facility areas
American Fire Protection	2500' of main piping in Hallways, Mechanical, BOH, Support, Court, facility areas US Engineering (GMP) is responsible for the Mechanical (HVAC/Plumbing) Scope of Work. Their component package 2A funding includes the following definable features of work: USE General Conditions (Project management/temporary offices): \$548,559 Shop Drawings/Detailing/UG and Precast Module BIM Coordination: \$1,509,029 Fee: \$538,888, Permit: \$182,000 UG Piping: \$3,501,571 Drains and Piping: \$425,654 Precast Material (Security Bars):\$183,887 Mock-up for Precast Module/Seismic Planning: \$71,162 Temperature Controls (Subcontractor detailing/shop drawings): \$100,000 Long Lead Central Plant Equipment (Chillers, Boilers, Pumps): \$1,225,000 Plumbing Equipment: \$615,000 Security Plumbing Fixtures (non-modular locations): \$1,200,000
US Engineering	Long Lead Smoke Exhaust Fans and Louvers: \$1,900,000 Mark One Electric (GMP) is responsible for the Electrical Scope of Work and their Component Package 2A funding includes \$683,604 of labor per month for 3 months which includes detailing/shop drawings, UG coordination, BIM Coordination/modeling and also procurement of long lead equipment noted below. Early Procurement Quote: \$7,328,626 - Equipment slated for early procurement includes: Switchgear, paralleling gear, lights, lighting controls,
	emergency generators, UPS, Fire Alarm, wire/conduit, etc.
Mark One Electric	ve of the full GMP pricing included in Exhibit 1 of the GMP.

*Note - some numbers above are not all-inclusive of the full GMP pricing included in Exhibit 1 of the GMP.

JE DUNN • AXIOM • DLR GROUP DESIGN-BUILD TEAM

March 14th, 2023

Mr. Troy Schulte Jackson County, Missouri 415 E 12th Street Kansas City, MO 64106

Re: Jackson County Detention Center Guaranteed Maximum Price (GMP)

Dear Troy,

Please see the attached updated GMP proposal, items of note that have been added/changed are Exhibit 3 Item 9 converting housing units into dorms savings amount and Exhibit 7 GMP Clarification items 12-15.

We are pleased to tell Jackson County we have completed Interval 1 - Preconstruction and Interval 2 -Component Package 1 that resulted in Conceptual and Schematic Design documents. This has allowed us to tap the market and subsequently secure approximately 60% of the project GMP. In addition, due to the hard work of Jackson County, JCDC Partners and our team we have completed an exhaustive Value Engineering process that has concluded with a GMP totaling **\$301,162,067 (Three Hundred and One Million, One Hundred Sixty-Two Thousand, Sixty-Seven Dollars)** that includes 1,000 beds and the recommended changes included (Option #3). As communicated previously and due to unprecedented times, JE Dunn + Axiom believes it to be necessary to combine portions of the three (3) component packages together and release trade partners early to combat unrealized escalation as defined in section 3.1.6.3 of the Design-Build Agreement. That breakout is included in this GMP deliverable along with other contractual GMP deliverables.

The following supporting documents have been reviewed by JCDC, the Owner's Representative, and are attached for your approval.

- Exhibit 1 (3.2.2.4.3.2) GMP for Component Packages 1 (12 pages)
- Exhibit 2 List of Drawings/Contract Documents (8 pages)
- Exhibit 3 Approved Value Engineering Path (1 page)
- Exhibit 4 (3.2.2.4.3.1) Master Schedule (5 pages)
- Exhibit 5 Sequence Map (1 page)
- Exhibit 6 Logistics Plan (1 page)
- Exhibit 7 GMP Clarifications (10 pages)
- Exhibit 8 (3.2.2.4) Includes Deviations from Design Criteria Package Criteria Modification Log (11 pages)
- Exhibit 9 (3.2.2.2.4.4) Workforce Plan (1 page)
- Exhibit 10 (3.2.2.4.6) Contractor Utilization Plan/MWBE Strategy (7 pages)
- Exhibit 11 JCDC Systems Matrix (5 pages)
- Exhibit 12 HVAC Lifecycle Analysis (26 pages)

JE DUNN • AXIOM • DLR GROUP DESIGN-BUILD TEAM

In order to hold trade partner (subcontractor) pricing reflected in this GMP proposal, Jackson County approval is needed no later than April 17th, 2023.

Upon receiving written approval of this GMP proposal JE Dunn + Axiom will forward the formal contract amendment for execution, obtaining insurance, procure payment and performance bonds, begin issuing subcontracts to our trade partners, and begin onsite mobilization.

Sincerely,

Jeffer Jentin

Jeff Jenkins Project Director, JE Dunn + Axiom

Cc: Vance McMillan, JE Dunn + Axiom Daniel Felder, JE Dunn + Axiom Brian Dietz, JE Dunn + Axiom Paul Neidlein, JE Dunn + Axiom Rob Cleavinger, JE Dunn + Axiom Tom Bartelli, JE Dunn + Axiom Nick Tuggle, JE Dunn + Axiom Martin Berglund, DLR Group Dan Wehmueller, JCDC Partners Dan Musser, JCDC Partners Rick Davidson, JCDC Partners Cameron Glass, JCDC Partners Babette Macy, JCDC Partners

Jackson County, Missouri

County Executive (Signature)

County Counselor (*Signature*)

(Printed Name)

(Printed Name)

Clerk of the County Legislature (*Signature*)

(Printed Name)

Jackson County Detention Center Kansas City, Missouri March 3, 2023

SD 12

Construction Cost Summary Option #3 Incorporated (Total of 1,000 Beds)

Description	Quantity	Cost	Unit Cost
Design	398,619 NSF	19,540,695	49.02
Mass Excavation-Early Site Fill	398,619 NSF	11,253,283	28.23
Sitework	41 Acres +/-	8,480,988	207,528
Jail Building	398,619 SF	251,829,673	631.76
LEED Premium Allowance	398,619 NSF	Excluded	0.00
FF&E Allowance	398,619 NSF	Excluded	0.00
Construction Subtotal	398,619 SF	291,104,639	\$730.28
Design Contingency		2,911,046	7.30
Construction Contingency		3,517,372	8.82
Escalation Allowance		2,487,005	6.24
Owner Contingency		1,142,005	2.86
Total Construction Cost	398,619 SF	\$301,162,067	\$755.51

J:\DesignPhaseServices\01Precon\KC\05Correctional\2021\Jackson County Jail\04-Estimate\12SD-GMP2\Post Owner Review with VE 2023.03.01\2023.03.02_Jackson County GMP2-Post Owner Rev with VE-ContingencyR1-Present

Powered by *LENS aim*[™]

Jackson County Detention Center Kansas City, Missouri March 3, 2023 SD 12



Design 398,619 SF

Item	Description	Unit	Quantity	Unit Price	Cost	Cost/SF	Note
01 00 00 Ge 01 15 00 De	eneral Conditions esign	LS	1	17,570,187	1,016,116 17,570,187		
	Subtotal Permits and Insurance Fee				18,586,303 543,110 411,282	46.63	
	Total				\$19,540,695	\$49.02	

Jackson County Detention Center Kansas City, Missouri March 3, 2023 SD 12

Mass Excavation-Early Site Fill 398,619 SF

ltem	Description	Unit	TP	Esc	PH	Quantity	Unit Price	Cost	Cost/SF	Note
01 00 00 G	eneral Conditions							585,171		
31 20 00 Si	ubc-Earthwork/Wick Drains	LS	V	Е	mex	1	10,118,488	10,118,488		
	Subtotal							10,703,659	26.85	
	Permits and Insurance							312,771		
	Fee							236,853		
	Total							\$11,253,283	\$28.23	



Jackson County Detention Center Kansas City, Missouri March 3, 2023 SD 12

Sitework

Item	Description	Cost
1	General Conditions	441,011
2	Excavation and Grading	112,340
3	Asphalt Paving	1,690,448
4	Concrete Work	2,113,094
5	Site Structures	0
6	Fencing	452,000
7	Specialty Paving	47,178
8	Signage and Striping	52,427
9	Site Specialties	18,492
10	Site Utilities	2,432,041
11	Storm Drainage Systems	0
12	Fire Protection	0
13	Landscaping and Irrigation	707,734
14	Electrical	0
	Subtotal	8,066,766
	Permits and Insurance	235,719
	Fee	178,503
	Total	\$8,480,988



Site

Item	Description	Unit	TP	Esc	Ph	Quantity	Price	Amount	QuantF Note
2	Excavation and Grading								
31 20 00	Temporary Erosion Control	AC			fdn	40.87	1,644	67,183	
01 10 00	Temporary Roads and Parking	SF			fdn	27,023	0.72	19,534	6" Thick
01 10 00	6' Temp Fencing - Sand Bags	LF			fdn	2,400	10.68	25,624	2 EA Gates
						,			
	Total							112,340	
3	Asphalt Paving								
32 13 00	Subc Asphalt	LS	В		fin	1	1,690,448	1,690,448	
	•		_				.,,		
	Total							1,690,448	
4	Concrete Work								
32 13 00	24"Ø CameraPole Bases	EA			fin	6	1,017	6,101	
32 13 00	Subc- Site Concrete	LS	Т	Е	fin	1	1,962,345	1,962,345	
32 13 00	Misc Site Concrete	LS			fin	1	3,125	3,125	
01 10 00	Site Layout and Misc Cleanup	DA			fin	92	1,543	141,524	
	Total							2,113,094	
5	Site Structures Subc-Concrete Retaining Walls	SF	Т		fin	2,681	0.00	0	
32 32 00	-	ЪГ	I	Е	1111	2,001	0.00	0	
	Total							0	
6	Fencing								
32 31 00	Subc Fence	LS	В		fin	1	452,000	452.000 U	se 10% annually
							. ,		· ,
	Total							452,000	
7	Specialty Paving	05			<i>C</i>	0.000	04.44	17,170	
32 14 00	Limestone Pavers, 1"	SF			fin	2,200	21.44	47,178	
	Total							47,178	
8	Signage and Striping								
10 10 00	Monument Sign	LS			fin	1	40,000	40,000	
10 14 00	Misc Signage	EA			fin	44	280.22	12,427	
10 14 00							200.22		
	Total							52,427	
9	Site Specialties								
32 33 00	Site Furniture Allowance	LS			fin	1	10,000	10,000	
10 75 00	Flagpoles	EA			fin	2	4,246	8,492	
	Total							18,492	
	Iotai							10,492	
10	Site Utilities								
33 00 00	Auger Monster-Pit	LS	_		fdn	2	75,000	150,000	
33 00 00	Subc Site Utility	LS	В	Α	fdn	1	2,282,041	2,282,041	
	Total							2,432,041	
11	Storm Drainage Systems								
11	Storm Drainage Systems							0	

Powered by *LENS aim*[™]

Site

ltem	Description	Unit	TP	Esc	Ph	Quantity	Price	Amount	QuantF	Note
12	Fire Protection									
	Tota	I						(
13	Landscaping and Irrigation									
32 90 00	Synth Turf-Courtyards	LS	В		fin	1	49,650	49,650		
32 90 00	Maint. Watering	MO	В		fin	3	3,500	10,500)	
32 90 00	Subc Landscape	LS	В		fin	1	647,584	647,584	4	
	Tota	I						707,734	-	
14	Electrical									
	Tota	l						()	

VV

Jackson County Detention Center Kansas City, Missouri March 3, 2023 SD 12

Jail Building 398,619 SF

Item	Description		Cost	Cost/SF
1	General Conditions		13,095,143	32.85
2	Demolition		0	0.00
3	Excavation		37,387	0.09
4	Structure		49,537,179	124.27
5	Enclosure		92,500	0.23
6	Rough Carpentry		0	0.00
7	Finish Carpentry		3,684,595	9.24
8	Roofing and Sheet Metal		9,460,033	23.73
9	Moisture Protection		3,753,160	9.42
10	Doors and Hardware		2,810,283	7.05
11	Glass and Glazing		1,635,969	4.10
12	Interior Partitions		15,526,029	38.95
13	Stone and Tile		365,057	0.92
14	Ceilings and Acoustic		0	0.00
15	Flooring		2,410,235	6.05
16	Painting		2,962,801	7.43
17	Specialties		1,274,736	3.20
18	Equipment and Furnishings		21,724,040	54.50
19	Special Construction		18,889,854	47.39
20	Elevators		298,500	0.75
21	Fire Protection		3,097,297	7.77
22	Plumbing		0	0.00
23	HVAC Systems		49,372,434	123.86
24	Electrical		39,502,764	99.10
	Subtotal		239,529,995	600.90
	Permits and Insurance		6,999,298	17.56
	Fee		5,300,380	13.30
	Total		\$251,829,673	\$631.76
	Skin/Floor Area Ratio	53%	Total Skin Cost, Contact Area	\$8.19 /SF
	Glass/Skin Area Ratio	4%	Skin Cost, Bldg Area	\$4.34 /SF

Powered by *LENS aim* ™

Item	Description	Unit	TP	Esc	Ph	Quantity	Price	Amount	QuantF Prod
2	Demolition								
	Total							0	\$0.00
3	Excavation								
31 23 00	Perim First Foundation Drains	LF			fdn	3,442	10.86	37,387	
	Total							37,387	\$0.09
4	Structure								
05 50 00	Interior Storefront Supports	LF			stru	118	170.41	20,109	
05 45 00	Operable Wall & Fold Part Spts	LF			stru	72	137.15	9,875	
05 50 00	Other Miscellaneous Steel	TN			stru	15	10,987	166,611	0.08 #/SF
07 95 00	Expansion Joint Covers Fireproofing	LF			stru	2,837	148.62	421,640	\$0.79/SF
07 80 00	Subc Fireproofing Light Gauge Structure	LS	В	Е	stru	1	318,000	318,000	
	General Items	~-							
01 10 00 03 32 00	Layout and Cleanup Weather Conditions Trade Partner Estimates	SF %			stru stru	404,367 2.00%	0.50 14,249,918	201,736 284,998	
03 31 00	Concrete Foundations Estimate	LS	Т	Е	fdn	1	14,249,918	14,249,918	
03 45 00	PC Matl Sub Est (Enterprise)	LS	V	Е	stru	1	17,674,402	17,674,402	
03 41 00	PC Erect Sub Est	LS	Т	Е	stru	1	6,477,249	6,477,249	
05 40 00	Steel StructSub Estimate	LS	В		stru	1	3,917,686	3,917,686	
05 12 00	Struct Misc Steel	LS	В	Е	stru	1	2,230,266	2,230,266	No
05 12 00							0 504 000	2 564 600	Nie
	Misc Steel Erection and Hoistin	LS	Т	Е	stru	1	3,564,689	3,564,689	No
05 45 00			Т	E	stru	1	3,564,689	49,537,179	NO \$122.51
05 45 00 05 50 00 5 01 10 00	Misc Steel Erection and Hoistin Total Enclosure Building Skin Review	LS	Т	E	encl	1	10,000	49,537,179	\$122.51
05 45 00 05 50 00 5	Misc Steel Erection and Hoistin Total Enclosure	LS	Т	E				49,537,179	\$122.51 20.00' Wide 15.00' Ta
05 45 00 05 50 00 5 01 10 00	Misc Steel Erection and Hoistin Total Enclosure Building Skin Review	LS	Т	E	encl	1	10,000	49,537,179	\$122.51
05 45 00 05 50 00 5 01 10 00	Misc Steel Erection and Hoistin Total Enclosure Building Skin Review Enclosure Mockup w/ Punch W Total Rough Carpentry	LS	Т	E	encl	1	10,000	49,537,179 10,000 82,500 92,500	\$122.51 20.00' Wide 15.00' Ta \$0.23
05 45 00 05 50 00 5 01 10 00 01 10 00	Misc Steel Erection and Hoistin Total Enclosure Building Skin Review Enclosure Mockup w/ Punch W Total	LS	Т	E	encl	1	10,000	49,537,179 10,000 82,500	\$122.51 20.00' Wide 15.00' Ta
05 45 00 05 50 00 5 01 10 00 01 10 00 6 7	Misc Steel Erection and Hoistin Total Enclosure Building Skin Review Enclosure Mockup w/ Punch W Total Rough Carpentry Total Finish Carpentry	LS SF	Т	E	encl encl	1 300	10,000 275.00	49,537,179 10,000 82,500 92,500 0	\$122.51 20.00' Wide 15.00' Ta \$0.23
05 45 00 05 50 00 5 01 10 00 01 10 00 6 7 06 20 00	Misc Steel Erection and Hoistin Total Enclosure Building Skin Review Enclosure Mockup w/ Punch W Total Rough Carpentry Total Finish Carpentry 6" Chair Rail, One Piece	LS SF LF			encl encl	1 300 221	10,000 275.00 15.00	49,537,179 10,000 82,500 92,500 0 3,315	\$122.51 20.00' Wide 15.00' Ta \$0.23
05 45 00 05 50 00 5 01 10 00 01 10 00 01 10 00 6 7 06 20 00 06 20 00	Misc Steel Erection and Hoistin Total Enclosure Building Skin Review Enclosure Mockup w/ Punch W Total Rough Carpentry Total Finish Carpentry 6" Chair Rail, One Piece Genl Carp Trade Pkg	LS SF LF LS	В	A	encl encl fin	1 300 221 1	10,000 275.00 15.00 2,139,575	49,537,179 49,537,179 10,000 82,500 92,500 92,500 0 3,315 2,139,575	\$122.51 20.00' Wide 15.00' Ta \$0.23
05 45 00 05 50 00 5 01 10 00 01 10 00 6 7 06 20 00	Misc Steel Erection and Hoistin Total Enclosure Building Skin Review Enclosure Mockup w/ Punch W Total Rough Carpentry Total Finish Carpentry 6" Chair Rail, One Piece	LS SF LF			encl encl	1 300 221	10,000 275.00 15.00	49,537,179 10,000 82,500 92,500 0 3,315	\$122.51 20.00' Wide 15.00' Ta \$0.23
05 45 00 05 50 00 5 01 10 00 01 10 00 01 10 00 6 7 06 20 00 06 20 00	Misc Steel Erection and Hoistin Total Enclosure Building Skin Review Enclosure Mockup w/ Punch W Total Rough Carpentry Total Finish Carpentry 6" Chair Rail, One Piece Genl Carp Trade Pkg	LS SF LF LS	В	A	encl encl fin	1 300 221 1	10,000 275.00 15.00 2,139,575	49,537,179 49,537,179 10,000 82,500 92,500 92,500 0 3,315 2,139,575	\$122.51 20.00' Wide 15.00' Ta \$0.23
05 45 00 05 50 00 5 01 10 00 01 10 00 01 10 00 6 7 06 20 00 06 20 00	Misc Steel Erection and Hoistin Total Enclosure Building Skin Review Enclosure Mockup w/ Punch W Total Rough Carpentry Total Finish Carpentry 6" Chair Rail, One Piece Genl Carp Trade Pkg Subc Millwork	LS SF LF LS	В	A	encl encl fin	1 300 221 1	10,000 275.00 15.00 2,139,575	49,537,179 10,000 82,500 92,500 0 3,315 2,139,575 1,541,705	\$122.51 20.00' Wide 15.00' Ta \$0.23 \$0.00
05 45 00 05 50 00 5 01 10 00 01 10 00 01 10 00 6 7 06 20 00 06 20 00 06 20 00	Misc Steel Erection and Hoistin Total Enclosure Building Skin Review Enclosure Mockup w/ Punch W Total Rough Carpentry Total 6" Chair Rail, One Piece Genl Carp Trade Pkg Subc Millwork Total	LS SF LF LS LS	В	AAA	encl encl fin	1 300 221 1	10,000 275.00 15.00 2,139,575 1,541,705 35.00	49,537,179 10,000 82,500 92,500 92,500 0 3,315 2,139,575 1,541,705 3,684,595 245,000	\$122.51 20.00' Wide 15.00' Ta \$0.23 \$0.00 \$9.11
05 45 00 05 50 00 5 01 10 00 01 10 00 01 10 00 6 7 06 20 00 06 20 00 06 20 00 8	Misc Steel Erection and Hoistin Total Enclosure Building Skin Review Enclosure Mockup w/ Punch W Total Rough Carpentry Total 6" Chair Rail, One Piece Genl Carp Trade Pkg Subc Millwork Total	LS SF LS LS LS	B B	AAA	encl encl fin fin	1 300 221 1 1	10,000 275.00 15.00 2,139,575 1,541,705	49,537,179 10,000 82,500 92,500 92,500 3,315 2,139,575 1,541,705 3,684,595	\$122.51 20.00' Wide 15.00' Ta \$0.23 \$0.00 \$9.11
05 45 00 05 50 00 5 01 10 00 01 10 00 01 10 00 06 20 00	Misc Steel Erection and Hoistin Total Enclosure Building Skin Review Enclosure Mockup w/ Punch W Total Rough Carpentry Total Finish Carpentry 6" Chair Rail, One Piece Genl Carp Trade Pkg Subc Millwork Total Roofing and Sheet Metal Roof Walkway Pads Misc Items	LS SF LF LS LS	B B V	A A E	encl encl fin fin fin encl encl	1 300 221 1 1 1 7,000 1	10,000 275.00 2,139,575 1,541,705 35.00 15,960	49,537,179 10,000 82,500 92,500 0 3,315 2,139,575 1,541,705 3,684,595 245,000 15,960	\$122.51 20.00' Wide 15.00' Ta \$0.23 \$0.00 \$9.11 15% Roof Carey Tread
05 45 00 05 50 00 5 01 10 00 01 10 00 01 10 00 6 6 7 06 20 00 06 20 00 06 20 00 06 20 00 06 20 00	Misc Steel Erection and Hoistin Total Enclosure Building Skin Review Enclosure Mockup w/ Punch W Total Rough Carpentry Total 6" Chair Rail, One Piece Genl Carp Trade Pkg Subc Millwork Total Roofing and Sheet Metal Roof Walkway Pads	LS SF LF LS LS	B B	AAA	encl encl fin fin fin encl	1 300 221 1 1 7,000	10,000 275.00 15.00 2,139,575 1,541,705 35.00	49,537,179 10,000 82,500 92,500 92,500 0 3,315 2,139,575 1,541,705 3,684,595 245,000	\$122.51 20.00' Wide 15.00' Ta \$0.23 \$0.00 \$9.11
05 45 00 05 50 00 5 01 10 00 01 10 00 01 10 00 6 0 6 0 6 20 00 06 20 00 00	Misc Steel Erection and Hoistin Total Enclosure Building Skin Review Enclosure Mockup w/ Punch W Total Rough Carpentry Total 6" Chair Rail, One Piece Genl Carp Trade Pkg Subc Millwork Total Roofing and Sheet Metal Roof Walkway Pads Misc Items Subc Roof (Flynn)	LS SF LF LS LS LS	B B V V	A A E E	encl encl fin fin fin fin encl encl encl	1 300 221 1 1 1 7,000 1 1	10,000 275.00 2,139,575 1,541,705 35.00 15,960 8,564,353	49,537,179 10,000 82,500 92,500 0 3,315 2,139,575 1,541,705 3,684,595 245,000 15,960 8,564,353	\$122.51 20.00' Wide 15.00' Ta \$0.23 \$0.00 \$9.11 15% Roof Carey Tread \$27.74
05 45 00 05 50 00 5 01 10 00 01 10 00 01 10 00 6 0 6 0 6 20 00 06 20 00 00	Misc Steel Erection and Hoistin Total Enclosure Building Skin Review Enclosure Mockup w/ Punch W Total Rough Carpentry Total Finish Carpentry 6" Chair Rail, One Piece Genl Carp Trade Pkg Subc Millwork Total Roofing and Sheet Metal Roof Walkway Pads Misc Items Subc Roof (Flynn) Subc Roof (Flynn) Subc Metal Panels	LS SF LF LS LS LS	B B V V	A A E E	encl encl fin fin fin fin encl encl encl	1 300 221 1 1 1 7,000 1 1	10,000 275.00 2,139,575 1,541,705 35.00 15,960 8,564,353	49,537,179 10,000 82,500 92,500 92,500 3,315 2,139,575 1,541,705 3,684,595 245,000 15,960 8,564,353 634,720	\$122.51 20.00' Wide 15.00' Ta \$0.23 \$0.00 \$9.11 15% Roof Carey Tread \$27.74 \$2.06
05 45 00 05 50 00 5 01 10 00 01 10 00 01 10 00 6 0 6 0 20 00 06 20 00 07 50 00	Misc Steel Erection and Hoistin Total Enclosure Building Skin Review Enclosure Mockup w/ Punch W Total Rough Carpentry Total Finish Carpentry 6" Chair Rail, One Piece Genl Carp Trade Pkg Subc Millwork Total Roofing and Sheet Metal Roof Walkway Pads Misc Items Subc Roof (Flynn) Subc Metal Panels Total	LS SF LF LS LS LS	B B V V	A A E E	encl encl fin fin fin fin encl encl encl	1 300 221 1 1 1 7,000 1 1	10,000 275.00 2,139,575 1,541,705 35.00 15,960 8,564,353	49,537,179 10,000 82,500 92,500 92,500 3,315 2,139,575 1,541,705 3,684,595 245,000 15,960 8,564,353 634,720	\$122.51 20.00' Wide 15.00' Ta \$0.23 \$0.00 \$9.11 15% Roof Carey Tread \$27.74 \$2.06

Item	Description	Unit	TP Esc	: Ph	Quantity	Price	Amount	QuantF Prod
	Total						3,753,160	\$9.28
10	Doors and Hardware							
08 30 00	Access Panels, 24"x24"	EA		fin	30	309.42	9,283	
08 30 00	Coiling Overhead Door	EA		fin	17	4,000	68,000	4.00' Wide 4.00' Tall
08 30 00	Elec Coiling Dr, Shutter or Grill	EA		fin	4	22,800	91,200	10.00' Wide 12.00' Tall
08 30 00	Elec Coiling Dr, Shutter or Grill	EA		fin	2	18,050	36,100	8.00' Wide 10.00' Tall
08 10 00	Subc Door Supply	LS	ΒА	fin	1	2,605,700	2,605,700 F	
	Total						2,810,283	\$6.95
	Total						2,010,200	\$0.00
11	Glass and Glazing	05		C	500	45.45	0.770	
08 40 10	Sheet Mirrors	SF		fin	568	15.45	8,776	3.00' Wide 4.00' Tall
08 40 10	Glaze Sidelites	SF	U	fin	3,374	25.00	84,351	14 SF 1/4" Glass
08 40 10	Prem. Fire Rating @ Glaze Sid	SF	U	fin	384	275.63	105,840	49 SF 1/4" Glass
08 40 10	Door Lites and Misc Glazing	EA	U	fin	454	195.00	88,481	75% Doors 2.50 SF
08 40 10	PremFire Rated Glass Borrow	EA	U	fin	96	180.00	17,325	1 HR Rated
01 10 00	Enclosure Curtainwall Mockup	SF	D 4	encl	60	30.00	1,800	6.00' Wide 6.00' Tall
08 40 00	Subc Glass	LS	ΒA	encl	1	1,329,396	1,329,396	No
	Total						1,635,969	\$4.05
12	Interior Partitions							
01 10 00	Layout and Cleanup	SF		fin	404,367	1.30	524,512	
01 10 00	Temp Conditioning Interiors	SF		fin	404,367	0.54	216,842	
04 20 10	Interior Masonry Sub Estimate	LS	ΤЕ	fin	1	9,867,836	9,867,836	
09 20 00	Subc Drywall	LS	ΒE	fin	1	4,916,839	4,916,839	
	Total						15,526,029	\$38.40
	Total						10,020,023	430.40
13	Stone and Tile	05		6	0.40	10.10	7.050	
09 30 00 09 30 00	Break Room Tile Sub Tile-MMG (V)	SF LS	В	fin fin	648 1	12.13 357,198	7,859 357,198 N	\$4.00 Mat'l 0% Area
00 00 00	Total	20	D			007,100		
	TOLAI						365,057	\$0.90
14	Ceilings and Acoustic							
	Total						0	\$0.00
15	Flooring							
09 67 00	Subc Spec/Res Ctgs	LS	В	fin	1	1,199,160	1,199,160	1% Area
06 20 00	Stain Grade Wood Base	LF		fin	1,285	30.99	39,824	12" High 2% Base
09 60 00	Stainless Steel Base	LF		fin	305	20.96	6,392	4" High 0% Base
09 60 00	Floor Protection	SF		fin	18,213	4.22	76,807	15% Area
09 60 00	Subc Cpt/Vnyl-Moisture Mitigat	SF	В	fin	79,006	6.00	474,036	27% Area
09 60 00	Subc Resinous-Moisture Mitiga	LS	ΒE	fin	1	61,756	61,756	22% Area
09 60 00	Subc Flooring	LS	В	fin	1	552,260	552,260	
	Total						2,410,235	\$5.96
46	Painting							
16 01 10 00	Painting Punchlist	SF		fin	404,367	0.49	200,147	160 SF/LH
01 74 23	Final Cleanup	LS	В	fin	404,307	471,194	471,194	80 SF/LH
01 74 23	Painting Sub Estimate	LS	BA	fin	1	2,291,460	2,291,460	
	Total	20				_,_01,100	2,962,801	\$7.33
	I OTAI						2,902,801	φ <i>ι</i> .33
17	Specialties			-				
10 14 00	Signage and Directories	LS		fin	1	12,000	12,000	
10 14 00	Bldg Ext Sign	EA		fin	1	30,000	30,000	
10 14 00	Door Signs owered by <i>LENS aim</i> ™	EA		fin	433	61.28	26,536	
-								

Control Planue-Control EA In Control Fill (2000)	Item	Description	Unit	TP E	sc Ph	Quantity	Price	Amount	QuantF	Prod
10 21 22 Cubicle Trackis LF fm 600 6.00 3.600 20 FFEA 10 22 00 Operable Walls SF B fm 792 121.02 95.846 72 LF 11.0 High 10 22 10 Wire Mesh Partitions, 10 Gaug SF B fm 14.55 38.34 29.836 10 20 00 FRP Handrais LF fm 821 38.34 29.836 28.148 29.844 40.149 10 20 00 SF SC Concer Guards EA fm 500 86.28 44.142 94.710 5460 Maril Concers Staff 547.16 16.3483 5500 Maril Concers Staff 10.160 54.84 10.160 54.84 10.160 54.84 10.160 54.84 10.160 54.84 10.160		· · · · · · · · · · · · · · · · · · ·							Quanti	
10 21 20 Cubicle Curtains EA fin 30 100.00 3.000 10 22 00 Openable Walls SF B fin 721 (2) 95,84 721 (2) 95,84 721 (2) 95,84 721 (2) 95,84 721 (2) 95,84 721 (2) 95,84 150 (16) (16) (2) 150 (16) (2) (2) 150 (16) (2) (2) 150 (16) (2) (2) 150 (16) (2) (2) 150 (16) (2) (2) 150 (16) (2) (2) 150 (16) (2) (2) 150 (16) (2) (2) 150 (16) (2) (2) 150 (16) (2) (2) 150 (16) (2) (2) 150 (16) (2) (2) 150 (16) (2) (2) (2) 150 (16) (2) (2) (2) (2) 150 (16) (2) (2) (2) (2) (2) 150 (16) (2) (2) (2) (2) (2) (2) (2) (2) (2) (2									2015/54	
10 22 00 Operable Wells SF B fin 7.92 121.02 96.948 72.12 1.10.0400, 10 20 00 FRP Handrais LF fin 8.21 38.34 29.834 10 20 00 FRP Wall Protection SF fin 4.105 6.8.6 28.448 28.438 10 20 00 FRP Handrais EA fin 500 88.28 44.142 24.448 26.0484 10 20 00 Spa.4 5.125 Lockers, 187.145 EA fin 32 574.16 18.343 2500 Meril Londvall/FG Se 10 5100 Spa.4 5.125 Lockers, 187.145 EA fin 24 274.16 6.5.00 200.0487 Locker with Bench, 187W; EA fin 24 274.16 6.500 200.0487 Locker with Bench 187W; EA fin 1 200.588 <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td>20 LI/LA</td> <td></td>									20 LI/LA	
10 22 10 Wire Mesh Partitions, 10 Gaug SF fin 1,455 38.30 55.728 15.0 High 2:14 Wower W 10 2000 FRP Wall Protection SF fin 4,105 6.86 28.433 28. Wall 4.0 High 10 2000 St SS Correr Cuards EA fin 52.0 High 2:14 Wower W 4.0 High 29. 333 10 4000 Detention Fire Extinguishers are EA fin 32. 574.16 5.483 5.500 Meri [.chnc Staff 10 5100 Spa# 11.09 Lockers, 12*HS X EA fin 20. 274.16 5.483 5.500 Meri [.chnc Staff 10 5100 Spa# 11.09 Lockers, 12*HS X EA fin 12.0 Z/74.16 5.850 500 Meri [.chnc Staff 10 2100 Itratition-Phonicle EA fin 17.000 17.000 \$1.000 Meri [.chnc Staff 10 2100 Itratition-Phonicle EA fin 1 28.15 Meri [.chnc Staff 10 2100 Itratition-Phonicle EA fin 1 28.12 Meri [.chnc Staff 10 2100 Staff Lockers W Bench, 18"W; EA fin 1 28.12 Meri [.chnc Staff 10 2100				D					7215	11.0' High
10 2000 FRP Handralis LF fm 6.21 38.34 29.836 10 2000 SP Wall Protection SF fm 4.105 6.66 28.143 28.936 10 2000 SP Wall Protection SF fm 4.105 6.66 28.143 28.944 1.15 10 5100 Spa.# 8.125 Lackers, 18*18* EA fm 32 S74.16 15.375 S450 Mart Clinic Staff 10 5100 Spa.# 9.102 Intel Cockers wit Banch, 18*W. EA fm 22 TA16 5.580 S200 Mart Laundy/Fd Se 10 2010 Th Parttion-Phenotic EA fm 1 200.588 200.588 11.162 3.126 Mart 11 200 Subc Dock LS B fm 1 249.913 48.913		•		Б						
10 26 00 FRP Wall Protection SF fm 4,105 6.86 28,149 _28,Vall .4,149 10 40 00 Detention Fire Extinguishers ar EA fm 500 88,28 44,142 10 40 00 Detention Fire Extinguishers ar EA fm 82 74,16 18,373 .450 Matri Clinic Staff 10 5100 Spa.# 1.109 Lockers, 12*18* EA fm 20 274,16 5,630 .500 Matri Locker Subtect 10 5100 Spa.# 1.09 Lockers, 12*18* EA fm 20 274,16 5,630 .500 Matri Locker Subtect 10 5100 Spa.# 1.09 Lockers, 12*18* EA fm 10 200 17,717,85 .500 Matri Locker Subtect 10 2100 Inmate changing stall EA fm 1 120,000 Matri Locker Subtect .53 fm 1 200,588 200,580 .200,186 .200,186 .200,186 .200,186 .200,186 .200,186 .200,186 .200,186 .200,186 .200,186 .200,186 .200,186 .200,186 .200,186 .200,186 .200,186 .200,186 .200,186 .200,186										
10 26 00 36° SS Corner Guards EA fm 500 88.28 44.142 10 61 00 Spa.# 8.12 Lockers, 18°.18°. EA fm 32 574.16 18,373 Sefo Mart[Lockers/Public] 10 61 00 Spa.# 8.12 Lockers, 18°.18°. EA fm 32 574.16 18,373 Sefo Mart[Lockers/Public] 10 61 00 Spa.# 9.102 Lockers/Public] EA fm 24 274.16 5,843 S200 Mart[Lockers/Public] Source Mart[Loundy/Fd Se 10 21 00 Tht Partition-Phenoice EA fm 24 2.75 5 552.016 32.12 Mart[Loundy/Fd Se 10 20 00 Subc Specialties/ Toilet Access LS fm 1 200.588 200.588 200.588 11 300 Subc Dock LS B fm 1 244.090 2.44.090 2.44.090 2.44.090 2.44.090 2.44.090 2.44.090 2.44.090 2.44.090 2.44.090 2.44.090 2.44.090 2.44.090 2.44.090 2.40.090 2.44.090 2.40.100 2.00.07.11 2.00.17.11 2.00.17.11 2.00.17.11 2.00.17.11 2.00.17.11 2.00.17.1									2% M/all	4 0' High
10 4 0.00 Detention File Extinguishers ar EA fin 82 1.155 94.710 Staff Metri Chino Staff 105100 Spa.# 1.190 Lockers, 12*18* EA fin 20 274.16 5.845 Metri Chino Staff 105100 Spa.# 1.090 Lockers, 12*18* EA fin 20 274.16 5.845 Metri Chino Staff 105100 Spa.# 1.090 Lockers, 12*18* EA fin 20 4 2.74,16 5.680 Staff Lockers will bench, 18*19* EA fin 20 4 2.74,16 5.680 Staff Lockers will bench, 18*19* EA fin 120 4 2.755 550.000 Metri Lockers field and the extince of the extinc									2 /0 VVali	4.0 TIIGH
10 51 00 Spail 8.125 Lockers. 18 X18'x EA fin 32 574.16 1,837 3550 Mmt Coline Start 10 50 00 Spail 9.10 20 Lockers 12 X18'x EA fin 24 274.16 5.483 5500 Mmt Loundry Fd Sc 500 Mmt Loundry Fd Sc 51 200 Mmt Loundry Fd Sc 50 7 mt 18 600 Rope Climb Ford EA fin 18 1,941 3,430 10,148 20.00 Wide 5,007 Tal 18 600 Rope Climb Pd Bgboard EA fin 18 3,141 45,550 10,148 20.00 Wide 5,007 Tal 18 600 Rope Climb Pd Bdb Rd Clambra Fd Fin 13 20 200 Lound Het Rd Sc 50 7 mt 18 8,569 10,148 20.00 Wide 5,007 Tal 18 8,569 10,148 20.00 Wide 5,007 Tal 18 8,569 10,148 20.00 Wide 5,007 Tal 18 8,00 Fd Fin 13 2,550 10,148 20.00 Wide 5,007 Tal 18 8,569 10,148 20.00 Wide 5,007 Tal 18 8,569 10,148 20.00 Wide 5,007 Tal 18 8,569 10,148 2,000 Wide 5,007 Tal 18 8,569 10,148 2,000 Wide 5,007 Tal 18 8,000 Fd Fin 13 20 20 Mmt Loch 7,550 1,166 7,550 1,166 7,550 1,166 7,550 1,166 7,550 1,166 7,550 1,166 7,550 1,166 7,550 1,166 7,550 1,166 7,550 1,166 7,550 1,166 7,550 1,166 7,550 1,166 7,550 1,166 7,550 1,166 7,550 1,166 7,550 1,166 7,550 1,166 7										
10 51 00 Spart 1.108 Lockers, 12 x18 'x EA fin 20 274.16 6.580 500 Marif_Lockey Public Intervet Inter		0							¢450 Matil	Clinic Staff
10 61 00 Spa.# 9.102 Inmate Stor. Cubb. EA fin 244 274.16 6,560 S20.00411 Laurday/Fd Sa 10 21 00 TH Partition-Phenolic EA fin 17 1,000 S1,225 Martill S21,255 Martill S21,255 Martill S21,255 Martill S1,225 Marti										
10 61 00 Staff Lockers w/ Bench, 18*V: Double Lockers w/ Bench, 18*V: Double Lockers w/ Bench, 18*V: Double Lockers w/ Bench, 18*V: Double Lockers w/ Bench, 18*V: Total Fin 17 1.000 17,000 17,000 17,000 17,000 17,000 17,000 17,000 17,000 17,000 17,000 17,000 11,02: 1,027,03 11,02: 1,027,03 11,02: 1,027,03 11,02: 1,027,03 11,02: 1,027,736 \$3,15 Total Total 11,100 Subc Dock LS B fin 1 48,913 48,913 Colspan="4">Colspan="4">Capacity 11,112 Subc Dock LS B E fin 1 24,090 2,440,990 2,440,990 2,440,990 2,440,990 2,440,990 2,440,990 2,440,990 2,440,990 2,440,990 2,440,990 2,440,990 2,440,990 2,441,451,730 11600 Chin Up Bar EA fin 18 2,111 45,730 11600 Chin Up Bar EA fin 13 4,5730 11600 2,443,990 2,443,990 2,443,930 14,845,730 11600 2,443,930 14,943,730 11600 11600 <td></td>										
10 21 00 The Partition-Phenolic EA fin 17 17,000 14,000 14,00,000 14,00,000 <td< td=""><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td>aunury/Fu Se</td></td<>										aunury/Fu Se
10 21 00 Inmate changing stall EA fin 6 1,859 200,588 200,598 200,588 200,598 201,593,512 21,724,040 </td <td></td>										
10 00 00 Subc Specialities/ Toilet Access LS fin 1 200,588 200,588 111 Total 1,274,736 \$3.15 111 Subc Dock LS B fin 1 48,913								· · · · · · · · · · · · · · · · · · ·		
Total 1.274.736 \$3.15 1113 00 Subc Dack LS B fin 1.274.736 \$3.15 1113 00 Subc Dack LS B fin 1.48.913 48.913 1111 000 Subc Food Equipment LS B fin 1.440.990 2.440.990 1111 000 Box Call Calls Capacity 1111 000 Box Call Calls Capacity 1111 000 Subc Laundry EA fin 18.40.990 2.440.990 2.440.990 1113 000 Subc Laundry EA 6 5.550 18.067.550 18.07.550 18.07.550 18.07.550 18.07.550 18.07.550 18.07.550 18.07.07 2.00.07 <th< td=""><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></th<>										
18 Equipment and Furnishings 111300 Subc Dock LS B fin 1 48,913	10 00 00	Subc Specialities/ Tollet Access	LO		1111	1	200,566	200,300		
111300 Šubč Dock LS B fin 1 48,913 48,913 Capacity 112173 Subc Laundry EA B fin 1 281,722 281,722 Capacity 114000 Subc Pood Equipment LS B E fin 1 2,440,990 2,440,990 Capacity 2,440,990 2,440,91,81,81 2,410,91,81,81 2,411,81 2,411,81 2,412,81 2,412,71		Total						1,274,736	\$3.15	
111300 Šubč Dock LS B fin 1 48,913 48,913 Capacity 112173 Subc Laundry EA B fin 1 281,722 281,722 Capacity 114000 Subc Pood Equipment LS B E fin 1 2,440,990 2,440,990 Capacity 2,440,990 2,440,91,81,81 2,410,91,81,81 2,411,81 2,411,81 2,412,81 2,412,71	18	Equipment and Furnishings								
11 21 3 Subc Laundry EA B fin 1 281,722 281,722 Capacity 11 40 00 Subc Food Equipment LS B E fin 1 2,440,990 2,440,990 11 66 00 Basketball Goals, Fixed EA fin 18 4,341 78,130 11 66 00 Climbin Pegboard EA fin 18 1,941 34,393 11 66 00 Climbin Pegboard EA fin 18 3,141 56,530 11 66 00 Climbin Pegboard EA fin 138,08 108,317 108,00 11 80 00 Add Cargo Netting SF fin 1 18,057,550 16,057,550 11 80 00 Add Cargo Netting ticks EA B E fin 2 202,107 404,213 11 98 00 Detention Subcontractor Estimit LS V E fin 1 18,057,550 16,057,550 12 00 0 Fixed Jury Chairs EA V E stru 296 52,506 15,541,883 13 42 00 Matt-Cell Modules (Cells) EA V E stru 296			LS	В	fin	1	48.913	48.913		
11 40 00 Subc Food Equipment LS B E fin 1 2,440,990 2,440,990 11 66 00 Rope Climb EA fin 18 4,341 78,130 11 66 00 Rope Climb EA fin 18 2,941 34,930 11 66 00 Climbing Pegboard EA fin 18 3,141 56,530 11 66 00 Climbing Pegboard EA fin 640 15.86 10,148 20.00 Wide 8.00 Tall 11 98 00 Add Cargo Netting SF fin 1 13.057,550 18.057,550 18.057,550 11 98 00 Detention Subcontractor Estim. LS V E fin 1 18.057,550 12 40 00 Entrance Mat & Frames SF B fin 13 1.570 20.413 \$51.000 Matri 12 40 00 Entrance Mat & Frames SF fin 573 63.57 47,866 12 40 00 Matl-Shur/Unfn Modules (Cells) EA V E stru 296 52.506 15,541,883 1,952.761 <t< td=""><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td>Capacitv</td></t<>										Capacitv
11 66 00 Basketball Goals, Fixed EA fin 18 3,441 78,130 11 66 00 Chim Up Bar EA fin 18 2,541 45,730 11 66 00 Chim Up Bar EA fin 18 1,941 34,930 11 66 00 Chim Up Bar EA fin 18 1,941 34,930 11 66 00 Chim Up Bar EA fin 18 3,141 56,530 11 66 00 Vall Padding SF fin 13395 8.09 100,317 11 98 00 Detertion Subcontractor Estim: LS V E fin 1 18,057,550 18,057,550 12 20 00 Manual Mecch Shades SF B fin 13 1,570 20,413 \$1,000 Mat'I 12 40 00 Entrance Mat & Frames SF fin 573 83,57 47,888 \$1,000 Mat'I 13 42 00 Matl-Self Modules (Cells) EA V E stru 21,52,506 15,541,883 \$1,195,210 13 42 00 Matl-Self Modules (Modules) EA T <t< td=""><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></t<>										
11 66 00 Rope Climb EA fin 18 2,541 45,730 11 66 00 Climbing Pegboard EA fin 18 3,141 56,550 11 66 00 Climbing Pegboard EA fin 18 3,141 56,550 11 66 00 Wall Padding SF fin 640 15,86 10,148 20.00 Wide 8.00" Tail 11 86 00 Kad Cargo Netting SF fin 13395 8.09 108,317 20.00 Wide 8.00" Tail 11 90 00 Four Fold Hyd Det Drs EA B E fin 13395 8.09 108,317 20.00 Wide 8.00" Tail 11 90 00 Four Fold Hyd Det Drs EA B E fin 13395 8.09 108,317 20.00 MatT 12 40 00 Entrance Mat & Frames SF fin 57.3 83.57 47.886 51.000 MatT 12 40 00 Entrance Mat & Frames SF fin 52.506 15.541.883 53.72 13 42 00 Matt-Sell Modules (Cells) EA V E stru 296 52.506<										
11 66 00 Chin Up Bar EA fin 18 1,941 34,930 11 66 00 Climbing Pegboard EA fin 18 1,941 34,930 11 66 00 Climbing Pegboard EA fin 18 1,941 34,930 11 66 00 Climbing Pegboard EA fin 18 1,941 34,930 11 66 00 Climbing Pegboard EA fin 18 1,941 34,930 11 68 00 Cargo Netting SF fin 133,955 8.09 108,317 11 90 00 Detention Subcontractor Estim: LS V E fin 13 1,570 20,413 \$1,000 Mat1 12 00 00 Manual Mecho Shades SF B fin 13 1,570 20,413 \$1,000 Mat1 12 00 00 Entrance Mat & Frames SF fin 573 83,57 47,886 13 42 00 Matl-Cell Modules (Cells EA V E stru 273 4,378 1,195,210 13 42 00 Instal-Cell Modules (Modules) EA V E <td></td>										
11 66 00 Climbing Pegboard EA fin 18 3,141 56,530 11 86 00 Vall Padding SF fin 640 15.86 10,148 20.00*Wide 8.00*Tall 11 86 00 Add Cargo Netting SF fin 13395 8.09 108,317 11 1000 Four Fold Hyd Det Drs EA B E fin 12,020 404,213 11 80 00 Detention Subcontractor Estim: LS V E fin 18,057,550 18,057,550 12 40 00 Exer Fold Hyd Det Drs EA Fin 53,357 47,886 31,000 Matt 12 40 00 Entrance Mat & Frames SF Fin 57,3 83,577 47,886 13 42 00 Matl-Cell Modules (Cells) EA V E stru 296 52,506 15,541,883 13 42 00 Matl-Cell Modules (Cells) EA V E stru 217 4,378 1,195,210 13 42 00 Matl-Shwr/Unfin Modules (Modules) EA T E stru 213 4,378 1,195,210		•								
11 f6 00 Wall Padding SF fin 640 15.86 10.148 20.00 Wide 8.00 Tail 11 19 00 Four Foid Hyd Det Drs EA B E fin 13395 8.09 108.317 11 00 00 Four Foid Hyd Det Drs EA B E fin 1 18,057,550 18,057,550 12 20 00 Manual Meccho Shades SF B fin 8.267 10.71 88,569 12 20 00 Fixed Jury Chairs EA Fin 13 1,570 20,413 \$1,000 Matri 12 40 00 Entrance Mat & Frames SF Fin 573 83.57 47,886 13 42 00 Matr-Cell Modules (Cells) EA V E stru 296 52,506 15,541,883 13 42 00 Matr-Cell Modules (Cells) EA V E stru 273 4,378 1,195,210 13 42 00 Matr-Sell Modules (Modules (Cells) EA T E stru 273 4,378 1,195,210 13 42 00 Matr-Sell Modules (Modules (Modules) EA T		•								
11 98 00 Add Cargo Netting SF fin 13395 8.09 108.317 11 00 00 Four Fold Hyd Del Drs EA B E fin 2 202.107 404.213 11 98 00 Manual Meccho Shades SF B E fin 1 18.057.550 18.057.550 12 00 00 Fixed Jury Chairs EA fin 13 1.570 20.413 \$1.000 Matting 12 40 00 Entrance Mat & Frames SF B fin 57.3 83.57 47.886 13 42 00 Matt-Cell Modules (Cells) EA V E stru 296 52.506 15.541.883 13 42 00 Matt-Shwr/Unfin Modules (Cells EA V E stru 273 4,378 1,195.210 13 42 00 Matt-Shwr/Unfin Modules (Modules) EA T E stru 273 4,378 1,195.210 13 42 00 Subc Elevators LS B E fin 1 298,500 298,500 14 20 00 Subc Elevator LS V E mep									20.00' Wide	8.00' Tall
11 00 00 11 98 00 Detention Subcontractor Estim: 12 20 00 Fixed Jury Chairs EA LS B E fin 2 202,107 404,213 11 98 00 Detention Subcontractor Estim: 12 20 00 Fixed Jury Chairs LS V E fin 11 8,057,550 18,057,550 12 00 00 Fixed Jury Chairs EA fin 13 1,570 20,413 \$1,000 Mat1 12 40 00 Entrance Mat & Frames SF in fin 573 83.57 47,886 Total Total 70 20,413 \$1,000 Mat1 Total 57 83.57 47,886 Total 52,506 15,541,883 Total 296 52,506 15,541,883 Total 21,724,040 \$53.72 Total 14 52,506 15,541,883 Total 296 52,506 15,541,883 Total 18,889,854 \$46.71 Z0 Elevators Total 298,500 298,500 Total 298,500 \$0.74										
11 98 00 12 20 00 Manual Meccho Shades SF LS V E fin 1 18,057,550 8,267 10.71 10.71 88,569 20,413 51,000 Mat1 12 00 00 Entrance Mat & Frames SF fin 573 83,57 47,886 12 00 00 Entrance Mat & Frames SF fin 573 83,57 47,886 12 40 00 Entrance Mat & Frames SF fin 573 83,57 47,886 13 42 00 Matl-Cell Modules (Cells) EA V E stru 296 52,506 15,541,883 13 42 00 Matl-Shwr/Unfin Modules (Cells) EA V E stru 41 52,506 2,152,761 13 42 10 Instail-Cell Modules (Modules) EA T E stru 273 4,378 1,195,210 14 20 00 Subc Elevator LS B E fin 1 298,500 298,500 298,500 210 000 Fire Protection LS V E mep 1 3,097,297 \$7.66 210 000 Fire Prot. Estimate (Amer Fire) LS <td< td=""><td></td><td></td><td></td><td>В</td><td></td><td></td><td></td><td></td><td></td><td></td></td<>				В						
12 20 00 Manual Meccho Shades SF B fin 8,267 10.71 88,569 12 60 00 Fixed Jury Chairs EA fin 13 1,570 20,413 \$1,000 Mat1 12 40 00 Entrance Mat & Frames SF fin 573 83.57 47,886 12 40 00 Entrance Mat & Frames SF fin 573 83.57 47,886 Total Total 21,724,040 \$53.72 13 4200 Matl-Cell Modules (Cells) EA V E stru 296 52,506 15,541,883 1,195,210 13 4200 Matl-Shwr/Unfin Modules (Cells) EA V E stru 273 4,378 1,195,210 13 4201 Install-Cell Modules (Modules) EA T E stru 273 4,378 1,195,210 13 4200 Subc Elevator LS B E fin 1 298,500 298,500 21 Fire Protection Ital Ital 1 3,097,297 \$7.66 22 Plumbing Ital		•								
12 60 00 12 40 00 Fixed Jury Chairs Entrance Mat & Frames EA SF fin fin 13 573 1,570 83,57 20,413 47,886 \$1,000 Matri 47,886 Total Total 21,724,040 \$53,72 9 Special Construction 13 42 00 Matt-Cell Modules (Cells) EA EA V E stru 296 52,506 15,541,883 13 42 00 Matt-Shwr/Unfin Modules (Cells) EA EA V E stru 273 4,378 1,195,210 13 42 00 Total 273 4,378 1,195,210 Total 273 4,378 1,195,210 Total 18,889,854 \$46.71 20 Elevators Total 298,500 Total 298,500 Total W E mep 1 3,097,297 \$7.66 Total W/HVAC 0 \$0.00 21 Piumbing Total W/HVAC 0 \$0.00 <td></td>										
12 40 00 Entrance Mat & Frames SF fin 573 83.57 47,886 Total Total 21,724,040 \$53.72 19 Special Construction EA V E stru 296 52,506 15,541,883 13 42 00 Matl-Cell Modules (Cells) EA V E stru 41 52,506 2,152,761 13 42 00 Matl-Cell Modules (Modules) EA V E stru 41 52,506 2,152,761 13 42 00 Install-Cell Modules (Modules) EA V E stru 273 4,378 1,195,210 14 20 00 Subc Elevator LS B E fin 1 298,500 298,500 21 Fire Protection It Total 1 3,097,297 \$7.66 22 Plumbing It It 3,097,297 \$7.66 3,097,297 \$7.66 22 Plumbing It It w/HVAC 0 \$0.00 23 HVAC Systems It V E mep 1 49,3				_					\$1 000 Mat'l	
Total $21,724,040$ \$53.72 19 Special Construction EA V E stru 296 52,506 15,541,883 52,761 13 42 00 Mati-Shwr/Unfin Modules (Cells EA V E stru 41 52,506 15,541,883 195,210 13 42 10 Install-Cell Modules (Modules) EA V E stru 41 52,506 1,195,210 13 42 10 Install-Cell Modules (Modules) EA V E stru 41 52,506 1,195,210 13 42 10 Install-Cell Modules (Modules) Total T E stru 41 52,506 1,95,41,883 20 Elevators Total T E stru 273 4,378 1,195,210 14 20 00 Subc Elevator LS B E fin 1 298,500 298,500 21 00 00 Fire Protection Total LS V E mep 1 3,097,297 \$7.66 3,097,297 Total Total V E mep									• .,	
19 Special Construction 13 42 00 Mati-Cell Modules (Cells) EA V E stru 296 552,506 15,541,883 13,120,10 13 42 00 Mati-Shir/Unfin Modules (Cells) EA V E stru 41 52,506 2,152,761 1,195,210 13 42 10 Install-Cell Modules (Modules) EA V E stru 273 4,378 1,195,210 Total T 298,500 298,500 298,500 \$0.74 Total T S.097,297 \$7.66 Total V E mep 1 3,097,297										
13 42 00 Matl-Cell Modules (Cells) EA V E stru 296 52,506 15,541,883 13 42 00 Matl-Shwr/Unfin Modules (Cells EA V E stru 41 52,506 2,152,761 13 42 10 Install-Cell Modules (Modules) EA T E stru 273 4,378 1,195,210 Total T E stru 273 4,378 1,195,210 Total T E stru 273 4,378 1,195,210 Total Total Total 20 Elevators Total Total 298,500 298,500 Total Total 298,500 298,500 Total Total 298,500 298,500 Total S V E mep 1 3,097,297 \$7.66 Total V E mep 1 3,097,297 \$7.66 Total w/HVAC 0 \$0.00 Total w/HVAC		lotal						21,724,040	\$53.72	
13 42 00 Matl-Cell Modules (Cells) EA V E stru 296 52,506 15,541,883 13 42 00 Matl-Shwr/Unfin Modules (Cells EA V E stru 41 52,506 2,152,761 13 42 10 Install-Cell Modules (Modules) EA T E stru 273 4,378 1,195,210 Total T E stru 273 4,378 1,195,210 Total T E stru 273 4,378 1,195,210 Total Total Total 20 Elevators Total Total 298,500 298,500 Total Total 298,500 298,500 Total Total 298,500 298,500 Total S V E mep 1 3,097,297 \$7.66 Total V E mep 1 3,097,297 \$7.66 Total w/HVAC 0 \$0.00 Total w/HVAC	19	Special Construction								
13 42 00 13 42 10 Matl-Shwr/Unfin Modules (Cells Install-Cell Modules (Modules) EA V E stru 41 52,506 2,73 2,152,761 1,195,210 20 Elevators Total T E stru 273 4,378 1,195,210 14 20 00 Subc Elevator LS B E fin 1 298,500 298,500 21 00 00 Fire Protection LS B E fin 1 3,097,297 \$7.66 21 Fire Protection LS V E mep 1 3,097,297 \$7.66 22 Plumbing Total V E mep 1 49,372,434 49,372,434 \$122.10 23 00 00 HVAC Systems LS V E mep 1 49,372,434 49,372,434 \$122.10			EA	V	E stru	296	52,506	15,541,883		
13 42 10 Install-Cell Modules (Modules) EA T E stru 273 4,378 1,195,210 Total Total Total 18,889,854 \$46.71 20 Elevators LS B E fin 1 298,500 14 20 00 Subc Elevator LS B E fin 1 298,500 298,500 21 Fire Protection Total V E mep 1 3,097,297 \$7.66 22 Plumbing Total V E mep 1 3,097,297 \$7.66 23 HVAC Systems Total V E mep 1 49,372,434 49,372,434 \$122.10		Matl-Shwr/Unfin Modules (Cells								
20 Elevators 14 20 00 Subc Elevator LS B E fin 1 298,500 298,500 21 Fire Protection Total - - - 298,500 \$0.74 21 00 00 Fire Protection - - - - - 298,500 \$0.74 21 00 00 Fire Protection -										
20 Elevators 14 20 00 Subc Elevator LS B E fin 1 298,500 298,500 21 Fire Protection Total - - - 298,500 \$0.74 21 00 00 Fire Protection - - - - - 298,500 \$0.74 21 00 00 Fire Protection -		T-4-1						40.000.054	¢ 40 74	
14 20 00 Subc Elevator LS B E fin 1 298,500 298,500 Total Total 298,500 \$0.74 21 Fire Protection 21 00 00 Fire Prot. Estimate (Amer Fire) LS V E mep 1 3,097,297 \$7.66 21 00 00 Fire Prot. Estimate (Amer Fire) LS V E mep 1 3,097,297 \$7.66 22 Plumbing Total V E mep 1 3,097,297 \$7.66 23 HVAC Systems Total V E mep 1 49,372,434 \$122.10		Iotal						18,889,854	\$46.71	
Total 298,500 \$0.74 21 Fire Protection 21 00 00 Fire Prot. Estimate (Amer Fire) LS V E mep 1 3,097,297 \$7.66 21 Otal V E mep 1 3,097,297 \$7.66 22 Plumbing V E mep V V/VAC 0 \$0.00 23 HVAC Systems LS V E mep 1 49,372,434 \$122.10	20	Elevators								
21 Fire Protection 21 00 00 Fire Prot. Estimate (Amer Fire) LS V E mep 1 3,097,297 \$7.66 22 Plumbing Total V E mep 1 3,097,297 \$7.66 22 Plumbing Total V V V V V 23 HVAC Systems V V E mep 1 49,372,434 49,372,434 \$122.10	14 20 00	Subc Elevator	LS	В	E fin	1	298,500	298,500		
21 Fire Protection 21 00 00 Fire Prot. Estimate (Amer Fire) LS V E mep 1 3,097,297 \$7.66 22 Plumbing Total V E mep 1 3,097,297 \$7.66 22 Plumbing Total V V V V V 23 HVAC Systems V V E mep 1 49,372,434 49,372,434 \$122.10		Total						208 500	¢0.74	
21 00 00 Fire Prot. Estimate (Amer Fire) LS V E mep 1 3,097,297 \$7.66 Total Total V E mep 1 3,097,297 \$7.66 22 Plumbing Total V E w/HVAC 0 \$0.00 23 HVAC Systems V E mep 1 49,372,434 49,372,434 \$122.10		Total						296,500	\$0.74	
21 00 00 Fire Prot. Estimate (Amer Fire) LS V E mep 1 3,097,297 \$7.66 Total Total V E mep 1 3,097,297 \$7.66 22 Plumbing Total V E w/HVAC 0 \$0.00 23 HVAC Systems V E mep 1 49,372,434 49,372,434 \$122.10	21	Fire Protection								
22 Plumbing Total w/HVAC 0 \$0.00 23 HVAC Systems V E Plumep 1 49,372,434 49,372,434 \$122.10			LS	V	E mep	1	3,097,297	3,097,297	\$7.66	
Total w/HVAC 0 \$0.00 23 HVAC Systems 23 00 00 HVAC Estimate-USE LS V E mep 1 49,372,434 49,372,434 \$122.10		Total						3,097,297	\$7.66	
Total w/HVAC 0 \$0.00 23 HVAC Systems 23 00 00 HVAC Estimate-USE LS V E mep 1 49,372,434 49,372,434 \$122.10										
23 HVAC Systems 23 00 00 HVAC Estimate-USE LS V E mep 1 49,372,434 \$122.10	22	Plumbing								
23 00 00 HVAC Estimate-USE LS V E mep 1 49,372,434 49,372,434 \$122.10		Total				,	w/HVAC	0	\$0.00	
23 00 00 HVAC Estimate-USE LS V E mep 1 49,372,434 49,372,434 \$122.10	22	HVAC Systems								
			IS	V	F men	1	49 372 434	49 372 434	\$122 10	
l otal 49,372,434 \$122.10	20 00 00		20	v	– mep	I	10,012,707			
		Iotal						49,372,434	\$122.10	

Powered by *LENS aim* ™

Item	Description	Unit	TP	Esc	Ph	Quantity	Price	Amount	QuantF	Prod
24	Electrical									
01 10 00	Temporary Power Bills	MO	V	Е	encl	24	3,360	80,640		/Month
26 00 00	Electrical Estimate	LS	V	Е	mep	1	25,656,074	25,656,074	\$63.45	/SF
28 00 00	Sec Elect. Estimate	LS	V	Е	mep	1	13,766,050	13,766,050	\$34.04	/SF

Total

39,502,764 **\$97.69**

Jackson County Detention Center Kansas City, Missouri March 3, 2023 SD 12 Option #3 Incorporated (Total of 1,000 Beds) Trade Partner Bid/ Pricing Summary



Risk/TP	Proj.						Scope H	old			Trade Pa	rtnor	Escalation Applied	
Туре	Phase	Scope of Work	BP#	Teamed Trade Partners	Bids/ Budgets	Qty of Bids	(In Bids		Continge	ncv	Escalation		Escalated	
	1	GRs/ GCs			15,137,441	NA		-/			Included	(
		Design			17,570,187	NA					Included			
В	fin	Final Cleaning	124A		471,194	2			14,884	3.2%			42,612	9.0%
т	fdn	CIP Concrete			14,249,918	1			150,044	1.1%	223,971	1.6%	,	
т	stru	Precast Concrete Erection			6,477,249	1			68,202	1.1%	116,170	1.8%		
V	stru	Precast Concrete Materials- Structure	3M	Enterprise Precast	17,674,402	2			186,102	1.1%	514,788	2.9%		
Т	fin	CMU Masonry			9,867,836	1			103,903	1.1%	204,361	2.1%		
В	stru	Structural steel	5B		3,917,686	2			123,753	3.2%			281,306	7.2%
В	stru	Misc. Steel- Steel Structure	5B		2,230,266	1			70,450	3.2%	176,930			
Т	stru	Misc. Steel- Precast Structure			3,564,689	1			37,534	1.1%	200,935	5.6%		
В	fin	General Carp-Install	6E		2,139,575	4			67,586	3.2%			193,489	9.0%
В	fin	Finished Carpentry Supply	6E		1,541,705	1			48,700	3.2%			139,422	9.0%
V	encl	Membrane Roofing	7G	Flynn Midwest	8,809,353	3			92,758	<mark>1.1%</mark>	948,977	10.8%		
В	encl	Metal Wall and Roof Panels	7E		634,720	3			20,050	3.2%	18,335	2.9%		
В	encl	Joint Sealants/Rated Sealants	71		1,877,000	3			59,291	3.2%	139,037	7.4%		
В	encl	Penetration Firestopping	71		1,876,160	1			59,265	3.2%			205,143	10.9%
В	stru	Spray Applied Fireproofing	07H		318,000	2			10,045	3.2%	Included			
В	fin	Comm. Doors, Frames & Hdwr Supply	8C		2,605,700	3			82,310	3.2%			235,642	9.0%
В	fin	Four-Fold Doors	8F		404,213	2			12,768	3.2%	20,000	4.9%		
В	encl	Glass & Glazing	8G		1,329,396	3			41,993	3.2%			145,359	10.9%
U	fin	Interior Borrowed Light Glazing			295,997	1			10,908	3.7%			26,768	9.0%
В	fin	Tile	9C	Midland Marble and Granite	357,198	2			11,283	<mark>3.2%</mark>			32,303	9.0%
В	fin	Drywall	9A		4,916,839	3			155,315	3.2%	Included			
В	fin	Flooring	9H		1,026,296	2			32,419	3.2%			92,811	9.0%
В	fin	Resinous/ Special Coatings	91		1,260,916	3			39,830	3.2%			114,029	9.0%
В	fin	Painting and Floor Sealer	9B		2,291,460	2			72,383	3.2%			207,224	9.0%
В	fin	Operable Partitions			95,846	3			3,028	3.2%			8,668	9.0%
В	fin	Laundry Equipment	11K		281,722	2			8,899	3.2%			25,477	9.0%
V	fin	Detention Equipment	11B	CML Security	18,057,550	2	0		190,136	1.1%	Included			
В	fin	Food Service Equipment	11C		2,440,990	1			77,107	3.2%	Included			
В	fin	Dock Equipment			48,913	1			1,545	3.2%			4,423	9.0%
В	fin	Roller Window Shades	12C		88,569	3			2,798	3.2%			8,010	9.0%
V	stru	Modular Cells Materials	111	Cornerstone Detention	17,694,644	3			186,315	<mark>1.1%</mark>	Included			
Т	stru	Modular Cells Erection			1,195,210	1			12,585	1.1%	20,885	1.7%		
B	fin	Elevators	14A		298,500	4			9,429	3.2%	Included			
V	mep	Fire Protection		American Fire Protection	3,097,297	4			32,613	<mark>1.1%</mark>	Included			
V	mep	Plumbing			with/ HVAC	3	4 000 000	0.004	540.005	4.40/	Included			
V	mep	HVAC		US Engineering	49,372,434	2	1,000,000	2.0%	519,865	1.1%	Included			
V	encl	Temporary Power			80,640	1			849	1.1%	Included			
V	mep	Electrical		Mark One Electric	25,656,074	4	0		270,144	1.1%	Included			
V	mep	Security Electronics	28A	Cornerstone Detention	13,766,050	4	0		144,949	1.1%	Included			
	fdn	Misc. Foundations			37,387	NA			1,575	4.2%			1,322	3.5%
	stru	Misc. Structural Items			1,104,969	NA			46,539	4.2%			79,341	7.2%
	encl	Misc. Enclosure Items			110,260	NA			4,644	4.2%			12,056	10.9%
	fin	Misc. Finishes & Arch Specialties			2,870,030	NA			120,879	4.2%			259,547	9.0%
V	mex	Mass Excavation		Kissick Construction	10,118,488	5			106,542	1.1%	Included			
Т	fin	Site Concrete			1,962,345	1			20,662	1.1%	137,971	7.0%	450.070	0.001
В	fin	Asphalt	32A		1,690,448	4			53,398	3.2%			152,873	9.0%
В	fin		32H		452,000	2			14,278	3.2%			40,876	9.0%
В	fin	Synthetic Turf	200		49,650	1			1,568	3.2%			4,490	9.0%
В	fin	Landscape/ Irrigation	32G		658,084	3			20,788	3.2%			59,513	9.0%
В	fdn	Site Utilities	33A		2,282,041	5			72,086	3.2%			80,710	3.5%
	fdn	Site Strucutres			262,340	NA			11,049	4.2%			9,278	3.5%
	fin	Site Specialties/ Signage			268,846	NA			11,323	4.2%			24,313	9.0%
		Permits, Bonds, Insurance			8,090,898	NA					Included			
		Fee			6,127,019	NA					Included			

291,104,639 Legend Subtotal T= Budgets Prepared by JE Dunn Self Perform Design Contingency 2,911,046 V= Teamed-Best Value Trade Partner Construction Contingency 3,517,372 B=Budget From Trade Partner U=Unit Price form Trade Partner 2,487,005 Escalation Allowance 1,142,005 I-Internal Estimate Owner Contingency Total Design & Construction Cost \$301,162,067

Escalation based upon 1.5% /Quarter from today through Start of Work

Contingency

3,517,372

Scope Hold (In Bids) 1,000,000 Trade

Partner Escalation

(Incl)

2,722,359

Escalation Allowance

Applied to

Non-Escalated Budgets

2,487,005





Rev Date

Version

EXHIBIT B GMP 2 Jackson County, Mo – Jackson County Detention Center J.E. Dunn Project No. 22026200

Contract Documents

1. The contract between Owner and Design/Builder dated May 19th 2022

2. Design/Builder's Front End Documents dated August 17th, 2022.

3. Geotechnical Report prepared by CFS dated September 8th, 2022.

4. Drawings and Specifications prepared by Design/Builder as follows:

Sheet Number and Title

Jackson	County	Detention	Center
Jackson	County	Detention	Center

Special Use Permit	11.30.2022	Special Use Permit
C-000 – Cover Alt		1
C-001 – Survey	11.30.2022	Special Use Permit
C-002 – Site Plan Alt	11.30.2022	Special Use Permit
C-003 – Site Grading Plan Alt	11.30.2022	Special Use Permit
C-004 – Site Utility Plan Alt	11.30.2022	Special Use Permit
	11.30.2022	Special Use Permit
C-005 – Signage Plan	11.30.2022	Special Use Permit
-001 – Landscape Plan	11.30.2022	Special Use Permit
002 – Enlarged Landscape Plan	11.30.2022	Special Use Permit
-003 – Enlarged Landscape Plan		
-004 – Enlarged Landscape Plan	11.30.2022	Special Use Permit
A-400 – Elevation	11.30.2022	Special Use Permit
Schematic Design Documents		
Appendix A – Program Validation	02.10.2023	Schematic Design Documents
Appendix C1 – Storm Water Drainage Report	02.03.2023	Schematic Design Documents
	02.03.2023	Schematic Design Documents
Appendix C2 – Private Grading and Site disturbance Plans	02.03.2023	Schematic Design Documents
Schematic Design Narrative	02.10.2023	Schematic Design Documents
0.0 – Schematic Design Drawings Cover Sheet/Index of Drawings	02.10.2023	Schematic Design Documents
).1 – Site Plan – Overall Building		·
).2 – Overall Floor Plan – Level 1	02.10.2023	Schematic Design Documents
).3 – Overall Floor Plan – Level Upper Housing Tier	02.10.2023	Schematic Design Documents
0.4 – Overall Floor Plan – Level 2 0.5 – Overall Building Plan – Roof	02.10.2023 02.10.2023	Schematic Design Documents Schematic Design Documents
0.6.1 – Overall Building Perspectives	02.10.2023	Schematic Design Documents
0.6.2 – Overall Building Rendering	02.10.2023	Schematic Design Documents
0.6.3 – Overall Building Rendering	02.10.2023	Schematic Design Documents
0.7.0 – Exterior Elevations – Front Building	02.10.2023	Schematic Design Documer
0.7.1 – Overall Building – Exterior Elevations	02.10.2023	Schematic Design Documents
1.0 – Floor Plan, Level 1 & Building Section - 6.100 Orientation, 6.700 Juvenile and	02.10.2023	Schematic Design Documents
3.500 Special Needs Stage 4 Housing 1.1 – Floor Plan, Upper Tier & Building Sections - 6.100 Orientation and 8.500 Special Needs Stage 4 Housing	02.10.2023	Schematic Design Documents
1.2 – Building Section & Interior Perspectives – 6.700 Juvenile Housing	02.10.2023	Schematic Design Documents
2.0 – Floor Plans & Building Sections – 6.200 Maximum Housing - Male	02.10.2023	Schematic Design Documents
2.1 – Interior Perspectives – 6.200 Maximum Housing - Male	02.10.2023	Schematic Design Documents
8.0 – Floor Plans & Building Sections – 6.300 Segregation Housing – Male and 6.500A Med/Min Housing – Male Unit 1 (All ADA Lower Level	02.10.2023	Schematic Design Documents
3.1 – Interior Perspectives – 6.300 Segregation Housing - Male	02.10.2023	Schematic Design Documents
4.0 – Floor Plan, Level 1 & Building Sections – 6.500B Medium & Minimum Housing	02.10.2023	Schematic Design Documents
- Male Units 2,3,4 & 5 4.1 – Floor Plan, Upper Tier & Building Sections – 6.500B Medium & Minimum	02.10.2023	Schematic Design Documents
lousing – Male Units 2,3,4 & 5 .2 – Floor Plan, Level 1 & Building Section – 6.500B Med & Min Housing – Male	02.10.2023	Schematic Design Documents
Jnits 6 & 7 – 6.500C Med & Min Housing – Male Dorms 8 & 9 I.3 – Floor Plan, Upper Tier & Building Sections – 6.500B Med & Min Housing –	02.10.2023	Schematic Design Documents
Male Units 6 & 7 – 6.500C Med & Min Housing – Male Dorms 8 & 9	02.10.2023	Schematic Design Documents
	02.10.2023	Schematic Design Documents
4.4 – Interior Perspective – 6.500B Medium and Minimum Housing – Male		Schematic Design Documents
4.4 – Interior Perspective – 6.500B Medium and Minimum Housing – Male 4.5 – Interior Perspective – 6.500B Medium and Minimum Housing - Male		Schematic Design Documente
4.4 – Interior Perspective – 6.500B Medium and Minimum Housing – Male 4.5 – Interior Perspective – 6.500B Medium and Minimum Housing - Male 4.6 – Interior Perspective – 6.500B Medium and Minimum Housing - Male	02.10.2023	8
4.4 – Interior Perspective – 6.500B Medium and Minimum Housing – Male 4.5 – Interior Perspective – 6.500B Medium and Minimum Housing - Male		Schematic Design Documents Schematic Design Documents Schematic Design Documents

pecification	Rev Date	Version
103 – Enlarged Landscape Plan 3	02.03.2023	Schematic Design Documents
102 – Enlarged Landscape Plan 2	02.03.2023	Schematic Design Documents
101 – Enlarged Landscape Plan 1	02.03.2023	Schematic Design Documents
100 – Landscape Plan	02.03.2023	Schematic Design Documents
104 – Enlarged Site Utility Plan	02.03.2023	Schematic Design Documents
-102 – Site Otinity Plan	02.03.2023	Schematic Design Documents
-101 – Site Grading Plan	02.03.2023	Schematic Design Documents
-100 – Site Frain -101 – Site Grading Plan	02.03.2023	Schematic Design Documents
100 – Site Plan	02.03.2023	Schematic Design Documents
-012 – Enlarged Site Demolition Plan 12	02.03.2023	Schematic Design Documents
-010 – Enlarged Site Demolition Plan 10	02.03.2023	Schematic Design Documents
-009 – Enlarged Site Demolition Plan 9 -010 – Enlarged Site Demolition Plan 10	02.03.2023 02.03.2023	Schematic Design Documents
-009 – Enlarged Site Demolition Plan 8 -009 – Enlarged Site Demolition Plan 9	02.03.2023	Schematic Design Documents Schematic Design Documents
-007 – Enlarged Site Demolition Plan 7	02.03.2023	Schematic Design Documents
006 – Enlarged Site Demolition Plan 6 007 – Enlarged Site Demolition Plan 7	02.03.2023	Schematic Design Documents
-005 – Enlarged Site Demolition Plan 5	02.03.2023	Schematic Design Documents
-004 – Enlarged Site Demolition Plan 4	02.03.2023	Schematic Design Documents
-003 – Enlarged Site Demolition Plan 3	02.03.2023	Schematic Design Documents
002 – Enlarged Site Demolition Plan 2	02.03.2023	Schematic Design Documents
001 – Enlarged Site Demolition Plan 1	02.03.2023	Schematic Design Documents
000 – Overall Site Demolition Plan	02.03.2023	Schematic Design Documents
000 Overall Site Demolition Plan	02.02.2022	Schematic Desire Desure
.3.2 – Code Separations Plan – Overall Upper Cell Tier/Level 2	02.10.2023	
.3.1 – Code Separations Plan – Overall Level 1	02.10.2023	Schematic Design Documents
.2.2 – Code Smoke Zone Plan – Overall Upper Cell Tier/Level 2	02.10.2023	Schematic Design Documents
I.2.1 – Code Smoke Zone Plan – Overall Level 1	02.10.2023	Schematic Design Documents
1.1.2 – Code Occupancy Type Diagram – Overall Level 1	02.10.2023	Schematic Design Documents
ells – Stage 1-3 I.1.1 – Code Occupancy Type Diagram – Overall Level 1	02.10.2023	Schematic Design Documents
0.6 – Enlarged Plans and Elevations, Precast Modules – Special Needs Housing	02.10.2023	Schematic Design Documents
boms 0.5 – Enlarged Plans and Elevations, Medical and Infirmary Housing Cells	02.10.2023	Schematic Design Documents
0.4 – Enlarged Plans and Elevations, Precast Modules – Dormitory Sleeping coms	02.10.2023	Schematic Design Documents
0.3 – Enlarged Plans and Elevations, Precast Modules – 4-Person Housing Cells	02.10.2023	Schematic Design Documents
0.2 – Enlarged Plans and Elevations, Precast Modules – 1-Person & 2-Person busing Cells	02.10.2023	Schematic Design Documents
 D.1 – Enlarged Plans and Elevations, Precast Modules – 1-Person & 2-Person busing Cells 	02.10.2023	Schematic Design Documents
2 – Floor Plan, Level 1 – 9.300 Receiving, 9.400 Maintenance and 9.600 Central ant	02.10.2023	Schematic Design Documents
1.2 – Interior Perspectives – Courtyard, Central Training and Staff Dining	02.10.2023	Schematic Design Documents
1.1 – Floor Plan, Level 1 – 2.200 Command, 3.200 Staff Support, 7.100 ograms, 9.100 Food Service, 9.200 Laundry, 9.300 Central Storage	02.10.2023	Schematic Design Documents
3.2 – Interior Perspectives – 1.000 Public Lobby, 2.000 Administration, 3.000 Staff upport	02.10.2023	Schematic Design Documents
3.1 – Floor Plan, Level 1 – 1.000 Public Lobby. 1.200 Visitation, 4.000 Master ontrol and 5.600 Release	02.10.2023	Schematic Design Documents
2 – Floor Plan, Level 2 & Bidg Section – 2.100 Facility Admin, 2.500 Safety, zeurity & Technology, and 3.100 Training/Accreditation/Analyst	02.10.2023	Schematic Design Documents
1 – Floor Plan, Level 1 & Building Section - 2.300 Information Management, 2.600 ommunity Corrections, and 3.200 Staff Support	02.10.2023	Schematic Design Documents
3.3 – Interior Perspective – 5.300 Court	02.10.2023	Schematic Design Documents
3.2 – Interior Perspectives – 5.300 Court	02.10.2023	Schematic Design Documents
3.1 - Floor Plan, Level 2 - 5.300 Court	02.10.2023	Schematic Design Documents
500 Transportation 2.2 – Interior Perspectives – 5.200 Intake	02.10.2023	Schematic Design Documents
2.1 – Floor Plan, Level 1 – 5.100 Vehicle Sallyport & Armory, 5.200 Intake and	02.10.2023	Schematic Design Documents
1.2 – Interior Perspectives – 5.500 Transportation	02.10.2023	Schematic Design Documents
2.2 – Interior Perspectives – 8.400 Special Needs Stage 1-3 1.1 – Floor Plan, Level 1 – 5.500 Transportation	02.10.2023 02.10.2023	Schematic Design Documents Schematic Design Documents
2.1 – Floor Plan, Level 1 & Building Section – 8.400 Special Needs Stage 1-3, 300 Central Storage and 9.500 Custodial	02.10.2023	Schematic Design Documents
1.2 – Interior Perspectives – 8.300 Medical Housing	02.10.2023	Schematic Design Documents
1.1 – Floor Plan, Level 1 – 8.100 Central Clinic, 8.200 Infirmary, and 8.300 edical Housing	02.10.2023	Schematic Design Documents
nd 8.400 Special Needs Stage 4		

DB

DCP

DCP

01 35 13.16 SPECIAL PROJECT PROCEDURES FOR DETENTION CENTER

Division 02 - EXISTING CONDITIONS	
02 41 16 STRUCTURE DEMOLITION	01.17.2022
02 41 19 SELECTIVE DEMOLITION	01.17.2022
Division 03 - CONCRETE	

03 01 30 MAINTENANCE OF CAST-IN-PLACE CONCRETE	01.17.2022	DCP
03 10 00 CONCRETE FORMING AND ACCESSORIES	01.17.2022	DCP
03 12 30 GEOFOAM CONCRETE FORMS		DB
03 20 00 CONCRETE REINFORCING	01.17.2022	DCP
03 30 00 CAST IN PLACE CONCRETE 03 33 00 ARCHITECTURAL CONCRETE	01.17.2022 01.17.2022	DB DCP
03 35 43 POLISHED CONCRETE FINISHING	01.26.2023	DB
03 41 00 PRECAST STRUCTURAL CONCRETE	- 01.26.2023	DB
		55
DIVISION 04 - MASONRY	-	
04 20 00 UNIT MASONRY	01.26.2023	DB
DIVISION 05 - METALS	-	
05 12 00 STRUCTURAL STEEL FRAMING	- 01.26.2023	DB
05 21 00 STEEL JOIST FRAMING		DB
05 31 00 STEEL DECKING	01.26.2023	DB
05 40 00 COLD-FORMED METAL FRAMING	01.26.2023	DB
05 50 00 METAL FABRICATIONS	01.17.2022	DCP
05 51 13 METAL PAN STAIRS		DCP
05 52 13 PIPE AND TUBE RAILINGS	01.17.2022	DCP
05 53 13 BAR GRATINGS		DCP
05 53 16 PLANK GRATINGS 05 59 63 DETENTION ENCLOSURES	_ 01.17.2022 01.17.2022	DCP DCP
		201
DIVISION 06 - WOOD, PLASTICS, AND COMPOSITES		
06 10 53 MISCELLANEOUS ROUGH CARPENTRY	01.26.2023	DB
06 16 00 SHEATHING	01.26.2023	DB
06 20 23 INTERIOR FINISH CARPENTRY	01.17.2022	DCP
	01.17.2022	DCP
06 20 23 INTERIOR FINISH CARPENTAL 06 64 00 PLASTIC PANELING 06 40 23 INTERIOR ARCHITECTURAL WOODWORK 06 41 16 PLASTIC-LAMINATE-CLAD ARCHITECTURAL CABINETS	01.26.2023 01.26.2023	DB DB
06 42 16 FLUSH WOOD PANELING	01.26.2023	DB
00 42 TO FLOSH WOOD FAITELING	01.20.2023	
DIVISION 07 - THERMAL AND MOISTURE PROTECTION	_	
07 11 13 BITUMINOUS DAMPPROOFING		DCP
07 13 26 SELF-ADHERING SHEET WATERPROOFING	01.26.2023	DB
07 13 53 ELASTOMERIC SHEET WATERPROOFING		DCP
07 14 16 COLD FLUID-APPLIED WATERPROOFING	01.17.2022	DCP DCP
07 18 00 TRAFFIC COATINGS 07 19 00 WATER REPELLENTS	_ 01.17.2022 01.17.2022	DCP
07 19 00 WATER REFELEENTS 07 21 00 THERMAL INSULATION		DB
07 25 00 WEATHER BARRIERS	- 01.17.2022	DCP
07 26 00 VAPOR RETARDERS	01.17.2022	DCP
07 41 13.16 STANDING-SEAM METAL ROOF PANELS	01.17.2022	DCP
07 42 13.19 INSULATED METAL WALL PANELS	01.26.2023	DB
07 42 13.23 METAL COMPOSITE MATERIAL WALL PANELS	01.17.2022	DCP
07 42 23.13-FORMED METAL WALL PANELS	01.26.2023	DB
07 42 93 SOFFIT PANELS	01.17.2022	DCP
07 53 23 ETHYLENE-PROPYLENE-DIENE-MONOMER (EPDM) ROOFING		DB
07 54 23 THERMOPLASTIC POLYOLEFIN TPO ROOFING	01.26.2023	DB DB
07 62 00 SHEET METAL FLASHING AND TRIM 07 71 00 ROOF SPECIALTIES	01.26.2023 01.26.2023	DB
07 71 29 MANUFACTURED ROOF EXPANSION JOINT	01.26.2023	DB
07 72 00 ROOF ACCESSORIES	- 01.26.2023	DB
07 72 53 SNOW GUARD	01.17.2022	DCP
07 81 00 APPLIED FIRE PROTECTION		DB
07 81 23 INTUMESCENT FIRE PROTECTION	01.26.2023	DB
07 84 13 PENETRATION FIRESTOPPING	01.26.2023	DB
07 84 43 JOINT FIRESTOPPING	01.26.2023	DB
07 91 00 PREFORMED JOINT SEALS	01.17.2022	DCP
07 92 00 JOINT SEALANTS	01.26.2023	DB
07 92 00.53 SECURITY JOINT SEALANTS		DB
07 92 19 ACOUSTICAL JOINT SEALANTS 07 95 13.13 INTERIOR EXPANSION JOINT COVER ASSEMBLIES	01.26.2023	DB DB
07 95 13.13 INTERIOR EXPANSION JOINT COVER ASSEMBLIES 07 95 13.16 EXTERIOR EXPANSION JOINT COVER ASSEMBLIES	01.26.2023 01.17.2022	DCP
	_	201
DIVISION 08 - OPENINGS	-	
08 11 13 HOLLOW METAL DOORS AND FRAMES	01.26.2023	DB
08 12 16 ALUMINUM FRAMES	01.17.2022	DCP
08 14 16 FLUSH WOOD DOORS 08 31 13 ACCESS DOORS AND FRAMES	01.26.2023 01.26.2023	DB DB
08 31 13.53 SECURITY ACCESS DOORS AND FRAMES	09.14.2022	DB
08 33 13 COILING COUNTER DOORS	01.26.2023	DB
08 33 23 OVERHEAD COILING DOORS		DB
08 33 26 OVERHEAD COILING GRILLES	01.17.2022	DCP
08 33 43 OVERHEAD COILING SMOKE CURTAINS		DB
08 34 63 DETENTION DOORS AND FRAMES	01.26.2023	DB
08 41 13 ALUMINUM-FRAMED ENTRANCES AND STOREFRONTS	01.26.2023	DB
08 42 29.23 SLIDING AUTOMATIC ENTRANCES	01.17.2022	DCP
08 51 13 ALUMINUM WINDOWS	01.17.2022	DCP
08 62 00 UNIT SKYLIGHTS OPTION A	01.26.2023	DB
08 62 00 UNIT SKYLIGHTS OPTION B	01.26.2023	DB
08 71 11 DOOR HARDWARE 08 71 13 AUTOMATIC DOOR OPERATORS	_ 01.26.2023 01.26.2023	DB DB
08 71 13 AUTOMATIC DOOR OPERATORS 08 71 63 DETENTION DOOR HARDWARE	01.26.2023	DB
08 80 00 GLAZING		DB
	_	20

08 84 00 PLASTIC GLAZING	01.26.2023	DB
08 88 13 FIRE-RATED GLAZING	01.26.2023	DB
08 88 53 SECURITY GLAZING	01.26.2023	DB
08 91 19 FIXED LOUVERS	01.17.2022	DCP
DIVISION 09 - FINISHES		
09 05 61.13 MOISTURE VAPOR EMISSION CONTROL	01.26.2023	DB
09 21 16.23 GYPSUM BOARD SHAFT WALL ASSEMBLIES	01.26.2023	DB
09 22 16 NON-STRUCTURAL METAL FRAMING	01.26.2023	DB
09 24 00 CEMENT PLASTERING	01.17.2022	DCP
09 29 00 GYPSUM BOARD	01.26.2023	DB
09 30 13 CERAMIC TILING	01.26.2023	DB
09 51 13 ACOUSTICAL PANEL CEILINGS	01.26.2023	DB
09 51 23 ACOUSTICAL TILE CEILINGS	01.17.2022	DCP
09 65 13 RESILIENT BASE AND ACCESSORIES	01.26.2023	DB
09 65 16 RESILIENT SHEET FLOORING	01.26.2023	DB
09 65 19 RESILIENT TILE FLOORING	01.26.2023	DB
09 65 66 RESILIENT ATHLETIC FLOORING	01.26.2023	DB
09 67 23 RESINOUS FLOORING	01.26.2023	DB
09 68 13 TILE CARPETING	01.26.2023	DB
09 72 00 WALL COVERINGS	01.17.2022	DCP
09 74 36 DECORATIVE WOOD GRD SYSTEMS	01.26.2023	DB
09 77 23 FABRIC-WRAPPED PANELS	01.17.2022	DCP
09 84 33 SOUND ABSORBING WALL UNITS	01.26.2023	DB
09 91 14 EXTERIOR PAINTING	01.26.2023	DB
09 91 24 INTERIOR PAINTING	01.26.2023	DB
09 93 00 STAINING AND TRANSPARENT FINISHING	01.17.2022	DCP
09 96 00 HIGH-PERFORMANCE COATINGS	01.26.2023	DB
09 96 03 SPECIAL COATINGS	01.26.2023	DB
09 96 53 ELASTOMERIC COATINGS	01.17.2022	DCP
		DCP
09 97 26 CEMENTITIOUS COATINGS	01.17.2022	
09 98 53 RESILIENT PADDING SYSTEMS	01.26.2023	DB
DIVISION 10 - SPECIALTIES		
10 11 00 VISUAL DISPLAY UNITS	01.17.2022	DCP
10 12 00 DISPLAY CASES	01.17.2022	DCP
10 14 16 PLAQUES	01.26.2023	DB
10 14 19 DIMENSIONAL LETTER SIGNAGE	01.26.2023	DB
10 14 23 PANEL SIGNAGE	01.26.2023	DB
10 14 23.16 ROOM-IDENTIFICATION PANEL SIGNAGE	01.17.2022	DCP
10 14 26 POST AND PANEL/PYLON SIGNAGE	01.17.2022	DCP
10 14 73 PAINTED SIGNAGE	01.26.2023	DB
10 17 00 TELEPHONE SPECIALTIES	01.17.2022	DCP
10 21 13.14 STAINLESS-STEEL TOILET COMPARTMENTS	01.17.2022	DCP
10 21 13.17 PHENOLIC-CORE TOILET COMPARTMENTS	01.17.2022	DCP
10 21 13.19 PLASTIC TOILET COMPARTMENTS	01.17.2022	DCP
10 21 16.14 STAINLESS-STEEL SHOWER AND DRESSING COMPARTMENTS	01.17.2022	DCP
10 21 23 CUBICLE CURTAINS AND TRACK	01.26.2023	DB
10 22 13 WIRE MESH PARTITIONS	01.26.2023	DB
10 22 39 FOLDING PANEL PARTITIONS	01.17.2022	DCP
10 26 00 WALL AND DOOR PROTECTION	01.26.2023	DB
10 28 00 TOILET, BATH, AND LAUNDRY ACCESSORIES	01.26.2023	DB
10 28 13.63 DETENTION TOILET ACCESSORIES	01.17.2022	DCP
10 44 13 FIRE PROTECTION CABINETS	01.26.2023	DB
10 44 16 FIRE EXTINGUISHERS	01.26.2023	DB
10 51 13 METAL LOCKERS	01.17.2022	DCP
10 51 16 WOOD LOCKERS	01.26.2023	DB
10 55 00.16 PRIVATE-DELIVERY POSTAL SPECIALTIES	01.17.2022	DCP
10 56 13 METAL STORAGE SHELVING	01.17.2022	DCP
10 75 16 GROUND-SET FLAGPOLES	01.26.2023	DB
10 75 23 WALL-MOOUNTED FLAGPOLES	01.17.2022	DCP
DIVISION 11 - EQUIPMENT		
11 11 00 COMMERCIAL LAUNDRY EQUIPMENT	01.26.2023	DB
11 12 00 PARKING CONTROL EQUIPMENT	01.17.2022	DCP
11 13 13 LOADNG DOCK BUMPERS	01.17.2022	DCP
11 13 19 STATIONARY LOADING DOCK EQUIPMENT	01.17.2022	DCP
11 19 00 DETENTION EQUIPMENT GENERAL REQUIREMENTS	01.17.2022	DCP
11 19 05 DETENTION DOORS AND FRAMES	01.17.2022	DCP
11 19 07 DETENTION ACCESS PANELS	01.17.2022	DCP
11 19 08 DETENTION GROUTING OF HOLLOW METAL FRAMES	01.17.2022	DCP
11 19 10 DETENTION HARDWARE	01.17.2022	DCP
11 19 15 DETENTION WINDOW ASSEMBLIES	01.17.2022	DCP
11 19 16 DETENTION WINDOW ASSEMBLIES	01.17.2022	DCP
11 19 20 DETENTION SECURITY GLAZING	01.17.2022	DCP
11 19 20 DETENTION SECURITY GLAZING 11 19 25 DETENTION OPENING SECURITY GRILLES	01.17.2022	DCP
		DCP
11 19 26 DETENTION GRILLAGE ASSEMBLIES	01.17.2022	DCP
11 19 30 DETENTION CEILING ASSEMBLIES	01.17.2022	
11 19 35 DETENTION WALL ASSEMBLIES	01.17.2022	DCP
11 19 36 DETENTION MODULAR STEEL CELLS	01.17.2022	DCP
11 19 40 DETENTION FIXED EQUIPMENT & ACCESSORIES	01.17.2022	DCP
11 19 45 DETENTION FUDBISHINGS	01.17.2022	DCP
11 19 50 DETENTION CELL PADDING	01.17.2022	DCP
11 19 71 DETENTION SECURITY SCREENS	01.17.2022	DCP
11 19 80 DETENTION SEALANTS	01.17.2022	DCP
11 19 85 DETENTION SCREWS AND FASTENERS	01.17.2022	DCP
11 19 90 DETENTION WALL AND FLOOR FINISHES	01.17.2022	DCP

11 40 00 FOODSERVICE EQUIPMENT	01.17.2022	DCP
DIVISION 12 - FURNISHINGS		
12 21 13 HORIZONTAL LOUVER BLINDS	01.17.2022	DCP
12 24 13 ROLLER WINDOW SHADES	01.26.2023	DB
12 36 23.13 PLASTIC-LAMINATE-CLAD COUNTERTOPS	01.17.2022	DCP
12 36 61.16 SOLID SURFACING COUNTERTOPS 12 48 13 ENTRANCE FLOOR MATS AND FRAMES	01.26.2023 01.17.2022	DB DCP
12 46 13 ENTRANCE FLOOR WATS AND FRAMES	01.17.2022	DOI
DIVISION 13 SPECIAL CONSTRUCTION	04.47.0000	DOD
13 34 23 MODULAR PRECAST CONCRETE CELLS 13 34 19 MODULAR BUILDING SYSTEMS	01.17.2022 01.17.2022	DCP DCP
	01.17.2022	DOI
DIVISION 21 - FIRE SUPPRESSION		
21 05 13 COMMON MOTOR REQUIREMENTS FOR SUPPRESSION EQUIPMENT	01.17.2022	DCP
21 05 23 GENERAL-DUTY VALVES FOR WATER-BASED FIRE-SUPPRESSION	01.17.2022	DCP
PIPING 21 05 33 HEAT TRACING	01.17.2022	DCP
21 05 48.13 VIBRATION CONTROLS FOR FIRE-SUPPRESSION PIPING AND	01.17.2022	DCP
EQUIPMENT		
21 11 16 FACILITY FIRE HYDRANTS	01.17.2022	DCP DCP
21 11 19 FIRE DEPARTMENT CONNECTIONS 21 12 00 FIRE-SUPPRESSION STANDPIPES	01.17.2022 01.17.2022	DCP
21 13 13 WET-PIPE SPRINKLER SYSTEMS	01.17.2022	DCP
21 13 16 DRY-PIPE SPRINKLER SYSTEMS	01.17.2022	DCP
DIVISION 22 - PLUMBING		
22 01 00 PLUMBING GENERAL PROVISIONS	01.17.2022	DCP
22 06 13 COMMON MOTOR REQUIREMENTS FOR PLUMBING EQUIPMENT 22 05 16 EXPANSION FITTINGS AND LOOPS FOR PLUMBING PIPING	01.17.2022 01.17.2022	DCP DCP
22 05 16 EXPANSION FITTINGS AND LOOPS FOR PLUMBING PIPING	01.17.2022	DCP
22 05 18 ESCUTCHEONS FOR PLUMBING PIPING	01.17.2022	DCP
22 05 19 METERS AND GAGES FOR PLUMBING PIPING	01.17.2022	DCP
22 05 23.12 BALL VALVES FOR PLUMBING PIPING	01.17.2022	DCP
22 05 23.13 BUTTERFLY VALVES FOR PLUMBING PIPING	01.17.2022	DCP
22 05 23.14 CHECK VALVES FOR PLUMBING PIPING 22 05 23.15 GATE VALVES FOR PLUMBING PIPING	01.17.2022 01.17.2022	DCP DCP
22 05 29 HANGERS AND SUPPORTS FOR PLUMBING PIPING AND	01.17.2022	DCP
EQUIPMENT		
22 05 48.13 VIBRATION CONTROLS FOR PLUMBING PIPING AND EQUIPMENT 22 05 93 TESTING, ADJUSTING AND BALANCING FOR PLUMBING	01.17.2022 01.17.2022	DCP DCP
22 05 93 TESTING, ADJUSTING AND BALANCING FOR PLOMBING 22 61 13 COMPRESSED-AIR PIPING FOR LABORATORY AND HEALTHCARE	01.17.2022	DCP
FACILITIES	01.11.2022	20.
22 07 16 PLUMBING EQUIPMENT INSULATION	01.17.2022	DCP
22 07 19 PLUMBING PIPING INSULATION	01.17.2022	DCP
22 09 63 MEDICAL GAS ALARMS 22 11 13 FACILITY WATER DISTRIBUTION PIPING	01.17.2022 01.17.2022	DCP DCP
22 11 16 DOMESTIC WATER PIPING	01.17.2022	DCP
22 11 19 DOMESTIC WATER PIPING SPECIALTIES	01.17.2022	DCP
22 11 23 DOMESTIC WATER PUMPS	01.17.2022	DCP
22 13 13 FACILITY SANITARY SEWERS	01.17.2022	DCP
22 13 16 SANITARY WASTE AND VENT PIPING	01.17.2022	DCP
22 13 19 SANITARY WASTE PIPING SPECIALTIES 22 13 19.13 SANITARY DRAINS	01.17.2022 01.17.2022	DCP DCP
22 13 23 SANITARY WASTE INTERCEPTORS	01.17.2022	DCP
22 13 29 SANITARY SEWERAGE PUMPS	01.17.2022	DCP
22 14 23 STORM DRAINAGE PIPING SPECIALTIES	01.17.2022	DCP
	01.17.2022	DCP DCP
22 15 13 GENERAL-SERVICE COMPRESSED-AIR PIPING 22 15 19 GENERAL-SERVICE PACKAGED AIR COMPRESSORS AND	01.17.2022 01.17.2022	DCP
RECEIVERS		
22 31 00 DOMESTIC WATER SOFTENERS	01.17.2022	DCP
22 33 00 ELECTRIC, DOMESTIC-WATER HEATERS	01.17.2022	DCP
22 34 00 FUEL-FIRED, DOMESTIC-WATER HEATERS 22 42 13.13 COMMERCIAL WATER CLOSETS	01.17.2022 01.17.2022	DCP DCP
22 42 13.15 COMMERCIAL WATER CLOSE 13	01.17.2022	DCP
22 42 16.13 COMMERCIAL LAVATORIES	01.17.2022	DCP
22 42 16.16 COMMERCIAL SINKS	01.17.2022	DCP
22 42 23 COMMERCIAL SHOWERS	01.17.2022	DCP
22 42 33 WASH FOUNTAINS 22 45 00 EMERGENCY PLUMBING FIXTURES	01.17.2022 01.17.2022	DCP DCP
22 45 00 EMERGENCE PLOMBING FIXTORES	01.17.2022	DCP
22 47 13 DRINKING FOUNTAINS	01.17.2022	DCP
22 61 13 COMPRESSED-AIR PIPING FOR LABORATORY AND HEALTHCARE	01.17.2022	DCP
FACILITIES 22 61 19 COMPRESSED-AIR EQUIPMENT FOR LABORATORY AND	01.17.2022	DCP
HEALTHCARE FACILITIES	01.17.2022	DCF
22 62 13 VACUUM PIPING FOR LABORATORY AND HEALTHCARE FACILITIES	01.17.2022	DCP
22 62 19 VACUUM EQUIPMENT FOR LABORATORY AND HEALTHCARE	01.17.2022	DCP
FACILITIES 22 63 13 GAS PIPING FOR LABORATORY AND HEALTHCARE FACILITIES	01.17.2022	DCP
LE 55 TO ONO FILING FOR EABOIRT OR FAID HEALTHORICE FROILITED	5	201
DIVISION 23 - HEATING VENTILATION AND AIR CONDITIONING (HVAC)		:
23 01 00 MECHANICAL GENERAL PROVISIONS	01.17.2022	DCP
23 05 19 COMMON MOTOR REQUIREMENTS FOR HVAC EQUIPMENT 23 05 19 METERS AND GAGES FOR HVAC PIPING	01.17.2022 01.17.2022	DCP DCP
23 05 19 METERS AND GAGES FOR HVAC PIPING 23 05 23.12 BALL VALVES FOR HVAC PIPING	01.17.2022	DCP
	-	-

23 05 23.13 BUTTERFLY VALVES FOR HVAC PIPING 23 05 23.14 CHECK VALVES FOR HVAC PIPING
22.14 CHECK VALVES FOR HVAC PIPING 29 HANGERS AND SUPPORTS FOR HVAC PIPING AND EQUIPMENT
5 48 VIBRATION AND SEISMIC CONTROLS FOR HVAC
5 53 IDENTIFICATION FOR HVAC PIPING AND EQUIPMENT
5 66 ANTIMICROBIAL ULTRAVIOLET LAMP SYSTEMS FOR HVAC
05 93 TESTING, ADJUSTING, AND BALANCING FOR HVAC
07 13 DUCT INSULATION
07 16 HVAC EQUIPMENT INSULATION
8 08 00 COMMISSIONING OF HVAC 8 09 23 DIRECT DIGITAL CONTROL (DDC) SYSTEM FOR HVAC
3 09 23.11 CONTROL VALVES
3 09 23.12 CONTROL DAMPERS
23 09 23.13 ENERGY METERS
23 09 23.14 FLOW INSTRUMENTS
23 09 23.16 GAS INSTRUMENTS
23 09 23.17 LEVEL INSTRUMENTS
23 09 23.18 LEAK DETECTION INSRUMENTS 23 09 23.19 MOISTURE INSTRUMENTS
23 09 23.19 MOISTURE INSTRUMENTS 23 09 23.22 POSITION INSTRUMENTS
23 09 23.23 PRESSURE INSTRUMENTS
23 09 23.24 SPEED INSTRUMENTS
23 09 23.27 TEMPERATURE INSTRUMENTS
23 09 23 33 VIBRATION INSTRUMENTS
23 09 23.43 WEATHER STATIONS
23 09 23.43 WEATHER STATIONS 23 09 93 SEQUENCE OF OPERATIONS FOR HVAC DDC
23 11 23 FACILITY NATURAL-GAS PIPING
23 21 13 HYDRONIC PIPING
23 21 13.13 UNDERGROUND HYDRONIC PIPING
23 21 16 HYDRONIC PIPING SPECIALTIES 23 21 23 HYDRONIC PUMPS
23 23 00 REFRIGERANT PIPING
23 25 00 HVAC WATER TREATMENT
23 31 13 METAL DUCTS 23 33 00 AIR DUCT ACCESSORIES
23 33 46 FLEXIBLE DUCTS
23 34 13 AXIAL HVAC FANS
23 34 16 CENTRIFUGAL HVAC FANS
23 34 23 HVAC POWER VENTILATORS
23 34 33.16 INDUSTRIAL AIR CURTAINS
23 34 39 HIGH-VOLUME, LOW-SPEED FANS 23 36 00 AIR TERMINAL UNITS
23 37 13.13 AIR DIFFUSERS
23 37 13.23 REGISTERS AND GRILLES 23 37 13.43 SECURITY REGISTERS AND GRILLES
23 37 23 HVAC GRAVITY VENTILATORS
23 38 13 KITCHEN HOODS
23 41 00 PARTICULATE AIR FILTRATION
23 43 00 ELECTRONIC AIR CLEANERS
23 51 23 GAS VENTS
23 52 16 CONDENSING BOILERS
23 52 10 CONDENSING BOILENS 23 53 13 BOILER FEEDWATER PUMPS 23 55 23.13 LOW-INTENSITY, GAS-FIRED, RADIANT HEATERS 23 55 33.16 GAS-FIRED UNIT HEATERS 23 65 14 AUB COOL ED DEEEDICEPANT CONDENSERS
23 55 23.13 LOW-INTENSITY, GAS-FIRED, RADIANT HEATERS
23 55 33.16 GAS-FIRED UNIT HEATERS
23 03 13 AIR-GOOLED REFRIGERANT CONDENSERS
23 64 16 CENTRIFUGAL WATER CHILLERS
23 65 13 COOLING TOWERS 23 72 13 HEAT WHEEL AIR-TO-AIR ENERGY RECOVERY UNITS
23 72 13 HEAT WHEEL AIR-TO-AIR ENERGY RECOVERY UNITS
23 72 10 HEAT FIFE AIR-10-AIR ENERGY RECOVERY UNITS
23 73 13.19 INDOOR, CUSTOM AIR-HANDLING UNITS
23 74 33 DEDICATED, OUTDOOR-AIR UNITS
23 81 26 SPLIT-SYSTEM AIR-CONDITIONERS
23 82 16.11 HYDRONIC AIR COILS
23 82 16.13 REFRIGERANT AIR COILS
23 82 16.14 ELECTRIC-RESISTANCE AIR COILS
23 82 19 FAN COIL UNITS
23 82 36 FINNED-TUBE RADIATION HEATERS
23 82 39 UNIT HEATERS
23 84 13.29 SELF-CONTAINED STEAM HUMIDIFIERS
DIVISION 26 - ELECTRICAL
26 01 00 BASIC ELECTRICAL REQUIREMENTS
26 05 13 MEDIUM-VOLTAGE CABLES
26 05 19 LOW-VOLTAGE ELECTRICAL POWER CONDUCTORS AND CABES
26 05 26 GROUNDING AND BONDING FOR ELECTRICAL SYSTEMS
26 05 29 HANGERS AND SUPPORTS FOR ELECTRICAL SYSTEMS
26 05 33 RACEWAYS AND BOXES FOR ELECTRICAL SYSTEMS
26 05 43 UNDERGROUND DUCTS AND RACEWAYS FOR ELECTRICAL
SYSTEM 26.05.44.91 EEVES AND SI EEVE SEALS FOD ELECTRICAL DACEWAYS AND
26 05 44 SLEEVES AND SLEEVE SEALS FOR ELECTRICAL RACEWAYS AND CABLING
26.05.53 IDENTIFICATION FOR ELECTRICAL SYSTEMS
26 05 53 IDENTIFICATION FOR ELECTRICAL SYSTEMS 26 05 73.16 COORDINATION STUDIES
26 05 53 IDENTIFICATION FOR ELECTRICAL SYSTEMS 26 05 73.16 COORDINATION STUDIES 26 09 13 ELECTRICAL POWER MONITORING

DCP DCP DCP

DCP DCP DCP DCP DCP

DCP DCP

DCP DCP DCP DCP DCP DCP

DCP DCP DCP DCP DCP

DCP DCP DCP DCP DCP

DCP DCP DCP DCP DCP

DCP DCP DCP

DCP

DCP DCP DCP DCP DCP DCP DCP

DCP

DCP DCP DCP DCP

26 09 43.23 RELAY-BASED LIGHTING CONTROLS		
20 09 43.23 NELAT-DAGED LIGITTING CONTROLS	01.17.2022	DCP
26 11 16.11 SECONDARY UNIT SUBSTATIONS WITH SWITCHGEAR	01.17.2022	DCP
SECONDARY		
26 22 13 LOW-VOLTAGE DISTRIBUTION TRANSFORMERS	01.17.2022	DCP
26 24 13 SWITCHBOARDS	01.17.2022	DCP
26 24 16 PANELBOARDS	01.17.2022	DCP
26 25 00 LOW-VOLTAGE ENCLOSED BUS ASSEMBLIES	01.17.2022	DCP
26 27 26 WIRING DEVICES	01.17.2022	DCP
26 28 13 FUSES	01.17.2022	DCP
26 28 16 ENCLOSED SWITCHES AND CIRCUIT BREAKERS	01.17.2022	DCP
26 29 13.03 MANUAL AND MAGNETIC MOTOR CONTROLLERS	01.17.2022	DCP
26 29 23 VARIABLE FREQUENCY MOTOR CONTROLLERS	01.17.2022	DCP
26 32 13.13 DIESEL-ENGINE-DRIVEN GENERATORS	01.17.2022	DCP
26 33 53 STATIC UNINTERRUPTIBLE POWER SUPPLY	01.17.2022	DCP
26 36 00 TRANSFER SWITCHES	01.17.2022	DCP
26 41 13 LIGHTNING PROTECTION FOR STRUCTURES	01.17.2022	DCP
26 43 13 SURGE PROTECTION FOR LOW-VOLTAGE ELECTRICAL POWER	01.17.2022	DCP
CIRCUITS		
26 51 19 LED INTERIOR LIGHTING	01.17.2022	DCP
26 52 13 EMERGENCY AND EXIT LIGHTING	01.17.2022	DCP
26 56 19 LED EXTERIOR LIGHTING	01.17.2022	DCP
DIVISION 27 - COMMUNICATIONS		
27 05 26 GROUNDING AND BONDING FOR COMMUNICATION SYSTEMS	01.17.2022	DCP
27 05 36 CABLE TRAYS FOR TELECOMMUNICATIONS	01.17.2022	DCP
27 10 00 FIBER OPTIC CABLE TESTING 09.14.22 DB	09.14.2022	DB
27 11 16 CABINETS, RACKS, FRAMES, AND ENCLOSURES	01.17.2022	DCP
27 13 23 COMMUNICATIONS OPTICAL FIBER BACKBONE CABLING	01.17.2022	DCP
27 15 00 COMMUNICATIONS HORIZONTAL CABLING SYSTEMS	09.14.2022	DB
27 15 13 COMMUNICATIONS COPPER HORIZONTAL CABLING	01.17.2022	DCP
27 15 33 COMMUNICATIONS COAXIAL HORIZONTAL CABLING	01.17.2022	DCP
27 41 13 CABLE TELEVISION SYSTEM	09.14.2022	DB
	09.14.2022	DB
27 41 16 AUDIO VISUAL SYSTEM	03.14.2022	
	01.17.2022	DCP
27 41 16 AUDIO VISUAL SYSTEM		DCP DCP
27 41 16 AUDIO VISUAL SYSTEM 27 41 33 MASTER ANTENNA TELEVISION SYSTEM	01.17.2022	- • ·

DIVISION 28 - ELECTRONIC SAFETY AND SECURITY

28 05 00 COMMON WORK RESULTS FOR ELECTRONIC SECURITY		
20 00 UU COMMON WORK RESULTS FOR ELECTRONIC SECORT	09.14.2022	DB
28 05 00.10 UNINTERRUPTIBLE POWER SOURCE	09.14.2022	DB
28 05 00.20 SECURITY AND COMMUNICATION CONDUIT/RACEWAY	09.14.2022	DB
28 05 10 MAINT, SERVICE, & WARRANTY FOR ELECTRONIC SECURITY	01.17.2022	DCP
28 05 11 BACKBONE SYSTEM CABLING FOR ELECTRONIC SECURITY	01.17.2022	DCP
28 05 12 HORIZONTAL CABLING SYSTEM FOR ELECTRONIC SECURITY	01.17.2022	DCP
28 05 26 GROUNDING, BONDING, SURGE, & UPS FOR ELEC SECURITY	01.17.2022	DCP
28 05 30 TAMPER PROOF FASTENERS FOR ELECTRONIC SECURITY	01.17.2022	DCP
28 11 16 CABINETS AND ENCLOSURES FOR ELECTRONIC SECURITY	01.17.2022	DCP
28 13 00 ACCESS CONTROL SYSTEM	09.14.2022	DB
28 15 00 ACCESS CONTROL HARDWARE DEVICES	01.17.2022	DCP
28 15 25 ELECTRONIC KEY MANAGEMENT SYSTEM	09.14.2022	DB
28 20 00 VIDEO SURVEILLANCE	01.17.2022	DCP
28 23 00 IP VIDEO SURVEILLANCE	09.14.2022	DB
28 31 11 DIGITAL ADDRESSABLE FIRE ALARM SYSTEM	09.14.2022	DB
28 44 00 REFRIGERANT DETECTION AND ALARM	01.17.2022	DCP
28 46 00 TOUCHSCREEN COMPUTER STATION	09.14.2022	DB
28 46 00.20 EVENT RECORDING SYSTEM	09.14.2022	DB
28 46 19 PLC HARDWARE FOR ELECTRONIC SECURITY	09.14.2022	DB
28 46 20 PLC SOFTWARE FOR ELECTRONIC SECURITY	01.17.2022	DCP
28 46 21.11 ADDRESSABLE FIRE-ALARM SYSTEMS	01.17.2022	DCP
28 51 23 INTEGRATED INTERCOM AND PAGING SYSTEM FOR ELECTRONIC	01.17.2022	DCP
SEC		
SEC 28 52 11 DETENTION MONITORING AND CONTROL SYSTEMS	01.17.2022	DCP
28 52 11 DETENTION MONITORING AND CONTROL SYSTEMS DIVISION 31 – EARTHWORK	01.17.2022	DCP
28 52 11 DETENTION MONITORING AND CONTROL SYSTEMS	01.17.2022 08.02.2022	DCP DB
28 52 11 DETENTION MONITORING AND CONTROL SYSTEMS DIVISION 31 – EARTHWORK		
28 52 11 DETENTION MONITORING AND CONTROL SYSTEMS DIVISION 31 – EARTHWORK 31 10 00 SITE CLEARING	08.02.2022	DB
28 52 11 DETENTION MONITORING AND CONTROL SYSTEMS DIVISION 31 – EARTHWORK 31 10 00 SITE CLEARING 31 20 00 EARTHWORK	08.02.2022 08.02.2022	DB
28 52 11 DETENTION MONITORING AND CONTROL SYSTEMS DIVISION 31 – EARTHWORK 31 10 00 SITE CLEARING 31 20 00 EARTHWORK 31 60 00 SETTLEMENT MONITORING 31 70 00 WICK DRAINS	08.02.2022 08.02.2022 08.02.2022	DB DB DB
28 52 11 DETENTION MONITORING AND CONTROL SYSTEMS DIVISION 31 – EARTHWORK 31 10 00 SITE CLEARING 31 20 00 EARTHWORK 31 60 00 SETTLEMENT MONITORING 31 70 00 WICK DRAINS DIVISION 32 - EXTERIOR IMPROVEMENTS	08.02.2022 08.02.2022 08.02.2022 08.02.2022 08.02.2022	DB DB DB
28 52 11 DETENTION MONITORING AND CONTROL SYSTEMS DIVISION 31 – EARTHWORK 31 10 00 SITE CLEARING 31 20 00 EARTHWORK 31 60 00 SETTLEMENT MONITORING 31 70 00 WICK DRAINS DIVISION 32 - EXTERIOR IMPROVEMENTS 32 12 16 ASPHALT PAVING	08.02.2022 08.02.2022 08.02.2022 08.02.2022 08.02.2022	DB DB DB DB
28 52 11 DETENTION MONITORING AND CONTROL SYSTEMS DIVISION 31 – EARTHWORK 31 10 00 SITE CLEARING 31 20 00 EARTHWORK 31 60 00 SETTLEMENT MONITORING 31 70 00 WICK DRAINS DIVISION 32 - EXTERIOR IMPROVEMENTS 32 12 16 ASPHALT PAVING 32 13 13 CONCRETE PAVING	08.02.2022 08.02.2022 08.02.2022 08.02.2022 08.02.2022 01.17.2022 01.17.2022	DB DB DB DB DCP DCP
28 52 11 DETENTION MONITORING AND CONTROL SYSTEMS DIVISION 31 – EARTHWORK 31 10 00 SITE CLEARING 31 20 00 EARTHWORK 31 60 00 SETTLEMENT MONITORING 31 70 00 WICK DRAINS DIVISION 32 - EXTERIOR IMPROVEMENTS 32 12 16 ASPHALT PAVING 32 13 13 CONCRETE PAVING 32 13 73 CONCRETE PAVING JOINT SEALANTS	08.02.2022 08.02.2022 08.02.2022 08.02.2022 01.17.2022 01.17.2022 01.17.2022	DB DB DB DCP DCP DCP DCP
28 52 11 DETENTION MONITORING AND CONTROL SYSTEMS DIVISION 31 – EARTHWORK 31 10 00 SITE CLEARING 31 20 00 EARTHWORK 31 60 00 SETTLEMENT MONITORING 31 70 00 WICK DRAINS DIVISION 32 - EXTERIOR IMPROVEMENTS 32 12 16 ASPHALT PAVING 32 13 13 CONCRETE PAVING 32 13 73 CONCRETE PAVING JOINT SEALANTS 32 14 00 UNIT PAVING	08.02.2022 08.02.2022 08.02.2022 08.02.2022 01.17.2022 01.17.2022 01.17.2022 01.17.2022	DB DB DB DB DCP DCP DCP DCP DCP
28 52 11 DETENTION MONITORING AND CONTROL SYSTEMS DIVISION 31 – EARTHWORK 31 10 00 SITE CLEARING 31 20 00 EARTHWORK 31 60 00 SETTLEMENT MONITORING 31 70 00 WICK DRAINS DIVISION 32 - EXTERIOR IMPROVEMENTS 32 12 16 ASPHALT PAVING 32 13 13 CONCRETE PAVING 32 13 13 CONCRETE PAVING 32 14 00 UNIT PAVING 32 14 71 3 PARKING BUMPERS	08.02.2022 08.02.2022 08.02.2022 08.02.2022 01.17.2022 01.17.2022 01.17.2022 01.17.2022 01.17.2022	DB DB DB DCP DCP DCP DCP
28 52 11 DETENTION MONITORING AND CONTROL SYSTEMS DIVISION 31 – EARTHWORK 31 10 00 SITE CLEARING 31 20 00 EARTHWORK 31 60 00 SETTLEMENT MONITORING 31 70 00 WICK DRAINS DIVISION 32 - EXTERIOR IMPROVEMENTS 32 12 16 ASPHALT PAVING 32 13 13 CONCRETE PAVING 32 13 13 CONCRETE PAVING 32 14 00 UNIT PAVING 32 17 13 PARKING BUMPERS 32 17 16 MANUFACTURED TRAFFIC-CALMING DEVICES	08.02.2022 08.02.2022 08.02.2022 08.02.2022 01.17.2022 01.17.2022 01.17.2022 01.17.2022 01.17.2022 01.17.2022 01.17.2022	DB DB DB DB DCP DCP DCP DCP DCP
28 52 11 DETENTION MONITORING AND CONTROL SYSTEMS DIVISION 31 – EARTHWORK 31 10 00 SITE CLEARING 31 20 00 EARTHWORK 31 60 00 SETTLEMENT MONITORING 31 70 00 WICK DRAINS DIVISION 32 - EXTERIOR IMPROVEMENTS 32 12 16 ASPHALT PAVING 32 13 13 CONCRETE PAVING 32 13 13 CONCRETE PAVING 32 13 73 CONCRETE PAVING JOINT SEALANTS 32 14 00 UNIT PAVING 32 17 13 PARKING BUMPERS 32 17 13 PARKING BUMPERS 32 17 23 PAVEMENT MARKINGS	08.02.2022 08.02.2022 08.02.2022 08.02.2022 01.17.2022 01.17.2022 01.17.2022 01.17.2022 01.17.2022 01.17.2022 01.17.2022 01.17.2022	DB DB DB DCP DCP DCP DCP DCP DCP DCP
28 52 11 DETENTION MONITORING AND CONTROL SYSTEMS DIVISION 31 – EARTHWORK 31 10 00 SITE CLEARING 31 20 00 EARTHWORK 31 60 00 SETTLEMENT MONITORING 31 70 00 WICK DRAINS DIVISION 32 - EXTERIOR IMPROVEMENTS 32 12 16 ASPHALT PAVING 32 13 13 CONCRETE PAVING 32 13 73 CONCRETE PAVING JOINT SEALANTS 32 14 00 UNIT PAVING 32 17 13 PARKING BUMPERS 32 17 16 MANUFACTURED TRAFFIC-CALMING DEVICES 32 17 26 TACTILE WARNING SURFACING	08.02.2022 08.02.2022 08.02.2022 08.02.2022 01.17.2022 01.17.2022 01.17.2022 01.17.2022 01.17.2022 01.17.2022 01.17.2022 01.17.2022 01.17.2022	DB DB DB DB DCP DCP DCP DCP DCP DCP DCP DCP
28 52 11 DETENTION MONITORING AND CONTROL SYSTEMS DIVISION 31 - EARTHWORK 31 10 00 SITE CLEARING 31 20 00 EARTHWORK 31 60 00 SETTLEMENT MONITORING 31 70 00 WICK DRAINS DIVISION 32 - EXTERIOR IMPROVEMENTS 32 12 16 ASPHALT PAVING 32 13 73 CONCRETE PAVING JOINT SEALANTS 32 14 00 UNIT PAVING 32 17 13 PARKING BUMPERS 32 17 16 MANUFACTURED TRAFFIC-CALMING DEVICES 32 17 23 PAVEMENT MARKINGS 32 17 16 TACTILE WARNING SURFACING 32 31 13 CHAIN LINK FENCES AND GATES	08.02.2022 08.02.2022 08.02.2022 08.02.2022 01.17.2022 01.17.2022 01.17.2022 01.17.2022 01.17.2022 01.17.2022 01.17.2022 01.17.2022 01.17.2022 01.17.2022	DB DB DB DB DCP DCP DCP DCP DCP DCP DCP DCP DCP
28 52 11 DETENTION MONITORING AND CONTROL SYSTEMS DIVISION 31 - EARTHWORK 31 10 00 SITE CLEARING 31 20 00 EARTHWORK 31 60 00 SETTLEMENT MONITORING 31 70 00 WICK DRAINS DIVISION 32 - EXTERIOR IMPROVEMENTS 32 12 16 ASPHALT PAVING 32 13 13 CONCRETE PAVING 32 14 00 UNIT PAVING 32 17 13 PARKING BUMPERS 32 17 16 MANUFACTURED TRAFFIC-CALMING DEVICES 32 17 26 TACTILE WARNING SURFACING 32 11 3.53 HIGH-SECURITY CHAIN LINK FENCES AND GATES	08.02.2022 08.02.2022 08.02.2022 08.02.2022 01.17.2022 01.17.2022 01.17.2022 01.17.2022 01.17.2022 01.17.2022 01.17.2022 01.17.2022 01.17.2022	DB DB DB DCP DCP DCP DCP DCP DCP DCP DCP DCP DCP
28 52 11 DETENTION MONITORING AND CONTROL SYSTEMS DIVISION 31 - EARTHWORK 31 10 00 SITE CLEARING 31 20 00 EARTHWORK 31 60 00 SETTLEMENT MONITORING 31 70 00 WICK DRAINS DIVISION 32 - EXTERIOR IMPROVEMENTS 32 12 16 ASPHALT PAVING 32 13 3 CONCRETE PAVING JOINT SEALANTS 32 14 00 UNIT PAVING 32 17 13 PARKING BUMPERS 32 17 16 MANUFACTURED TRAFFIC-CALMING DEVICES 32 17 23 PAVEMENT MARKINGS 32 17 36 TACTILE WARNING SURFACING 32 31 13 CHAIN LINK FENCES AND GATES	08.02.2022 08.02.2022 08.02.2022 08.02.2022 01.17.2022 01.17.2022 01.17.2022 01.17.2022 01.17.2022 01.17.2022 01.17.2022 01.17.2022 01.17.2022 01.17.2022 01.17.2022	DB DB DB DCP DCP DCP DCP DCP DCP DCP DCP DCP DCP

** LEDGEND DCP=DESIGN CRITIERIA PACKET
DB=DESIGN BUILDER
JED GMP Exhibits
JED.01 – HVAC VAV Zones
JED.02 – Plumbing One-Lines
JED.03 – Chilled Water and Heating Hot Water One-Lines
JED.04 – Electrical One-Line Diagram
JED.05 – Electrical Room Layouts JED.06 – Skylight Take-Off Plan
JED.07 – Woven Wire Rod and Detention Metal Panel Take-Off Plan
JED.08 – DEC-SEC Plans and Schedules



Exhibit 3

Jackson County Detention Center	hummin	ΈŊΉ	IBIT 3		
Kansas City, Missouri					
March 14, 2023					0
JE Dunn/Axiom/DLR GMP Proposal				CONSTRUCTION	

	Description	JCDC ID #	Current Estimate and ROM Savings Items Below	Recommend Y/N	Alternates or Cost Breakouts				
	Bold Number is Full Criteria (1256 Beds) based on January Bids & Budgets		\$333,380,782						
1	Delete all LEED Requirement, see Design Criteria Modification #014	G2a	-3,129,000	Yes					
	Delete Integral Color Concrete at Housing Floors, see Design Criteria Modification #015	G12	-337,000	Yes					
	Eliminate fill North of Facility, shift road to the south toward building	S3	-151,000	Yes					
	Alternate No. 1 - Alternative funding for the court component.	P1			-6,180,000				
5	Alternate No. 2 - Eliminate (2) 64 bed housing units, 128 total beds (1256 - 128 = 1128)	H2a			-9,007,435				
6	Alternate No. 3 - Eliminate and additional (2) 64 bed housing units, 128 total be (1128 - 128 = 1,000)	H2b			-10,152,080				
7	At (12) housing units reduce quantity of ADA holding cells to (2) per housing unit and reduce size of the remaining holding cells and overall unit, see Design Criteria Modification #001 and #017.	H3	-1,155,000	Yes					
8	Reduce size of the dayroom to meet ACA standards, decreases length not width	H6	-605,000	Yes					
9	Convert 2 male med/min housing units into dorms - 64 beds in each, 128 total beds. See revised floor plans and Design Criteria Modification #050.	H10	-500,000	Yes					
10	Delete cell cameras at Male and Female Med/Min Housing only, see Design Criteria Modification #020	H12	-400,000	Yes					
11	Delete Coax for all holding cell TVs, see Design Criteria Modification #021	H14	-250,000	Yes					
	Reduce cell ceiling height to 8'-0", in lieu of 9'-0" AFF. We need to increase clear height to 8'-1" at subdayrooms. Male Seg Lower Level Cells have increased to 10' Clear. All Sleeping Alcoves for Dorm shall be 9' clear, See Design Criteria Modification #023.	H21	-697,000	Yes					
13	Reduce generator dB rating to 90 dB. Lower dB rating is acceptable with generators located outside, see Design Criteria Modification #039.	M3e	-86,700	Yes					
14	Reduce Site Lighting below DCP 3 FC, goal is to hit an average 1 FC, see Design Criteria Modification #026.	E1	-246,000	Yes					
15	Delete windborn impact resistant requirement for exterior glazing, see Design Criteria Modification #025	J3	-1,280,000	Yes					
16	Reduce Avg Height of Structure at general cell housing to approximately 22'-4" AFF.	J5	-817,000	Yes					
	Use PVC for above grade waste piping in areas that are not return air plenums.	J13	-429,000	Yes					
18	Use PVC for above grade storm piping in areas that are not return air plenums.	J14	-111,000	Yes					
19	Provide snowmelt system in the Transportation Yard drive lanes only, see Design Criteria Modification #052.	J22	-98,900	Yes					
20	Use Schedule 40 PVC below grade in lieu of Schedule 80, see Design Criteria Modification #028.	J26	-300,000	Yes					
21	Use Aluminum wire in lieu of copper at all branch feeders, see Design Criteria Modification #029.	J27	-173,000	Yes					
22	Use open cable tray at Administration Building in lieu of EMT for LV wiring, see Design Criteria Modifciation #041.	J39	-250,000	Yes					
23	MC Cabling at Admin. Building in lieu of EMT, see Design Criteria Modification #053.	J41	-62,400	Yes					
24	Provide data jacks in lieu of coax at all AV/TV locations, see Design Criteria Modification #021	J43	-71,200	Yes					
25	Provide a gray roof provided by Flynn Roofing Company in lieu of white, see Design Criteria Modification #030	J45	-1,410,000	Yes					
26	Use new Ewing Entrance Budget to help pay for the new Ewing Road.	J57	-500,000	Yes					
	Total Savings in list	above	(\$13,059,200)		(\$25,339,515)				
GN	IP Options	D = -1-	#000 000 700						
	Full Criteria 1256		\$333,380,782						
	Option 1: 1256 Beds with recommended changes			Includes yeses					
	Option 2: 1128 Beds with recommended cha	nges	\$311,314,147	, Item #5 above, reduces schedule duration by 1 Month					
	Option 3: 1000 Beds with recommended changes			Item#6 abo	ove, includes schedule savir	1 more			
JE Dunn's M/W/VBE Goals respectively MBE 17.5%/WBE 11.0%/VBE0.5% = Totals 29%									
JE Dunn is on track to beat the Total M/W/VBE Goal stated above by a couple percent on any of the options above									


		\mathcal{C}	······	\dots	·······
OU/Anchor FSE			xhi	hi+	4
CU/Anchor FSE	Activity Name				
	Activity Name	Dur	Start	Finish	Jan F Mar Apr M Jun Jul Aug Sep Oct Nov Dec Jan F Mar Apr May Jun Jul /
Jackson C	county Detention Center				
Summary (V	•				
SUM-1000	Overall Project Duration	727	21-Jun-22 A	25-Sep-25	
SUM-1510	Overall Design Duration		21-Jun-22 A	21-Feb-24	Overall Design Duration
SUM-2010	GMP Development Duration		21-Jun-22 A	14-Apr-23	GMP Development Duration
SUM-2020	JCMO Review & Submit Comments of GMP (Cal. Days)		14-Feb-23	14-Apr-23	JCMO Review & Submit Comments of GMP (Cal. Days)
CON-1370	GMP Jackson County Legislative Approval	0	11100 20	20-Feb-23	 ♦ GMP Jackson County Legislative Approval
CON-1380	GMP Approved by Jackson County	0		17-Apr-23	 ♦ GMP Approved by Jackson County
JED-0100	Start Construction	0	17-Apr-23		◆ Start Construction
SUM-2000	Overall Construction Duration		17-Apr-23	25-Sep-25	
JED-0200	Structure Complete	020	1770120	10-Oct-24	
JED-0200	Skin Weather Tight	0		31-Oct-24	
JED-0300	Permanent Power Startup	0		25-Nov-24	
JED-0500	Start Up HVAC	0		02-Dec-24	
SUM-1520	Planning for Transition into Facility		08-Apr-25	02-Det-24	
SUM-1520	Anticipated Weather Days - 0 / 77 Used		09-Jun-25	25-Sep-25	
JED-0600	Substantial Completion / Contract End Date		09-301-23	25-Sep-25*	
SUM-1540	Final Move In / Transition	12	26-Sep-25	25-Sep-25 25-Nov-25	
JED-0700	Project / Final Completion	43	20-3ep-25	25-Nov-25	
SUM-1550	Final Move In / Transition Complete	0		25-Nov-25	
	-	0		25-1100-25	
Preconstruc					
	ponent Package 1 & 2A				
OWN-2050	GMP - Component Package 1 & 2A Development		21-Jun-22 A	13-Feb-23	GMP - Component Package 1 & 2A Development
OWN-2060	Detailed Estimate w/ Trade Partner Input		24-Aug-22 A	06-Feb-23	Detailed Estimate w/ Trade Partner Input
OWN-2210	Legislation Prep	5	07-Feb-23	13-Feb-23	Legislation Prep
OWN-2010	GMP - Component Package 1 & 2A Submitted to JCMO	0		13-Feb-23	◆ GMP - Component Package 1 & 2A Submitted to JCMO
SUM-2220	Release Long Lead Procurement	0		13-Feb-23	◆ Release Long Lead Procurement
OWN-2020	JCMO Review & Submit Comments of GMP - Component Package 1 & 2A(Cal. Days)	60	-	14-Apr-23	JCMO Review & Submit Comments of GMP - Component Package 1 & 2A(Cal.
OWN-2040	JED Incorporates JCMO GMP - Component Package 1 & 2A Comments		20-Mar-23	14-Apr-23	JED Incorporate's JCMO GMP - Component Package 1 & 2A Comments
OWN-2030	GMP - Component Package 1 & 2A Approval by JCMO	0		17-Apr-23	GMP - Component Package 1 & 2A Approval by JCMO
Procuremer				_	
PRO-1000	Long Lead MEP Procurement		17-Apr-23	02-Jan-24	Long Lead MEP Procurement
PRO-1070	Switchgear & Parallel Gears Procurement		17-Apr-23	11-Nov-24	
PRO-1080	Generator Procurement		17-Apr-23	11-Nov-24	
PRO-1090	RTU Procurement		17-Apr-23	27-Mar-24	RTU Procurement
PRO-1100	Chillers Procurement		17-Apr-23	27-Mar-24	Chillers Procuremen
PRO-1110	Boilers Procurement		17-Apr-23	04-Oct-23	Boilers Procurement
PRO-1010	Foundations & U/G MEP Procurement		24-Oct-23	06-Dec-23	Foundations & U/G MEP Procurement
PRO-1030	Security Electronics & Controls Procurement		14-Dec-23	26-Sep-24	
PRO-1040	Structural Steel Procurement	100	14-Dec-23	06-May-24	Structural Ste
PRO-1020	Architectural Precast Procurement		29-Dec-23	08-Apr-24	Architectural Preca
PRO-1060	Roof Procurement		29-Dec-23	17-Jul-24	
PRO-1050	Security Glazing Procurement	100	29-Dec-23	20-May-24	Security GI
	Cell Modules				
PRE-1040	Preliminary Precast Module Submittals		17-Apr-23	26-May-23	Preliminary Precast Module Submittals
PRE-1041	Precast Module Submittal Review & Approval	10	30-May-23	12-Jun-23	Precast Module Submittal Review & Approval
PRE-7450	Cell Mockup Production	70	13-Jun-23	20-Sep-23	Cell Mockup Production
PRE-7410	Cell Mockup Review & Approval		21-Sep-23	21-Sep-23	I Cell Mockup Review & Approval

Remaining Level of Effort Remai...

Run Date: 14-Mar-23

Actual Level of Effort Actual Work

Critical Remaining Work

♦ ♦ Milesto...

Jackson County Detention Center JE Dunn Construction Company March 3rd-2023 GMP Schedule

			-					-		20	25	-	-	-	-		026
ug	S	Oct	N	Dec	Jan	F	Mar	Apr	М	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan
			- - -				1 1 1						1 1 1 1		1 1 1 1		
			, , ,	1 1 1			1					1			rall P	roject	חח
																ojeci	Dui
			1 1 1	1			1						 				
												1					
				1								1	1		1		
														Ove	rall C	onstr	uctic
		♦ S		ure Co													
				n We		-						, , ,	1 1 1		1 1 1		
				Pen	nane art Up			ыапи	ip			1	1 1 1		1 1 1		
			- - -					♦ P	lannii	ng for	Tran	sition	into	Facilit	у		
				 - -								i 1	;	Anti	cipat	ed W	
			- - - -	1 1 1									•	Sub	stant	ial Co	
							1									Fina Proj	
			- - - -	1 1 1									 		•	Fina	
				1 1 1													
			, , ,	, , ,									, , ,		1 1 1		
			- - -	 									, 		 		
				1								1					
Day	s)		1 1 1	1 1 1													
												1					
 !			 	 								 	 				
			, , , ,	, , ,									, , , ,		, , , ,		
				witch					s Pro	curer	nent		1		1		
				}ener	ator F	Procu	reme	nt					, , , ,		 		
				; 													
			, , , ,	, , , ,									, , , ,		, , , ,		
			1 1 1	1 1 1			1 1 1					1 1 1	1 1 1		1 1 1		
			1	Electi	onics	& C	pntrol	s Pro	curer	nent			, , , ,		, , , ,		
		emer emer		 !									 				
		ireme	1														
		curen					 						 		 		
			1 1 1				 					1	 				
			 									1					
					•			•									
												_					R



OU/Anchor FSED	SW OKC			Page 2 of 5
Activity ID	Activity Name	Orig Start	Finish	2023 2024 2025 ⁰²⁶
, in the second s		Dur		Jan F Mar Apr M Jun Jul Aug Sep Oct Nov Dec Jan F Mar Apr May Jun Jul Aug S Oct N Dec Jan F Mar Apr M Jun Jul Aug Sep Oct Nov Dec Jan
PRE-7420	Precast Module Fabrication & Delivery	140 22-Sep-23	11-Apr-24	Precast Module Fabrication & Delivery
PRE-7650	Precast Module QC/QA Plant Visit	1 05-Dec-23	05-Dec-23	I Precast Module QC/QA Plant Visit
PRE-7660	Precast Module QC/QA Plant Visit	1 16-Feb-24	16-Feb-24	I Precast Module QC/QA Plant Visit
PRE-7670	Precast Module QC/QA Plant Visit	1 11-Apr-24	11-Apr-24	I Precast Module QC/QA Plant Visit
PRE-7460	Initial Precast Cell Module Delivery	0 12-Apr-24		♦ Ihitial Precast Cell Module Delivery
Construction				
JCMO Desigr	Approval			
OWN-5180N	Component Package 2B - Early Footings and Foundations Review	30 23-Aug-23	04-Oct-23	Component Package 2B - Early Footings and Foundations Review
CON-5180	Component Package 2B - Early Footings and Foundations Review Approval (100% DDs)	0	11-Oct-23	Component Package 2B - Early Footings and Foundations Review Approval (100% DDs)
OWN-1620	Component Package 2C Review (100% DDs)	30 24-Oct-23	06-Dec-23	Component Package 2C Review (100% DDs)
OWN-1700	Component Package 2C - Structure & Skin, & Remaining Site Utilities Approval (100% DDs)	0	13-Dec-23	Component Package 2C - Structure & Skin, & Remaining Site Utilities Approval (100% DDs)
OWN-1630	Component Package 3 Review (100% CDs)	30 03-Jan-24	14-Feb-24	Component Package 3 Review (100% CDs)
OWN-1710	Component Package 3 - Finishes Approval (100% CDs)	0	21-Feb-24	Component Package 3 - Finishes Approval (100% CDs)
Design DSN-1000	Component Package 2C - Structure & Skin, Remaining Site Utilities (100% DDs)	100 17-Apr-23	06-Sep-23	Component Package 2C - Structure & Skin, Remaining Site Utilities (100% DDs)
CON-5170N	Component Package 2C - Structure & Skin, Remaining Site Otilities (100% DDS) Component Package 2B - Early Footings and Foundations	60 17-Apr-23	11-Jul-23	Component Package 2B - Early Footings and Foundations
DSN-1030	Component Package 3 - Finishes (100% CDs)	80 07-Sep-23	02-Jan-24	Component Package 23 - Early Foundations
DSN-1020	Component Package 2C - JE Dunn Address & Incorporate Design Comments	3 07-Sep-23	11-Sep-23	Component Package 2C - JE Dunn Address & Incorporate Design Comments
CON-5170	Component Package 28 - JE Dunn Address & Incorporate Comments (100% DDs)	5 05-Oct-23	11-Oct-23	Component Package 2B - JE Dunn Address & Incorporate Comments (100% DDs)
DSN-1040	Component Package 2C - JE Dunn Address & Incorporate Comments (100% DDs)	5 07-Dec-23	13-Dec-23	Component Package 2C - JE Dunn Address & Incorporate Comments (100% DDs)
DSN-1050	Component Package 3 - JE Dunn Address & Incorporate Comments (100% CDs)	5 15-Feb-24	21-Feb-24	Component Package 3 - JE Dunn Address & Incorporate Comments (100% CDs)
Permits				
PERMIT-1000	Land Disturbance and Private Grading Permit	25 21-Nov-22 A	20-Jan-23	Land Disturbance and Private Grading Permit
PERMIT-1010	Land Disturbance and Private Grading Permit	0	20-Jan-23	♦ Land Disturbance and Private Grading Permit
PERMIT-1060	Early Footings and Foundations Permit	20 23-Aug-23	20-Sep-23	Early Footings and Foundations Permit
PERMIT-1020	Structural Permit	20 14-Dec-23	12-Jan-24	Structural Permit
PERMIT-1030	Structural Permits Received	0	12-Jan-24	♦ Structural Permits Received
PERMIT-1040	Building Permit	20 22-Feb-24	20-Mar-24	Building Permit
PERMIT-1050	Building Permit Received	0	20-Mar-24	Building Permit Received
Trade Partner				
TPB-11001	Concrete Trade Partner Selection	30 12-Jul-23	22-Aug-23	Concrete Trade Partner Selection
TPB-5170N	Precast Erection Trade Partner Selection	30 12-Sep-23	23-Oct-23	Precast Erection Trade Partner Selection
TPB-1100	Enclosure Trade Partners Selection	20 14-Dec-23	12-Jan-24	Enclosure Trade Partners Selection
TPB-1120	Remaining Trade Partners Selection	20 22-Feb-24	20-Mar-24	Remaining Trade Partners Selection
Early Sitewor	k Clearing & Grubbing	45 42 Mar 02*	24 Mar 02	
CON-2900	Clearing & Grubbing Clearing and Grubbing Complete ahead of Long Eared Bat Active Season	15 13-Mar-23*	31-Mar-23	Clearing & Grubbing
JED-00100 CON-2890	Clearing and Grubbing Complete anead of Long Eared Bat Active Season Mobilization	0 5 17-Apr-23	31-Mar-23 21-Apr-23	Clearing and Grubbing Complete ahead of Long Eared Bat Active Season Mobilization
CON-5110	Drainage Blanket Aggregate Crushing	90 17-Apr-23	21-Api-23 22-Aug-23	Drainage Blanket Aggregate Crushing
CON-5130	Wick Drain Engineering & Submittals	15 17-Apr-23	05-May-23	Wick Drain Engineering & Submittals
CON-5120	Erosion Control	5 24-Apr-23	28-Apr-23	Erosion Control
CON-2910	Site Demolition	15 01-May-23	19-May-23	
CON-2920	Drainage Blanket Aggregate Installation	45 22-May-23	25-Jul-23	Drainage Blanket Aggregate Installation
CON-2960	Wick Drain System Installation	55 30-May-23	15-Aug-23	Wick Drain System Installation
CON-2930	Site Fills - Building Pads & Surcharge Placement	45 13-Jun-23	15-Aug-23	Site Fills - Building Pads & Surcharge Placement
CON-4880	Site Utilities	231 30-Jun-23	29-May-24	Site Utilities
CON-2940	Surcharge Time (Cal. Days)	45 16-Aug-23	29-Sep-23	Sutcharge Time (Cal. Days)
CON-2950	Remaining Grading Site Fills	60 16-Aug-23	08-Nov-23	Remaining Grading Site Fills
U/G MEP & F	NDs			
Crew 1				
CON-4220	2A CUP - U/G MEP & FNDs	30 14-Dec-23	29-Jan-24	2ACUP - U/G MER & FNDs
CON-4280	Food Service / Laundry - U/G MEP & FNDs	25 30-Jan-24	04-Mar-24	Food Service / Laundry - U/Ġ MEP & FNDs
CON-4200	North Medium / Min Housing (DR 1&2) - U/G MEP & FNDs	24 05-Mar-24	05-Apr-24	North Medium / Min Housing (DR 1&2) - U/G MEP & FNDs
CON-4210	Orientation (DR 3) - U/G MEP & FNDs	19 08-Apr-24	02-May-24	Orientation (DR 3) - U/G MEP & FNDs

OU/Anchor FSED				
				Page 3 of 5
Activity ID	Activity Name	Orig Start Dur	Finish	
00				Jan F Mar Apr M Jun Jul Aug Sep Oct Nov Dec Jan F Mar Apr May Jun Jul Aug S Oct N Dec Jan F Mar Apr M Jun Jul Aug Sep Oct Nov Dec Jan
Crew 2	Fact Madium (Min Llausian (DD 4 E) LVC MED 8 END	20 24 Dec 4	22 22 Jan 24	East Medium / Min Housing (DR 4-5) - U/G MEP & FNDs
CON-4190	East Medium / Min Housing (DR 4-5) - U/G MEP & FNDs	20 21-Dec-2		
CON-4360	East Medium / Min Housing (DR 6-7) - U/G MEP & FNDs	20 23-Jan-2		East Medium / Min Housing (DR 6-7) - U/G MEP & FNDs
CON-4300	Clinic - U/G MEP & FNDs	30 20-Feb-	· ·	Clinic - U/G MEP & FNDs
CON-4290	Medical / Special Needs - U/G MEP & FNDs	30 05-Mar-2	24 15-Apr-24	Medical / Special Needs - U/G MEP & FNDs
Crew 3				
CON-4350	Admin - U/G MEP & FNDs	50 30-Jan-2	24 08-Apr-24	Admin - U/G MEP & FNDs
Structure				
SOG				
Crew 1				
CON-4600	2A CUP - SOG	5 30-Jan-2		1 2Á CUP - SÓG
CON-4380	East Medium / Min Housing (DR 4-5) - SOG	10 06-Feb-2		East Medium / Min Housing (DR 4-5) - SOG
CON-4610	Food Service / Laundry - SOG	10 05-Mar-2		■ Food Service / Laundry - SOG
CON-5140	Clinic - SOG	10 02-Apr-2	· ·	Clinic - SOG
CON-4620	Medical / Special Needs - SOG	10 16-Apr-2		Medical / Special Needs - SOG
CON-4450	East Medium / Min Housing (DR 6-7) - SOG	10 30-Apr-2	,	East Medium / Min Housing (DR 6-7) - SOG
CON-4390	North Medium / Min Housing (DR 1&2) - SOG	15 14-May-		North Medium / Min Housing (DR 1&2)- SOG
CON-4400	Orientation (DR 3) - SOG	5 05-Jun-2	24 11-Jun-24	Orientation (DR 3) - SOG
Crew 2				
CON-3410	Admin / Intake / Courts - Prep & Pour SOG	35 09-Apr-2	28-May-24	Admin / Intake / Courts - Prep & Pour SOG
Precast				
Crew A - Moo	lules & HC			
CON-3950	Dayroom 4 - East Medium / Min Housing - Modules	5 12-Apr-2	4 18-Apr-24	📕 Dayroom 4 - East Medium / Min Housing - Modules
CON-4470	Dayrooms 4 East Medium / Minimum - Walls & HC	20 19-Apr-2	4 16-May-24	Dayrooms 4 East Medium / Minimum - Walls & HC
CON-4630	Dayroom 5 - East Medium / Min Housing - Modules	5 17-May-	24 23-May-24	■ Dayroom 5 - East Medium / Min Housing - Modules
CON-4480	Dayrooms 5 East Medium / Minimum - Walls & HC	21 24-May-	24 24-Jun-24	Dayrooms 5 East Medium / Minimum - Walls & HC
CON-4170	Dayroom 6 - East Medium / Min Housing - Modules	5 25-Jun-2	24 01-Jul-24	🗖 Dayroom 6 - East Medium / Min Housing - Modules
CON-4490	Dayrooms 6 East Medium / Minimum - Walls & HC	20 02-Jul-2	4 30-Jul-24	Dayrooms 6 East Medium / Minimum - Walls & HC
CON-4640	Dayroom 7 - East Medium / Min Housing - Modules	5 31-Jul-2	4 06-Aug-24	Dayroom 7 - East Medium / Min Housing - Modules
CON-4570	Dayrooms 7 East Medium / Minimum - Walls & HC	20 07-Aug-	24 04-Sep-24	Dayrooms 7 East Medium / Minimum - Walls & HC
CON-4070	Medical - Walls & HC	40 05-Sep-	24 30-Oct-24	Medical - Walls & HC
CON-5090	Special Needs - Walls & HC	20 31-Oct-2	4 27-Nov-24	Special Needs - Walls & HC
Crew B - Wa	Is & HC		,	
CON-4460	2A CUP Precast Walls	15 09-Apr-2	4 29-Apr-24	2A CUP Precast Walls
CON-4060	Food Service / Laundry - Walls & HC	20 30-Apr-2	4 28-May-24	Food Service / Laundry - Walls & HC
CON-3940	Dayrooms 1 - West Medium / Min Housing - Modules	5 05-Jun-2		Dayrooms 1 - West Medium / Min Housing - Mcdules
CON-3960	Dayrooms 2 & 1 - East Medium / Min Housing - Modules	5 12-Jun-2		Dayrooms 2 & 1 - East Medium / Min Housing - Modules
CON-4590	Dayrooms 2 - North Medium / Min Housing - Walls & HC	20 19-Jun-2		Dayrdoms 2 - North Medium / Min Housing - Walls & HC
CON-4510	Dayrooms 1 - North Medium / Min Housing - Walls & HC	20 18-Jul-2		Dayrooms 1 - North Medium / Min Housing - Walls & HC
CON-4080	Clinic - Walls & HC	15 15-Aug-		Clinic - Walls & HC
	Dayroom 3 - Orientation - Modules	5 06-Sep-	· ·	■ Dayroom 3¦- Orientation - Modules
	Dayroom 3 - Orientation - Walls & HC	20 13-Sep-	· ·	Dayroom 3 - Orientation - Walls & HC
Crew C - Wa		20 10 00p-	- 10 30(24	
CON-5060	Admin Precast Walls (East)	25 26-Jun-2	24 31-Jul-24	Admin Precast Walls (East)
CON-4160	Admin Precast Walls (West)	45 01-Aug-		Admin Precast Walls (West)
Steel		45 01-Aug-		
CON-3420	Admin / Intake / Courts - Structural Steel	40 29-May-	24 24-Jul-24	Admin / Intake / Courts - Structural Stee
Pour Backs		40 29-iviay-	24-Jui-24	
CON-4530	Davroom 4 - East Medium / Min Housing - Shallow I V/C MED & SOC @ Davr Book	5 10 Apr	4 25-Apr-24	
	Dayroom 4 - East Medium / Min Housing - Shallow U/G MEP & SOG @ Pour Back	5 19-Apr-2	· ·	Dayroom 4 - East Medium / Min Housing - Shallow U/G MEP & SOG @ Pour Back
CON-4680	Dayroom 5 - East Medium / Min Housing - Shallow U/G MEP & SOG @ Pour Back	5 24-May-		Dayroom 5 - East Medium / Min Housing - Shallow U/G MEP & SOG @ Pour Back
CON-4550	Dayroom 1 - North Medium / Min Housing - Shallow U/G MEP & SOG @ Pour Back	5 19-Jun-2		Dayroom 1 - North Medium / Min Housing - Shallow U/G MEP & SOG @ Pour Back
CON-4700	Dayroom 2 - North Medium / Min Housing - Shallow U/G MEP & SOG @ Pour Back	5 26-Jun-2		Dayroom 2 - North Medium / Min Housing - Shallow U/G MEP & SOG @ Pour Back
CON-4560	Dayroom 3 - Orientation - Shallow U/G MEP & SOG @ Pour Back	5 13-Sep-		Dayroom 3 - Orientation - Shallow U/G MEP & SOG @ Pour Back
CON-4710	Medical - Shallow U/G MEP & SOG @ Pour Back	5 31-Oct-2	4 06-Nov-24	Medical - Shallow U/G MEP & SOG @ Pour Back

OU/Anchor FSE				F	Page 4	of 5										
Activity ID	Activity Name	Orig Start Dur	Finish	lon F	Mor		-	23		Oct N			E Mor /	Apr May J	2024	
CON-5100	Special Needs - Shallow U/G MEP & SOG @ Pour Back	5 02-Dec-24	06-Dec-24	Jan F		Apr IVI	Juri	Jui Au	ig Sep			Jan		vpr iviay J	uri Ju	I Auç
Enclosure							i i									
Skin							-									
CON-3500	Zone 1 - CUP, North Dayrooms, & Additional Support - Enclosure	10 30-Apr-24	13-May-24				-							Zo	ne 1 - 1	CUP, I
CON-3510	Zone 2 - East Dayrooms - Enclosure	10 14-May-24	28-May-24												Zone 2	2 - Eas
CON-5080	Admin Glazing - Enclosure	10 04-Oct-24	17-Oct-24				-									
Roof							-									
Crew 1							1									
CON-2700	Dayroom 4 Roof Dry-in	15 17-May-24	07-Jun-24				Ì								Dayro	oom 4
CON-2710	Dayroom 5 Roof Dry-in	15 25-Jun-24	16-Jul-24								+					Day
CON-2730	Dayroom 6 Roof Dry-in	15 31-Jul-24	20-Aug-24				1									
CON-2740	Dayroom 7 Roof Dry-in	15 05-Sep-24	25-Sep-24													
CON-3450	Clinic -Roof Dry-in	20 26-Sep-24	23-Oct-24				-									
CON-2690	Dayroom 3 Roof Dry-in	15 11-Oct-24	31-Oct-24				1									
CON-3440	Programs / Female Medical / Special Housing - Roof Dry-in	21 01-Nov-24	03-Dec-24													
Crew 2		· · · ·					-									
CON-3480	CUP - Roof Blocking & Dry-in	10 30-Apr-24	13-May-24											🗖 ¢u	P - Ro	of Blo
CON-3460	Food Service / Laundry / Receiving Roof Blocking & Dry-in	12 29-May-24	13-Jun-24				1								I Foo	dSer
CON-2660	Dayroom 1 Roof Dry-in	15 12-Jun-24	02-Jul-24			i										Dayroo
CON-2680	Dayroom 2 Roof Dry-in	15 18-Jul-24	07-Aug-24													
CON-3470	Admin / Intake / Courts - Roof Blocking & Dry-in (East)	35 22-Aug-24	10-Oct-24				1									
CON-5070	Admin / Intake / Courts - Roof Blocking & Dry-in (West)	35 11-Oct-24	02-Dec-24				-									
Interior Finis	hes	· · ·					1									
Support							-	-								
СМU											+					
Before Pre	ecast Walls															
CON-4840	0 Kitchen & Laundry - CMU	25 19-Mar-24	22-Apr-24				-							🔳 Kitche	n & La	undry
CON-4860	0 Special Needs - CMU	30 30-Apr-24	11-Jun-24				1								Spe	cial Ne
CON-4870	0 Medical Housing & Infirmary - CMU	30 30-Apr-24	11-Jun-24												Med	lical H
Crew 1		· · ·									+					
CON-4720	0 Transportation - CMU	10 11-Jul-24	24-Jul-24			Ì	-									Tra
CON-4730	0 Re-entry - CMU	10 25-Jul-24	07-Aug-24				-									Ļ I
CON-4730 CON-4740 Crew 2 CON-4750 Crew 3	0 Intake S - CMU	10 08-Aug-24	21-Aug-24				1									
Crew 2		· · ·														
CON-4750	0 Visitation - CMU	15 06-Sep-24	26-Sep-24													
Crew 3		· ·					-									
	0 Admin - CMU	5 25-Jul-24	31-Jul-24				-									A D
Crew 4		· · ·					1									
CON-4780	0 Intake W - CMU	15 25-Jul-24	14-Aug-24				-									i i i i i i i i i i i i i i i i i i i
CON-4810	0 Records - CMU	10 15-Aug-24	28-Aug-24													
Dayrooms		· ·				Ì										
CON-4820	Dayrooms 1 - 7 - CMU	50 17-May-24	29-Jul-24				-									
CUP																
CON-3530	CUP Buildout	60 14-May-24	07-Aug-24				-	-								i 🛋
CON-5160	Set & Terminate Switchgear	10 12-Nov-24	25-Nov-24								+					
Food Servic	ce / Laundry / Receiving	II	- '				-									
CON-3720	Rough-in	80 14-Jun-24	07-Oct-24				-									<u> </u>
CON-3730	Finishes	60 26-Aug-24	18-Nov-24													
CON-4910	JED Pre-Punch	10 19-Nov-24	04-Dec-24				-									
Programs /	Female Medical / Special Housing			1		!					+					
CON-3760	-	100 07-Nov-24	02-Apr-25													
CON-3770		80 30-Jan-25	21-May-25													
CON-4920		10 22-May-25	05-Jun-25													
		· · · ·		111			1	1	1.1	1 1	1	1 1			1	1



	SW OKC			The balance	ii	Page 5 of 5			i			~
ID	Activity Name	Orig S Dur	start	Finish	Jan E	Mar Apr	2023 M Jun Ju		Oct Nov Dec Jar	n E Mar	Apr May	20 Jun
CON-3740	Rough-in	100 0)7-Nov-24	02-Apr-25								
CON-3750	Finishes	80 0)4-Feb-25	27-May-25								
CON-4930	JED Pre-Punch	10 2	28-May-25	10-Jun-25								
ousing		, ,										
Crew 1												
Dayroom 4	,											
CON-3600			10-Jun-24	01-Oct-24								
CON-3610)2-Oct-24	27-Dec-24								
	JED Pre-Punch	10 3	30-Dec-24	13-Jan-25								-
Dayroom 5												
	Rough-in		17-Jul-24	06-Nov-24								-
CON-3630)7-Nov-24	05-Feb-25								
	JED Pre-Punch	10 0)6-Feb-25	19-Feb-25								
Dayroom 6	Describe in			40.5								
CON-3660	-		21-Aug-24	13-Dec-24								
CON-3670			16-Dec-24	12-Mar-25	-							
	JED Pre-Punch	10 1	13-Mar-25	26-Mar-25								-
Dayroom 7	Pough in	00.0		22-Jan-25								
CON-3680	-		26-Sep-24		-							-
	Finishes JED Pre-Punch)8-Jan-25)3-Apr-25	02-Apr-25								
		10 0	5-Api-25	16-Apr-25								
Crew 2 Dayroom 1												-
CON-3540	Boughin)3-Jul-24	24-Oct-24								-
CON-3540 CON-3550			25-Oct-24	24-Oct-24 23-Jan-25								-
	JED Pre-Punch		24-Jan-25	06-Feb-25								
Dayroom 2			_ / Gan 20									
CON-3560	Rough-in	80 0)8-Aug-24	02-Dec-24								-
	Finishes)3-Dec-24	27-Feb-25								1
	JED Pre-Punch		28-Feb-25	13-Mar-25								Ì
Dayroom 3			-									
CON-3580	Rough-in	50 0)1-Nov-24	15-Jan-25								-
	Finishes		16-Jan-25	13-Mar-25								-
	JED Pre-Punch		14-Mar-25	27-Mar-25	1							
dmin	·			, 								-
CON-3800	Rough-in	90 0)3-Sep-24	10-Jan-25	=							
CON-5150	Elevator Installation (3)	60 2	29-Oct-24	27-Jan-25								-
	Finishes)3-Dec-24	08-May-25								
	Master Control Buildout	20 0)3-Dec-24	31-Dec-24								-
CON-5030	JED Pre-Punch	10 0)9-May-25	22-May-25				· · · · · · · · · · · · · · · · · · ·			l	
e Sitework												
	Parking Lots, Sidewalks, Curbs, Asphalt)8-May-24	11-Jul-24								÷
	Landscaping	60 0)4-Oct-24	31-Dec-24								-
mmissionin												-
	MEP Reliant FFE Install	20 2	28-Feb-25	27-Mar-25				· · · · ·			!	
OSE-1010	CxA Inspections / Test		21-Mar-25	02-Jun-25								
OSE-1005	Systems Startup		28-Mar-25	08-May-25								-
OSE-1015	SEC/DEC Pre-Test		25-Apr-25	06-Jun-25								÷
_OSE-1020	Design / Owner Final Punchlist)9-May-25	06-Jun-25								-
LOSE-1025	Certificate of Occupancy Inspections	10 2	23-May-25	06-Jun-25		i	i	i i i		- i	1 1	1

Cummunum





JE DUNN • AXIOM • DLR GROUP DESIGN-BUILD TEAM

13-22116-00 10/31/2022

JACKSON COUNTY DETENTION CENTER

Exhibit 5 - Sequence

 \dots End of Exhibit 5

THIS INFORMATION IS CONCEPTUAL IN NATURE AND IS SUBJECT TO ADJUSTMENT PENDING FURTHER VERIFICATION AND CLIENT, TENANT AND GOVERNMENT AGENCY APPROVALS. NO WARRANTIES OR GUARANTEES OF ANY KIND ARE GIVEN OR IMPLIED OF THE ARCHITECT.





Jackson County Detention Center Exhibit 7 - GMP Clarifications 03/14/2023

General

- This Guaranteed Maximum Price (GMP) Proposal is based on Schematic Documents dated February 10th, 2023, and supporting documents as outlined in the attached Exhibit B –Contract Documents including listed Drawings and Specifications. The GMP is based on Option #3, which includes 1,000 beds and the recommended VE items.
- 2. This GMP is based upon the attached Exhibit 8 Criteria Modification Log that highlights Owner approved criteria modifications.
- 3. The GMP Proposal is based on the Geotechnical Engineering Report provided by CFS dated September 8th, 2022.
- 4. The Master Schedule includes a total of Ninety (90) lost weather days, based on NOAA's 10-year average for the Kansas City region. A lost day can occur during the weather event itself, as well as days following the event such as muddy conditions after rain, or snow and ice build-up following a winter storm which impacts critical path activities. Lost weather days exceeding this allowance shall be considered a Force Majeure Event.
- 5. The Project Site is assumed to be free of any unknown above ground or below ground hazardous materials and/or hazardous conditions, as well as any environmental and/or endangered species, flora, fauna, or wetlands requiring mitigation. The Design/Builder is aware of the two wetlands located on site and the existing long eared bat population that requires the site to be clear of trees prior to March 31st, 2023. This GMP assumes the trees to be removed prior to this date.
- 6. The GMP is based upon using the following Teamed Trade partners who were selected based on a best value selection process, those trade partners are as follows:
 - a. Kissick Construction Mass Excavation (Lump-Sum)
 - b. Cornerstone Detention Security Electronics (Lump-Sum)
 - c. Cornerstone Axiom JV LLC. Modular Cells Supply (Lump-Sum)
 - d. Mark One Electric Electrical (GMP)
 - e. US Engineering Mechanical (GMP)
 - f. American Fire Protection Fire Protection (GMP)
 - g. CML Security Detention Equipment (Lump-Sum)
 - h. Flynn Midwest Membrane Roofing (Lump-Sum)
 - i. Enterprise Precast Precast Wall Panels/Hollow-Core Supply (Lump-Sum)
 - j. Midland Marble and Granite Tile (Lump-Sum)
- 7. Per letter received from JCDC on January 24, 2023, titled Jackson County Detention Center -JE Dunn Self Perform, the GMP includes budgets for the concrete, masonry, precast erection, miscellaneous steel, and carpentry from JE Dunn Self-Perform Group/Axiom Construction Group. These scopes of work will be procured after the GMP using the best-value approach as described in our Design-Build agreement.
- 8. The GMP includes Cornerstone, Axiom JV LLC as a 59%/41% joint venture. Based on past conversations with Jackson County compliance, this JV will be counted as 100% MBE for the precast cell module fabrication Scope of Work.

- 9. Included in the GMP is a full-size cell mock-up to be reviewed at the cell module plant.
- 10. Included in the GMP is a functional exterior elevation mock-up that will include precast, curtain wall/glass, and other skin components that can be tested for functionality on site.
- 11. The final Contractor Utilization Plan will be reconciled with the final submission of Component Package 3.
- 12. A \$90,000 allowance for ~100 LF of 12' tall, galvanized chain link fencing is included at 3 locations. Each location includes a 4'x7' Tymetal 2150 Pedestrian Gates. This allowance is included in the Owner Contingency amount and will be moved to a CSI division once final design of the area is complete and formal documents can be bid.
- 13. Component Package 1 details work that pertains to continuation of design documents, site demolition, site development and earthwork that is directly tied to this GMP submission. Component Package 1 does not include a complete foundation package. This package will be brought forward an introduced as Component Package 2B.
- 14. Component Package 2A details work that pertains to engineering, detailing, mockups, and early procurement of long lead material that are directly tied to this GMP submission. The balance of Component Package 2 shell and core package of the project will be delivered as Component Package 2C.
- 15. If Component Package 1 and 2A are not approved simultaneous there will be a schedule and cost impact incurred by the project.

Program / Design Criteria Package Clarifications

- 1. Space # 5.511 Beverage Counter is excluded from project. We do not feel it is needed as space #5.410 Beverage Counter is in the same proximity.
- 2. Several rooms in the Room Data Sheets appear to have cabinet "Material" and "Worksurface" material reversed. In lieu of what is defined in the room data sheet we have assumed the following:

A 107 Records Window: Wood Cabinet/ Solid Surface Worksurface A 113 Mother's Room: Wood Cabinet/ Solid Surface Worksurface B 209 Workroom: Plastic Laminate Cabinet/ Solid Surface Worksurface B 210 Kitchen: Plastic Laminate Cabinet/ Solid Surface Worksurface B 217 Workroom: Plastic Laminate Cabinet/ Solid Surface Worksurface B 219 Break & Vending: Plastic Laminate Cabinet/ Solid Surface Worksurface B 223 Workroom: Plastic Laminate Cabinet/ Solid Surface Worksurface B 227 Break & Vending: Plastic Laminate Cabinet/ Solid Surface Worksurface C 301 Lounge: Plastic Laminate Cabinet/ Solid Surface Worksurface C 302 Classroom: Plastic Laminate Cabinet/ Solid Surface Worksurface C 303 Meeting Room: Plastic Laminate Cabinet/ Solid Surface Worksurface C 304 Computer Lab: Plastic Laminate Cabinet/ Solid Surface Worksurface C 310 Laundry: Plastic Laminate Cabinet/ Solid Surface Worksurface C 316 Break/Dining/Vending: Plastic Laminate Cabinet/ Solid Surface Worksurface C 318 Mother's Room: Wood Cabinet/ Solid Surface Worksurface D 401 Control Room: Plastic Laminate Cabinet/ Solid Surface Worksurface E 502 Main Armory: Plastic Laminate Cabinet/ Solid Surface Worksurface E 508 Law Enforcement Paperwork Area: No Base Cabinet/Solid Surface Worksurface E 513 Transfer Counter: No Base Cabinet/ Solid Surface Worksurface

E 531 Kitchen: Plastic Laminate Cabinet/ Solid Surface Worksurface E 539 Release Waiting: No Base Cabinet/Solid Surface Worksurface E 542 Large Open Workstation: Plastic Laminate Cabinet/ Solid Surface Worksurface F 622 Beverage Counter (Inmate): Plastic Laminate Cabinet/ Solid Surface Worksurface F 624 Issue Room: Plastic Laminate Cabinet/ Solid Surface Worksurface F 633 Break Area: Plastic Laminate Cabinet/ Solid Surface Worksurface H 802 Exam Room: Plastic Laminate Cabinet/ Solid Surface Worksurface H 803 Treatment Room: Plastic Laminate Cabinet/ Solid Surface Worksurface H 804 Lab: Plastic Laminate Cabinet/ Solid Surface Worksurface H 806 Dental Suite: Plastic Laminate Cabinet/ Solid Surface Worksurface H 807 Dental Lab & Workroom: Plastic Laminate Cabinet/ Solid Surface Worksurface H 809 Medication Storage: Plastic Laminate Cabinet/ Solid Surface Worksurface H 811 Multi-Purpose Room: Plastic Laminate Cabinet/ Solid Surface Worksurface H 813 Food & Bevg Staging/ Dist.: Plastic Laminate Cabinet/ Solid Surface Worksurface H 822 Issue Room (Medical): Plastic Laminate Cabinet/ Solid Surface Worksurface H 834 Work Alcove: Plastic Laminate Cabinet/ Solid Surface Worksurface H 838 Large Open Workstation: Plastic Laminate Cabinet/ Solid Surface Worksurface J 937 Mail Room: Plastic Laminate Cabinet/ Solid Surface Worksurface J 946 Beverage Counter: Plastic Laminate Cabinet/ Solid Surface Worksurface

- As approved through the VE process, the reduction in dayroom sizes and inclusion of two (2) ADA cell per unit. An inmate toilet was deleted from each dayroom in program spaces Male Max (6.215), Male Seg (6.313), Male Medium/Minimum (6.512) including proposed dorm, Female Medium/Minimum (6.612) and Female Special Housing (6.414).
- 4. As identified through our workshops, the design of the Intake Vehicle Sallyport (Program space # 5.101) and Transportation Vehicle Sallyport (Program Space # 5.102) have been modified to includes a single shared interior space that can accommodate both functions. The space is designed to include one vehicle entry door and one vehicle exit door. This revised Combined Vehicle Sallyport has been designed to allow for parking of 6 patrol vehicles. It also is designed to accommodate parking for 1 bus. This combined space shall be provided as sized on Schematic Design Drawings included with this proposal. The modifications defined herein shall take precedence over SF requirements, vehicle parking counts, vehicle door requirements and separation requirements defined in the Design Criteria Package.
- 5. Vol. 1, Section 5.100 indicates that intake sallyport shall have separate entry and exit overhead doors but room data sheet E 500 calls for Tri-Fold Sallyport Doors. Specification section 32 31 15 suggests Four-Fold Doors. We have provided solid four-fold doors at the combined Intake Vehicle Sallyport/ Transportation Vehicle Sallyport in lieu of mesh type as specified.
- 6. Vol. 1, space program 5.000 Intake/Transportation/Release Vehicle Sallyport indicated that a separate security vestibule for emergency vehicles to access the central clinic and healthcare area. The current proposal assumes that emergency vehicles will park within the transportation vehicle sallyport in one of the designated Bus or Van parking spaces. Entrance from the Transportation vehicle sallyport into the building includes a secure pedestrian sallyport with access to the corridor adjacent to Infirmary Clinic that is sized appropriately for emergency personnel access.

- 7. Room Data Sheets B 207 Standard Open Workstation, B216 Large Open Workstation, & E 534 Standard Open Workstation do not call for casework, we have excluded casework work surfaces at these locations (assumed to be Owner provided FF&E).
- 8. Proposal based upon the use of Cornerstone Detention to produce Modular Precast Concrete cells per spec section 13 34 23. Modules will be constructed at a remote job site that will not be PCI or NPCA certified.
- 9. Proposal is based upon the use of Enterprise Precast for architectural and structural precast panel supply and hollow-core and double-T supply. Enterprise currently has limited PCI certification due to an acquisition of a local Kansas City precast plant. The architectural panel with integral color, form liners, sandblast/acid etch located at the south elevation will be cast in their PCI certified plant in Omaha. Precast Double-T's and hollow-core will be manufactured in PCI certified plants. The remainder of the panels will likely be cast in the new plant with is APA certified. This plant is in the process of obtaining PCI certification and may achieve such prior to production but this cannot be guaranteed.
- 10. Heated slab at combined Intake Vehicle sallyport and Transportation Vehicle sallyport (Room Data Sheet Numbers E 500 and E 501) is limited to the drive path in from the parking lot access drive to the Combined Sallyport vehicle entry door and the drive path from vehicle exit door of combined vehicle sallyport out to the vehicle gate located in the fence.
- 11. For Space # 8.125 Staff lockers there is no room data sheet provided. We have included 32 metal lockers 18" wide x 18" Deep x 3' high. Lockers will be arranged in a double-tier configuration.
- 12. Included in GMP are 125 male lockers 18 x 24 x 6'H and 69 female lockers at 18 x 24 x 6'H with integrated bench and boot storage drawer in the Men's 3.201 and Women's locker rooms 3.201. An additional 3 female and 7 male 18 x 24 x6'H lockers without integrated benches for accessibility are provided for a total of 72 female and 132 male for total of 204 lockers per the DCP.
- 13. As there is no Room Data Sheet for A 117, we have used the Room Data Sheet for B216 Large Open Workstation as the basis of the GMP.
- 14. As there is no Room Data Sheet for B 215, we have used the Room Data Sheet B205 Small Office as the basis of the GMP.
- 15. As there is no Room Data Sheet for J 926, we have provided an eyewash station.
- 16. As there is no Room Data Sheet for E 505, we have used Room Data Sheet E 543 1-Person Holding Cell as the basis of the GMP.
- 17. All cells provided with interior height to bottom of ceiling at 8'-0". Bottom of surface mounted ceiling devices/ fixtures will be lower than 8' above finished floor.
- 18. Average height to bottom of the dayroom roof structures in dayroom housing to be 22-'4" at typical 2 tier housing units.
- 19. The program calls for 3 each of Space #5.507, 16-Person Group Holding Cells (Room data sheet #E 537). Our proposal only includes 2 of these cells. We have excluded the requirement for automatic drop-down vinyl curtains to cover or block view based upon proposed configuration of these cells.
- 20. Added approximately 1,500 square foot Virtual Reality training room.

Sitework

- 1. One entrance off US Highway 40 is included in the design. Two entrances off Ewing Avenue are provided.
- 2. Finished Floor Elevation is assumed to be at 762.50, which is 1'.5" above the 500-year floodplain.
- 3. Per the geotechnical report conducted by CFS, alluvial soils are present on site due to the nature of the Blue River. Due to this, there is a long-term settlement concern that will require the use of prefabricated vertical drains (Wick Drains) to be installed under the building footprint and locations at site utilities. The GMP currently includes a wick drain triangular spacing of 4' underneath the building footprint and wick drain 9' triangular spacing under all other hardscapes. Wick Drain spacing correlates with the amount of time the existing fill will need to settle prior to construction activities proceeding.
- 4. 122 Public and 412 Staff Parking Spaces are provided.
- 5. The water meter vault has been included in this GMP. The water meter assembly should be procured by Jackson County through the city/local utility company and installed once all fees are paid.

Foundations and Structure

- 1. Raised slabs have been included for officer workstations within the dayrooms and at the Intake slab in the administration building.
- 2. Structures consist of cell modules, architectural/structural precast, double-T's, CMU, and hollow core. The administration building will consist of structural steel with a slab on metal deck for the 2nd floor.

Enclosure and Roofing

- Clerestory windows at Stage 1-3 Housing and Juvenile Housing are provided via rooftop clerestory light wells. Light wells shall be doghouse structures comprised of cold formed metal framing applied on top of precast roof structure. Openings in precast structure shall be provided for light to enter space. Security will be provided via woven wire rod assemblies attached to precast structure.
- 2. GMP includes an adhered gray Thermoplastic-Polyolefin (TPO) roof that achieves a minimum Rvalue of 30. This includes a 2.7" base layer of Polyiso with tapered insulation. Our teamed trade partner Flynn, has confirmed a vapor barrier is not required to provide a full warranty with a gray TPO roof on this project.

Partitions and Finishes

 Where room data sheets call for gypsum board and high impact gypsum board partitions, we have excluded furring and gypsum board at locations where we have provided masonry or precast wall partitions/ building perimeter. Except in spaces accessible to the public, courts and two-story administration building. 2. CMU partitions have been included in various secure areas in lieu of precast. These areas include housing area showers, housing area restrooms, Stage 1-4 Male Special Needs, the medical/clinic area, Kitchen/Laundry, intake, and visitation.

Specialties, Equipment and Furnishings

- 1. We have included nurse call functionality at locations as indicated through the use of detention intercom system.
- 2. Laundry equipment space has been sized for a total inmate population of approximately 1,800 and is based on a 5-day week operation, 35 hours, with inmate clothing changes 3 times a week, bed linens 1 change a week, terry goods 3 changes a week, and miscellaneous items 2 changes a week. GMP currently includes 4 160 pound, 1 105 pound, and 1 45 pound washer/extractors and 5 170 pound and 1- 45 pound dryers. This is based on the 1256 bed count and additional washer/extractors and dryers would be needed at the time of expansion.
- 3. The kitchen is designed to prepare breakfast, lunch, and dinner for an initial population of 1,256 plus staff with MEP provisions for future expansion of up to 500 additional inmates. Additional equipment will be needed for expansion beyond the 1,256-bed count. The kitchen will function as a cook to serve with tray make-up using insulated trays delivered in carts.
- 4. Cooler, Freezers, and dry storage rooms shall be located inside the kitchen in close proximity to receiving doors.
- 5. A separate area included for special diets will provide separation for Kosher food.

Mechanical, Plumbing and Fire Sprinkler

- The smoke management system has been designed using an egress time of 20 minutes for an individual housing unit and a fire load of 1,000 KW. resulting in 40,000 CFM or smoke exhaust. Design is based of off the dayroom smoke control analysis questionnaire received from JCDC on January 30th, 2023. Assumptions for the smoke control system are as follows:
 - a. This analysis assumes normal fire conditions.
 - b. This analysis assumes one normal fire condition at a time in a housing unit.
 - c. The GMP includes design for 40,000 total CFM for smoke control in each 2-level dayroom.
- The 4-pipe water chilled hydronic HVAC System selection was based on utilizing the Federal Energy Management Program (FEMP) Building Life Cycle Cost methodologies and has been followed over a max 40-year study lifecycle with replacement costs applied at year 20. Input has been received from our Mechanical teamed trade partner on initial costs, maintenance costs, and replacement costs.
- 3. Mechanical Equipment located on the roof is currently screened with taller parapet precast walls. No decorative metal screening has been included in this GMP.

Electrical/Low Voltage/Security Systems

1. The GMP includes utilizing a Milestone video management server with Vicon cameras.

- 2. Reference the attached Exhibit 11 JCDC Systems Responsibility Matrix for additional clarity regarding delineation between this proposal and Owner provided work.
- 3. Only rough-in (conduit) has been included for the distributed antenna system (DAS)- DAS is Owner Provided.
- 4. We have included a two (2) post rack for contractor provided patch panels and fiber terminations in each IDF room as well as the equivalent of 1.5 KVA UPS capacity at each IDF room for Owner provided equipment. In addition, we have included a 16 KVA UPS at the MDF room to support Owner provided equipment.

Exclusions:

- 1. Costs associated with delays resulting from adjacent project operations and infrastructure work, which is not a part of, or under control of, this Design/Builder.
- 2. State, County, and Local Sales or Use Taxes.
- 3. Financing Costs.
- 4. Property acquisition costs and fees.
- 5. Guard services or security services.
- 6. Demolition of existing buildings and site infrastructure, including existing power poles. This GMP includes site clearing and demolition of existing mobile home pads.
- 7. Removal of unforeseen structures or obstructions.
- 8. All utility service line extensions to the project site including domestic water, fire suppression, sanitary sewer, storm sewer, electric, natural gas, and fiber/telecommunications. All utility service company capital costs, development fees, tap/service connection fees, investment fees, inspection fees, or charges of any kind are excluded. Coordination with responsible utility providers is assumed to be by JCDC or Jackson County.
- 9. Water meter assembly.
- 10. On-site natural gas main line to the meter and gas meter assembly.
- 11. Labor to unload or install Owner furnished equipment, and dumpsters for pallets, crating and packaging.
- 12. Environmental study of any kind.
- 13. Hazardous material abatement.
- 14. Commissioning and specialty consultants.
- 15. Rental of adjacent property or construction staging/parking.
- 16. Laboratory mockups: Full-size project specific physical assemblies constructed and tested at a testing facility to verify performance characteristics.
- 17. 08 62 00 Unit Skylights:
 - A. 1.3, A Fall Protection (All units have security bars, deemed not required). Not needed as the skylights have security bars incorporated and act as fall protection devices.
- 18. 07 72 00 Roof Accessories:
 - A. A1.2, A.4 Integral Spring-type vibration isolators. Presumed that this this is covered with mechanical specifications.
 - B. 1.2, A.5 Wind Restraint Straps
 - C. 1.2, B.4 Wind Restraint Straps

- 19. 1.2, J Roof Walkway: Formed from aluminum sheet. Standard roof walking pads have been included in the roof spec. 08 62 00 Unit Skylights:
 - A. 1.3, A Fall Protection (All units have security bars, deemed not required)
- 20. Clerestory windows at Space #s 5.202 Open seating (Intake), 5.216 Open holding (Intake), 8.307 Dayroom (Medical).
- 21. Operable windows at dayroom or recreation areas. Recreation areas have access to fresh air via partial woven wire rod ceiling enclosure assembly.
- 22. Vol. 1, Section 2.5.7 Intake Vehicle Sallyport calls for physical separation between law enforcement vehicles and inmates with the sallyport. The program does not support this requirement. We have excluded this physical separation.
- 23. We are not including the traffic signal at US HWY 40. Traffic Study suggests the new Detention Center will not need a traffic light. If there is a new facility built (i.e., Sheriff's Office) on the current development the traffic study will have to be reviewed and mostly likely will require a traffic signal.
- 24. Room Data Sheet J 955 calls for Dedicated HVAC units at Branch Electrical Rooms. We have excluded dedicated HVAC units at these locations and have instead provided cooling from AHU/RTUs serving adjacent spaces.
- 25. Room Data Sheet E 500 calls for redundant HVAC system. We have excluded this from our proposal. HVAC for the Intake Vehicle Sallyport will be heat and vent only.
- 26. Space Program 5.101 Intake Vehicle Sallyport Comments calls for a heated slab. Room Data sheet E 500 Calls for in slab snow melt system at Intake Vehicle Sallyport. This is an interior heated space, so we have excluded this from our proposal.
- 27. Room Data Sheets H814 and H815 call for medical headwall units at Infirmary Cells. Based upon discussions with JCDC Partners we have excluded headwalls and have provided room for bottle storage near the Infirmary.
- 28. Bullet Resistant Glazing at exterior of building including primary entrance and judge's offices.
- 29. Area of refuge enclosed fence area. In almost every instance, evacuation required at housing units will be accomplished from one space to an adjacent housing space.
- 30. Cost of construction for the Gas Utility Service Provider to extend services to the meter location located adjacent to the Central Utility Plant. This includes the cost of the meter itself.
- 31. Cost of construction for the Electrical Utility Service Provider to extend services to the transformer location. This includes the cost of the transformers itself.
- 32. Dumbwaiters per Vol. 2 Spec section 14 10 00.
- 33. Wheelchair Lifts per Spec Section 14 42 00.
- 34. Vol. 2, Spec Section 13 42 23 requirement that production facility shall be certified by PCI or NPCA.
- 35. Rooftop mechanical penthouse per Room data sheet J 959. Equipment shall be roof mounted and have enclosures for hydronic piping where required.
- 36. Room Data Sheet call for stainless steel partitions and doors at coolers and freezers. We exclude stainless steel partitions and doors and have included cooler/ freezer manufacturers standard insulated wall assembly with galvalume face panels.
- 37. Glazed wall between Space # 3.212 Break/Dining/Vending and adjacent corridor as called for per Room Data Sheet C 316. Room configuration does not support this.
- 38. Access floor at courtroom well spaces as called for in room data sheets E 526 and E 527.

- 39. Automatic glass sliding doors at space #1.101 staff and public entry vestibule as called for per Room Data Sheet A 100. We have provided aluminum storefront entrance doors with ADA operators as required.
- 40. Double doors at Space #s 5.301, 5.302, 5.303 for courtrooms and associated vestibules per Room Data Sheet sheets E 525, E 526 & E 527. We have provided single doors.
- 41. Cart washing machine as indicated per room data sheet J 921. We have included a cart washing area with hose reel and floor trough.
- 42. OFOI Fixtures, Furnishings and Equipment including but not limited to the following:
 - A. Exterior tables and chairs per RDS C 316 Break/Dining/Vending
 - B. Trash Compactor and Dumpsters
 - C. Vending Machines
 - D. Dental equipment including lab equipment, dental chairs, compressor, vacuum system, x-ray equipment, x-ray viewers and custom radiology dental casework. (We have included rough in of utilities and final connections after installation).
 - E. Exam room tables with fixed vital station
 - F. Hospital Beds
 - G. Automatic chemical dispenser system for laundry equipment. We have included laundry equipment equipped to receive chemicals from the Owner provided system.
 - H. Janitor Closet Chemical Dispensers
 - I. Lobby Queuing system stanchions
 - J. Open detention moveable seating
 - K. Wellness room fitness equipment including treadmills, elliptical machines, stationary bikes, stair masters, free weights/bars, and squat racks.
 - L. Ozone Sanitation Cabinets
 - M. Metal Shelving and Storage Racks
 - N. Property Storage Rack, Property Storage Bags, Property storage Shelving, Property Storage Bins and Secure Property Storage Cabinets.
 - O. CERT Equipment Lockers and Storage Cabinets
 - P. Residential Appliances (Refrigerators, Medical Storage Freezer, Commercial washer/dryer at Inmate Property Storage and Locker Rooms, Microwaves.
 - Q. Movable public seating
 - R. Tables, chairs, children's chairs, children's tables, movable sofas, lounge chairs, coffee tables, worktables, work benches, Library tables, library chairs, interior courtroom flagpoles and bases.
- 43. Audio Visual and IT equipment including but not limited to the following:
 - A. Telephones and VOIP Phone Devices
 - B. Video Visitation Equipment/ Video Visitation Kiosks
 - C. Inmate Phone System
 - D. Video Conferencing Equipment- includes inmate system and tele-med/psych/courts system
 - E. Televisions and AV Flat Panels Displays and associated mounting brackets
 - F. Lobby Electronic Information Monitors
 - G. Interactive Wayfinding Digital Signage
 - H. Courts presentation system, electronic docket system, evidence presentation system, court recording system (JAVS)

- I. Ceiling projectors
- J. Printers
- K. Cash bond (Bonding) Kiosk
- L. Visitation Appointment Kiosk
- M. Money Deposit-Inmate Accounting Kiosk
- N. Magnetometers
- O. Metal detectors
- P. Body Scanners
- Q. X-Ray Machines
- 44. Nurse Call/ Code Blue System per Spec section 27 52 23. See clarifications for nurse call functionality provided via detention grade intercom system.
- 45. Volume 1 of the DCP, section 2.5.18 defines requirements for Rear Chase including motion detectors that will notify central control of any movement. We have excluded motion detectors at rear chases because we have included door control to limit movement from inside to outside the secure perimeter at all rear chase locations.
- 46. Special Inspections. Provided by the Owner
- 47. Mechanical, electrical, and plumbing equipment decorative metal screening.
- 48. A centralized UPS system as noted in the Design Criteria Package Section 3.2 General Design and System Criteria.
- 49. Engineering, wiring, and devices for the distributed antenna system (DAS).
- 50. Sizing of generators for future expansion.
- 51. Sound attenuating enclosures for Emergency Generators.
- 52. Building FAA Permit
- 53. Floodplain Development Permit
- 54. Conditional Letter of Map Revision Permit (CLOMR-F)
- 55. Drop down vinyl curtain in 16-person Group Holding Cells, Room Data Sheet E537.
- 56. Harmonic Filtration at individual VAVs.
- 57. Smoke Control systems at Intake and Transportation.
- 58. Full-Size courtroom mock-ups.







Request #	Submitted	Request Title	Modification Request	Current Text/Perposed Text
1	07.29.2022	2nd Level ADA Cells	Per Workshop #1 dated 06.21.2022, the Design-Build Team recommends that the requirement for all Medium & Minimum Housing Cells, inorder to be ADA compliant as indicated in the Design Criteria Package under the Room Data sheets be revised to note that only cells located on the 1st level are to be ADA compliant, and all 2nd level cells are non-ADA. ADA compliant cells on an upper level would require ADA circulation access via elevator or wheel chair lift which would add additional square footage, equipment and construction cost to the design. There is additional savings in providing more typical combination plumbing fixtures in lieu of ADA Accessible combo fixtures in the 2nd level cells. Note: Request would also include that all housing cells on an upper level be non-ADA.	Current Text:Table 24: 6.503 4-person Occupancy ADA Cell (16 Units) Table 24: 6.603 4 Person Occupancy ADA Cell (14 Units) Proposed Text: Table 24: 6.503 4-person Occupancy Cell (16 Units) Comment: wet cell w/ A
2	07.29.2022	Glazing Clarification	The detention glazing specification lists 14 types of detention glazing (SG-1through SG-14). The room data sheets only reference three types. (SG-1, SG-2, SG-3). The Criteria package and room data sheets define detention levels with SG-1 being ASTM 1915 60 minute glazing, SG-2 being 40-minute detention glazing, and SG-3 being 20-minute detention glazing. The standards imply that SG-1 is used on the exterior detention barrier, SG-2 is used on the dayroom detention barrier, and SG-3 is used on the cell detention barrier. We are requesting the documents list 4 types of detention glazing with the attack ratings being the distinguishing factors. These values (SG-1 through SG-4) will coincide with the room data sheets. Different assemblies for these glazing will be required. For example, SG-3 glazing in a fire rated wall will differ in assembly from SG-3 glazing in an exterior wall, but the attack rating will correspond with the room data sheets and the defined theory.	Current Text: SG-1-SG-14 with corresponding test requirements and attack rating.
3	07.29.2022	SEC/IT Room Locations	Telecom rooms are to be located within 295' of the end user devices in lieu of 150' listed in RFP. Cable connecting telecom rooms will be fiber, and not subject to CAT6 cable distance limitations. Fiber does not have the distance or bandwidth limitations that CAT6 copper cabling does. The Division 27 Trade Partner will be installing a fiber backbone between SEC/Telecom rooms to maintain electrical isolation between rooms. Refer to attached page form the BICSI TDMM version 14, Chapter 5 page 17 describing the cable limitations at 295 feet. Honoring the 150 feet requirement would double the amount of equipment rooms. This in turn will lead to unnecessary increases in head end electronic equipment.	Current Text: Telecom rooms/closets should be spaced throughout the facility to provide a less than 150 feet in any direction to the end user devices, with horizontal cabling between than 300 feet apart Proposed Text: Telecom rooms/closets should be spaced throughout the facility to provide of less than 295 feet in any direction to the end user devices, with horizontal cabling betwee over fiber optic cable.
4	07.29.2022	UPS Back-Up	The UPS requirement for the locking control system is four hours. The locking control system is on emergency power. The UPS units are designed to provide power between the time of outage and the generator activation. Reducing the time to an hour will still provide the facility with time to evacuate if the generator does not start. Limiting the UPS time to an hour requires X of the batteries. This is a cost savings for construction as well as long term maintenance when the batteries need to be replaced every five years. Please note that within the Criteria Documents on JCDC page 42, 4.6 – Uninterruptible Power Supplies (UPS) "UPS to be provided with a manual bypass and sized to allow ride-through power upon loss of power with a minimum 15 minutes of backup". The criteria documents currently have emergency generator power covering the entire facility with the capacity to bring on a 3rd 1.5KW generator for expansion.	Current Text: 1.14 DEDICATED UPS A. Description: Single-phase units, rated 120 V, 60-Hz input and output, complying with req UPS-type central battery inverters adequate to supply full connected load for a minimum of Proposed Text: 1.14 SYSTEM UPS A. Description: Single-phase units, rated 120 V, 60-Hz input and output, complying with req UPS-type central battery inverters adequate to supply full connected load for minimum of (

	County Signature/Approval
ı/ ADA cells on 1st st Level only	
st Level only	
	Signed 08.03.2022
	Signed 08.16.2022
e a coverage area of een rooms to be less	
ide coverage areas ween rooms to be	
	Signed 09.01.2022
requirements for n of four (4) hours.	
requirements for of (15) fifteen	
	5'
	Signed 09.01.2022

r	1				
5	07.29.2022	Video System Warranty	The warranty period for the video system is listed as three years. This is longer than the warranty on other systems. Varying the warranty between the locking control system and the video system causes conflicts since the systems are integrated and provided by the same contractor. This also adds additional cost.	Current Text: Warranty Period: Three years from date of Substantial Completion. Proposed Text: Warranty Period: One year from date of Substantial Completion.	Signed 08.03.2022
6	07.20.2022	LEED v4.0 in lieu of v4.1	The Design Build team requests to be allowed to utilize LEED v4.0 in lieu of LEED v4.1 as specified in the DCP. This approach will provide increased flexibility to achieve the desired LEED Gold rating and also allows to switch to LEED v4.1 at a later time if desired.	Current Text: Energy Code: ASHRAE 90.1-2009 LEED Version 4.1 02.2021 Proposed Text: Energy Code: ASHRAE 90.1-2009 LEED Version 4.0	
7	07.29.2022	1 Entrance vs 2 off Highway 40	Per our Preliminary Application meeting on June 30, 2022, the KCMO Planning and Development Department approved the two access points off of Ewing Avenue to service our site. Ewing Avenue is a public street and connects directly to US Highway 40. Therefore, one access point for Ewing Avenue off of US Hwy 40 is acceptable. This will have a positive impact on cost, schedule and provide clear circulation. A traffic study is pending and will provide recommendations on the proposed intersection development of Ewing and US Hwy 40. A secondary entrance off of US Highway 40 can be developed at a future date as the parcel west of Ewing Avenue is further developed and defined, but is no part of the scope of this project at this time.	Current Text: Segregated public and staff vehicular entry points shall be from US Highway 40. Proposed Text: Two access points shall be provided to the site from Ewing Avenue. Ewing Avenue is public street and connects directly to US Highway 40.	Signed 08.03.2022 Hold until Master Planning is complete
8	08.04.2022	Female Housing	Per end user direction at OAC meeting dated 07.26.2022, please confirm the design is to deviate from the program criteria document and remove female cells from Unit 1 - Orientation (Co- Ed) Housing and Stage 4 Housing and relocate into revised Female Housing Units.		Not Approved per current SD
9	08.04.2022	Juvenile Housing - Adjusted Bed Count/Cell Types	Per end user direction at OAC meeting dated 07.26.2022, please confirm the design is to deviate from the program criteria document and remove 2-person occupancy cells from Unit 6 - Juvenile Housing and reduce the total number of beds to 8 vs. 12. Revised Component & # Cells: (1) 1-person Occupancy ADA cell and (7) 1-person Occupancy Cell	Current Text: Page 22) 2.5.16 Housing Pods Area – Unit 6-Juvenile (Page 22) 2.5.16 Housing Pods Area & Component – Unit 6-Juvenile 12 beds* 6.704 1-person Occupancy Cell 3 cells 6.705 2-person Occupancy Cell 4 cells* (Page 153) Table 26. Juvenile Housing Space 6.704 1-person Occupance Cell 3 units 6.705 2-Person Occupancy 4 units* Proposed Text: (Page 22) 2.5.16 Housing Pods Area & Component – Unit 6-Juvenile 8 beds* 6.704 1- person Occupancy Cell 7 cells*(Page 153) Table 26. Juvenile Housing Space 6.704 1-person Occupancy Cell 7 units*	Signed 09.01.2022

	1	1		1	
10	08.04.2022	Staff Support - Staff Breakroom Locations	Per end user direction at the OAC meeting dated 07.26.2022, please confirm the design is to include areas for staff dining both outside and inside the secure perimeter.	 Current Text: • All staff will have access to a Staff Dining Room in an environment that is removed from the feel of an institution. The staff dining room will consist of both served and self-serve items with a self-serve beverage counter. After-hour meal service with grab-n-go or re therm meals will be provided. Proposed Text: All staff will have access to a Staff Dining area outside and inside the secure perimeter of the building. The location of these spaces will be defined in the Schematic Design Documents. 	Signed 09.01.2022
11	08.04.2022	Inmate Cells - Underbunk Storage	Per end user direction at OAC meeting dated 07.26.2022, please confirm the design is to include under the bunk storage capabilities at each cell. Inmate property will be held in covered bins place under the bunks.	 Current Text: (Page 2-24) 2.5.20 Furniture in Cells and Sleeping Rooms All furniture in the cells and sleeping rooms shall be designed with inmate safety as a priority and shall limit ways in which inmates can harm themselves within the sleeping room or cell. To support suicide prevention, beds shall be either a heavy molded plastic or shall be steel-bolted flush to the wall with the frame constructed to prevent its use as an anchoring device. In any of the options described above, the bed shall be approximately 12 to 15 inches above the finished floor. For certain housing classification types with higher security levels open space below the bed shall be enclosed so as to prevent an inmate from barricading themselves under the bed or otherwise accessing that space. Desks shall be attached to the wall with chairs for seating, depending on the housing pod type higher security will have a chair or stool mounted to the floor or wall to prevent throwing. Proposed Text: (Page 2-24) 2.5.20 Furniture in Cells and Sleeping Rooms (Add sentence) Provide under the bunk storage capabilities. Inmate property will be held in covered bins place under the bunks. Owner to provide inmate storage bins. 	Signed 09.01.2022
12	01.27.2023	Housing Units	Per end user direction at OAC meeting dated 07.26.2022, please confirm the design can include sub-dayrooms in selected housing units to allow for increased out-of-cell time while limiting contact between the inmates.	 Current Text: (Page 25) 2.5.21 Dayrooms Direct supervision is mandated at all times for the inmate population to be housed at the JCDC. Custody staff shall have a central custody station raised above the floor by 12 to 18 inches to optimize views into inmate- occupied areas. Custody staff are required to move in and around the housing units. Space within the dayroom shall maximize visibility through the space. Columns shall not impede views. Inmate meals shall be eaten within the housing units. Support spaces adjacent to the dayroom, including multipurpose rooms, interview rooms, and private visitation rooms, shall be clearly viewable from the central housing security station. Proposed Text: (Page 25) 2.5.21 Dayrooms (Add sentence) Dayrooms may include sub-dayrooms in selected housing units to allow for some classification separation and to increase out-of-cell time while limiting contact between inmates in the same housing unit. (Add sentence to Typical Selected Housing Units Description of Function & Facility Program Enhancements) Dayrooms may include sub-dayrooms in selected housing units to allow for some classification separation and to increase out-of-cell time while limiting contact between inmates in the same housing unit. 	Signed 02.08.2023
13	08.04.2022	Intake/Release	Per end user direction at OAC meeting dated 07.26.2022, please confirm that Inmates being released from custody will not go through the Public Lobby as part of the design for the Intake/Release area for discretionary purposes.	 Current Text: (Pages 15-16) 2.5.11 Release & (Page 137) 5.6000 Release – Description of Function If the individual is being released to the community and there are no other warrants or holds from another jurisdiction, the individual is escorted from housing to the Release area and continues through the release process. If there is a hold or outstanding warrant, the individual remains in custody. Proposed Text: (Pages 15-16) 2.5.11 Release & (Page 137) 5.6000 Release – Description of Function (Add sentence to Paragraphs on page 16 & 137) Inmates being released from custody will not go through the Public Lobby. 	Signed 09.01.2022
14	01.27.2023	No LEED certification	The Design Build team requests to be allowed to eliminate all LEED requirements as specified in the DCP. This approach will provide increased flexibility to achieve the desired VE efforts that are currently under way to reach a GMP budget. Ref VE G2a	Current Text: See section 5.1 Schematic Design LEED Integrative Process Credit Modeling, section 5.2 Design Development and section 7 LEED Narrative. Proposed Text:Eliminate above mentioned LEED requirements entirely.	Signed/Received on 02.08.2023

15	01.27.2023	Integral color concrete floor	The Design Build team requests to be allowed to remove integral color concrete flooring in the housing units. This approach will provide increased flexibility on VE options to reach GMP. Ref G12	Current Text: (Page 30) 2.5.27 Material Selection Proposed Text: (Page 30) 2.5.27 Material Selection eliminate integral color from the material selection	Signed/Received on 02.08.2023
16	01.27.2023	Virtual Reality training room	Per end user direction from Owner, please add a 1500 SF room to be used as a Virtual Reality Training Room. Per P11 on the VE list to get to a GMP.	Current Text: Not currently in program	Signed/Received on 02.08.2023
17	01.27.2023	2 ADA cells in each med/min housing unit	The Design Build team requests to deviate from the program criteria document and reduce the quantity of ADA cells in housing units 3 and units 7-22. This approach will provide increased flexibility on VE options to reach GMP. Ref H3	 Current Text: (Page 22) 2.5.16 Housing Pods Area – Unit 3-Max Cells Male 16 (Page 22) 2.5.16 Housing Pods Area – Unit 7-18 -Med-Min Male and Female 16 (Page 22) 2.5.16 Housing Pods Area – Unit 19 -Medical Housing Co-ed 16 (male) & 8 (female) (Page 22) 2.5.16 Housing Pods Area – Unit 20 -Special Needs Stage 1-3 Male 40 & 4 (Page 22) 2.5.16 Housing Pods Area – Unit 21 -Special Needs Stage 4 Male 12 (Page 22) 2.5.16 Housing Pods Area – Unit 22 -Special Needs Stage Female 16 & 4 Proposed Text: Page 30) 2.5.16 Housing Pods Area – Unit 7-18 -Med-Min Male and Female 2 (Page 30) 2.5.16 Housing Pods Area – Unit 7-18 -Med-Min Male and Female 2 (Page 30) 2.5.16 Housing Pods Area – Unit 19 -Medical Housing Co-ed 2 (male) & 2 (female) (Page 30) 2.5.16 Housing Pods Area – Unit 20 -Special Needs Stage 1-3 Male 2 & 2 (Page 30) 2.5.16 Housing Pods Area – Unit 20 -Special Needs Stage 1-3 Male 2 & 2 (Page 30) 2.5.16 Housing Pods Area – Unit 20 -Special Needs Stage 1-3 Male 2 & 2 (Page 30) 2.5.16 Housing Pods Area – Unit 20 -Special Needs Stage 1-3 Male 2 & 2 (Page 30) 2.5.16 Housing Pods Area – Unit 21 -Special Needs Stage 4 Male 2 (Page 30) 2.5.16 Housing Pods Area – Unit 22 -Special Needs Stage 5 + 3 Male 2 & 2 	Signed/Received on 02.08.2023
18	01.27.2023	Reduce Dayrom height	The Design Build team requests to deviate from the program criteria document and reduce the average height of the structure at dayroom housing from 25'-4" to 22'-4", reduce glazing and smoke exhaust fans on the roof. This request is in conjunction with VE item H21 – Reducing the ceiling height in cells from 9'-0" to 8'-0". See Typ. Dayroom Section on page 2. This approach will reduce project material costs and will provide increased flexibility on VE options to reach GMP. Ref J5, H21	Current Text: Page 340, 347, 352, 363, 388, & 392) Room Data Sheets > Ceiling Height: 25'-0" Proposed Text: (Page 340, 347, 352, 363, 388, & 392) Room Data Sheets > Ceiling Height: 21'-6"	Signed 02.08.2023
19	01.27.2023	Canopy at transportation sallyport	The Design Build team requests to deviate from the program criteria document and remove the canopy at the Transportation Vehicle Sallyport. This approach will reduce project material costs and will provide increased flexibility on VE options to reach GMP.	Current Text: (Page 125) 5.102 Transportation Vehicle Sallyport Comment: "outdoor area with 2 lanes, partially covered, heated slab room for bus, parking for 6 vans," Proposed Text: (Page 125) 5.102 Transportation Vehicle Sallyport Comment: "outdoor area with 2 lanes, heated slab, room for bus, parking for 6 vans,"), Signed 02.08.2023
20	01.27.2023	Cameras inside Med/Min cells	The Design Build team requests to be allowed to delete cameras at Male and Female Med/Min Cells only.	Current Text: 2.5.13 Security: Paragraph 4, Bullet 13: Security cameras shall be used as a deterrent to criminal activity. Proposed Text: 2.5.13 Security: Paragraph 4, Bullet 13: Security cameras shall be used as a deterrent to criminal activity (except no cameras in Male and Female Med/Min Cells only)	Signed/Received on 02.08.2023

01.27.2023	Eliminate Coax at all cells	locations cells and instead provide data jacks only.	RDS: F617: AV/Telecommunications: MATV: COAX RDS: F618: AV/Telecommunications: MATV: COAX RDS: F620: AV/Telecommunications: MATV: COAX	Signed 02.08.2023
01.27.2023	Reduce Corridor Widths		Proposed Text: 2.5.15 Circulation Dimensions - Public circulation shall have a clear width of at least 10 feet where there is waiting area seating. In public seating areas, circulation corridors must have a clear width of 8	Signed/Received o
01.27.2023	Reduce cell height	from 9' to 8'-1" in all housing cells (less Male Seg). The male		Signed 02.08.2023
N/A	N/A	N/A	Current Text: Proposed Text:	NOT USEI
01.27.2023	Windborne-Debris impact resistance of Exterior glazing	The Design Build team requests to eliminate the requirement for Wind Zone 1 rating for glazing – not a code issue.	Current Text: 1.4 PERFORMANCE REQUIREMENTS, B. Windborne-Debris-Impact Resistance of Exterior Glazing: Wind Zone 1 Proposed Text: ELIMINATE 1.4	Signed/Received c
	01.27.2023 01.27.2023	Image: Display state in the sector of the sector with sector of the s	01.27.2023 Extinsiste Loss at all Cells instanta periodic cells and instanta periodic cells jucks cenjy. 01.27.2023 Resize Corridor Widths The Design Build team requests to resize corridor widths. 01.27.2023 Resize cell height The Diff team requests to resize corridor widths. 01.27.2023 Resize cell height The Diff team requests to be allowed to resize the cell height service corridor widths. N/A N/A N/A	Q222221Ensure Cost al offsEnsure Cost and Cost al offs

ications: MATV: COAX /: COAX	Signed 02.08.2023
of at least 12 feet where there is waiting area seating. In public ave a clear width of 10 feet. of 10 feet except where the corridor serves only exit stairs, service lation system wide ons - Public circulation shall have a clear width of at least 10 feet Jlic seating areas, circulation corridors must have a clear width of 8 width of 8 feet except where the corridor serves only exit stairs, lic circulation system Inmate corridors must be at least 10 feet	Signed/Received on 02.08.2023
; height in inmate cells and multiple num clear height of 9 foot" ng height in inmate cells and multiple num height of 8'1" foot in all housing cells except male segregation er units remaining at 8'1""	Signed 02.08.2023
	NOT USED
MENTS, B. Windborne-Debris-Impact Resistance of Exterior	Signed/Received on 02.08.2023

26	01.27.2023	Site Lighting levels	The Design Build team requests to deviate from the program criteria document and reduce the site lighting levels from the 3- foot-candle requirement to 1-foot-candle at all occupied areas of the site including parking, walk ways and roads. Pricing is based upon a combination of building wall pack lighting and site pole lighting using 25' tall light poles as needed to comply with code requirements. Proposed pole height was chosen to ensure uniformity of lighting. See lighting plan on page 2 for proposed light fixture layout. This approach will reduce project costs and will provide increased flexibility on VE options to reach GMP. Ref E1	 Current Text: (Page 6 & page 100) · The type and spacing of outdoor light standards should be selected based on the location of the buildings on the site, surrounding land uses, and environmental conditions. A level of three (3) foot candles should be maintained over the exterior areas of the facility. Proposed Text: (Page 6 & page 100) · The type and spacing of outdoor light standards should be selected based on the location of the buildings on the site, surrounding land uses, and environmental conditions. A level of one (1) foot candles should be maintained over the exterior areas of the facility. 	Signed/Received on 02.08.2023
27	01.27.2023	Above Grade Sanitary	The Design Build team requests to use PVC for waste piping in above grade non-plenum spaces.	Current Text: 1.2 HUBLESS, CAST-IRON SOIL PIPE AND FITTINGS (ABOVE GRADE ONLY) 1.4 PVC PIPE AND FITTINGS (BELOW GRADE ONLY) Proposed Text: 1.2 HUBLESS, CAST-IRON SOIL PIPE AND FITTINGS (ABOVE GRADE PLENUM SPACES ONLY) 1.4 PVC PIPE AND FITTINGS (BELOW GRADE AND NON-PLENUM SPACES ONLY)	Signed/Received on 02.08.2023
28	12.05.2022	Below Grade Conduit	The Design Build team requests to use schedule 40 PVC at below grade electrical work in lieu of 80 PVC	Current Text: Conduit below grade to be schedule 80 PVC. Proposed Text: Conduit below grade to be schedule 40 PVC.	Signed 12.22.2022
29	12.05.2022	Branch feeder wire	The Design Build team requests to use aluminum wire in lieu of copper at all branch feeders.	Current Text: Section 26 05 13 Medium-Voltage Cables, 1.2 Cables, C. Conductor: Copper Proposed Text: Section 26 05 13 Medium-Voltage Cables, 1.2 Cables, C. Conductor: Aluminum	Signed/Received on 02.08.2023
30	12.05.2022	TPO Roofing	The Design Build team requests to change from white roof to grey roof and eliminate 2-ply vapor barrier.	<i>Current Text:</i> See section 07 54 23 Thermoplastic-Polyolefin (TPO) Roofing, 1.4 Materials, B. TPO Roofing, 2. Color: White <i>Proposed Text:</i> Section 07 54 23 Thermoplastic-Polyolefin (TPO) Roofing, 1.4 Materials, B. TPO Roofing, 2. Color: Grey	Signed/Received on 02.08.2023

31	01.27.2023	Heated Slab	Per the program criteria document providing heated slabs at the intake vehicle sallyport is required. Please confirm the D/B can deviate from the program criteria document and remove heated slab from the vehicle sallyports. This approach will provide increased flexibility to achieve the desired VE efforts that are currently under way to reach a GMP budget. Ref VE J47 and J48	Current Text: (Page 125) 5.101 Intake Vehicle Sallyport Comment: enclosed area, heated slab, oversized lane, room for van and cars Proposed Text: (Page 125) 5.101 Intake Vehicle Sallyport Comment: enclosed area, oversized lane, room for van and cars	Signed 02.08.2023
32	01.27.2023	Operable clerestory windows or clerestory windows in intake and medical	Per the program criteria document having operable clerestory windows at intake, medical and dayrooms are required. Please confirm the Design Build Team can deviate from the program criteria document and remove operable clerestory windows from those areas. This approach will provide increased flexibility to achieve the desired VE efforts that are currently under way to reach a GMP budget. Ref VE J49 and J50	Current Text: (Page 340) RDS F 608 Windows – Notes: Clerestory Windows Operable Windows (out of reach areas) (Page 352) RDS F 621 Windows – Notes: Operable Windows (out of reach areas) Clerestory Windows (Page 363) RDS F 640 Windows – Notes: Operable Windows (out of reach areas) Clerestory Windows (Page 388) RDS H 821 Windows – Notes: Operable Windows (out of reach areas) Clerestory Windows (Page 392) RDS H 827 Windows – Notes: Operable Windows (out of reach areas) Clerestory Windows (Page 392) RDS H 827 Windows – Notes: Operable Windows (out of reach areas) Clerestory Windows (Page 352) RDS F 621 Windows – Notes: Clerestory Windows (Page 363) RDS F 640 Windows – Notes: Clerestory Windows (Page 363) RDS F 640 Windows – Notes: Clerestory Windows (Page 388) RDS H 821 Windows – Notes: Clerestory Windows (Page 392) RDS H 827 Windows – Notes: Clerestory Windows (Page 392) RDS H 827 Windows – Notes: Clerestory Windows	Signed/Received on 02.08.2023
33	01.27.2023	Commerical ceiling fans	Per the program criteria document having commercial and regular ceiling fans in various rooms throughout the facility as a requirement. Please confirm the Design Build team can deviate from the program criteria document and remove all reference of ceiling fans of any kind from those areas. This approach will provide increased flexibility to achieve the desired VE efforts that are currently under way to reach a GMP budget. Ref VE J51	Current Text: (Page 271) RDS C 301 HVAC – Notes: Commercial ceiling fans (Page 281) RDS C 311 HVAC – Notes: Commercial ceiling fans (Page 286) RDS C 316 HVAC – Notes: Commercial ceiling fans (Page 340) RDS F 608 HVAC – Notes: Commercial ceiling fans (Page 347) RDS F 615 HVAC – Notes: Commercial ceiling fans (Page 352) RDS F 621 HVAC – Notes: Commercial ceiling fans (Page 363) RDS F 640 HVAC – Notes: Commercial ceiling fans (Page 388) RDS H 821 HVAC – Notes: Commercial ceiling fans (Page 388) RDS H 821 HVAC – Notes: Commercial ceiling fans (Page 3292) RDS H 827 HVAC – Notes: Commercial ceiling fans (Page 425) RDS J 935 HVAC – Notes: Commercial ceiling fans (Page 421) RDS J 940 HVAC – Notes: Ceiling fans (Page 441) RDS J 951 HVAC – Notes: Ceiling fans Proposed Text: Eliminate any reference to ceiling fans	Signed/Received on 02.08.2023

				·	
34	01.27.2023	Operable clerestory windows	Per the program criteria document having operable clerestory windows in dayrooms recreation areas and some cells are required. Please confirm the D/B can deviate from the program criteria document and remove operable clerestory windows from those areas but add woven wire mesh over the outdoor recreation area. This approach will provide increased flexibility to achieve the desired VE efforts that are currently under way to reach a GMP budget. Ref VE J49 and J50	Current Text: RDS F 608 Windows – Notes: Clerestory Windows Operable Windows (out of reach areas) RDS F 609 Windows – Notes: Clerestory Windows Operable Windows (out of reach areas) RDS F 614 Windows – Notes: Clerestory Windows RDS F 620 Windows – Notes: Clerestory Windows RDS F 621 Windows – Notes: Clerestory Windows RDS F 621 Windows – Notes: Operable Windows (out of reach areas) Clerestory Windows RDS F 621 Windows – Notes: Operable Windows (out of reach areas) Clerestory Windows RDS F 621 Windows – Notes: Operable Windows (out of reach areas) Clerestory Windows RDS F 621 Windows – Notes: Operable Windows (out of reach areas) Clerestory Windows RDS F 821 Windows – Notes: Operable Windows (out of reach areas) Clerestory Windows RDS H 827 Windows – Notes: Operable Windows (out of reach areas) Clerestory Windows RDS F 609 Windows – Notes: Fixed detention grade windows with 40 minute containment glazing. RDS F 614 Windows – Notes: Fixed detention grade windows with 40 minute containment glazing. RDS F 615 Windows – Notes: Fixed detention grade windows with 40 minute containment glazing. RDS F 614 Windows – Notes: Fixed detention grade windows with 40 minute containment glazing. RDS F 615 Windows – Notes: Fixed detention grade windows with 40 minute containment glazing. RDS F 615 Windows – Notes: Fixed detention grade windows with 40 minute containment glazing. RDS F 612 Windows – Notes: Fixed detention grade windows with 40 minute containment glazing. RDS F 621 Windows – Notes: Fixed detention grade windows with 40 minute containment glazing. RDS F 640 Windows – Notes: Fixed detention grade windows with 40 minute containment glazing. RDS F 640 Windows – Notes: Fixed detention grade windows with 40 minute containment glazing. RDS F 640 Windows – Notes: Fixed detention grade windows with 40 minute containment glazing. RDS H 821 Windows – Notes: Fixed detention grade windows with 40 minute containment glazing. RDS H 827 Windows – Notes: Fixed de	Signed 02.08.2023
35	01.27.2023	Remove access floor at courtroom well spaces	The Design Build team requests to remove access floor from the hearing and small jury courtroom. This approach will provide increased flexibility on VE options to reach GMP	Current Text: RDS E 526, RDS E 527 Finishes Notes: Raised access floor in well Proposed Text: RDS E 526, RDS E 527 Finishes Notes:	Signed/Received on 02.08.2023
36	01.27.2023	Change glass sliding doors at staff and public entry vestibule	The Design Build team requests to eliminate the automatic glass sliding doors at the staff and public entry vestibule. This approach will provide increased flexibility on VE options to reach GMP	Current Text: RDS A 100 Doors Notes: Two sets of double auto sliding doors Proposed Text: RDS A 100 Doors Notes: Aluminum Storefront entrance doors with ADA operators as required.	Signed/Received on 02.08.2023
37	01.27.2023	No centralized UPS system only dedicated UPS for IT/IDF	The Design Build team requests to be allowed eliminate the centralized UPS system and provide a dedicated system for IT/IDF rooms only. This approach will provide increased flexibility on VE options to reach GMP	Current Text: Sections 3.2 General Design and System Critieria Telecom equipment to be connected through a centralized Uninterruptible Power Source (UPS) system. Proposed Text: Sections 3.2 General Design and System Critieria Telecom equipment to be connected through a Uninterruptible Power Source (UPS) system.	Signed/Received on 02.08.2023
38	01.27.2023	Double doors at 5.301, 5.302, 5.303 (courts)	The Design Build team requests to change the door types for the above referenced rooms to single doors. This approach will provide increased flexibility on VE options to reach GMP	Current Text: RDS E 525 Doors Door Type: Swing double doors RDS E 526 Doors Door Type: Swing double doors RDS E 527 Doors Door Type: Swing double doors Proposed Text: RDS E 525 Doors Door Type: Swing single doors RDS E 526 Doors Door Type: Swing single doors RDS E 527 Doors Door Type: Swing single doors RDS E 527 Doors Door Type: Swing single doors	Signed/Received on 02.08.2023

39	01.27.2023	Emergency Generators outside of building at sound rated 90dBs	The Design Build team requests to move the emergency generators to outside the building and to increase the sound rating to 90dBs. This approach will provide flexibility on VE options to reach GMP. Reference G12	Current Text: Section 9.600 Central Plant Sub section 9.610 Emergency Generators 2 generators, inside Proposed Text: Section 9.600 Central Plant Sub section 9.610 Emergency Generators 2 generators, outside	Signed/Received on 02.08.2023
40	01.27.2023	Elevated workstations for central command	The Design Build team requests to eliminate the elevated workstations in central command. This approach will provide increased flexibility on VE options to reach GMP.	Current Text: Section General Notes: Elevated workstation Proposed Text: Section General Notes: workstation	Signed/Received on 02.08.2023
41	01.27.2023	Open cable tray is being utilized at the Administration Building (areas east of Release)	The Design Build team requests to use open cable trays in the Administration building. This approach will provide increased flexibility on VE options to reach GMP.	Current Text: Each type of service (fiber, copper, coax) to be separate dedicated conduit. Proposed Text: Each type of service (fiber, copper, coax) to be set in an open cable tray for the Administration Building in the area east of release.	Signed/Received on 02.08.2023
42	01.27.2023	Requirement for the precast plant to be certified PCI or NPCA	The Design Build team requests to remove PCI and NPCA certified production facility. This approach will provide increased flexibility on VE options to reach GMP	Current Text: Section 13 34 23 Modular Precast Concrete Cells B. 5. 5. The production facility must be certified by PCI or NPCA, prior to bid date. Proposed Text: Section 13 34 23 Modular Precast Concrete Cells B. 5.	Signed/Received on 02.08.2023
43	01.27.2023	Rooftop Mechanical penthouse	The Design Build team requests to remove the mechanical penthouse to the roof and have enclosures for hydronic piping where required. This approach will provide increased flexibility on VE options to reach GMP	Current Text: The County preference wherever possible is to have mechanical equipment enclosed indoors such as in mechanical penthouses due to inclement weather in both winter and summer and also due to cottonwood trees and other debris that can clog up HVAC system. Proposed Text: The County preference wherever possible is to have mechanical equipment such as in mechanical penthouses rooftop mounted.	Signed/Received on 02.08.2023
44	01.27.2023	PVC piping to be utilized at above grade waste and storm piping in areas that are not return air plenums.	The Design Build team requests to change any reference to cast- iron storm drainage pipe to PVC. This approach will provide increased flexibility on VE options to reach GMP	Current Text: Section 22 14 23 Storm Drainage Piping Specialties Part 1 Products Any reference to cast-iron Proposed Text: Section 22 14 23 Storm Drainage Piping Specialties Part 1 Products Any reference to PVC	Signed/Received on 02.08.2023

· · · · · · · · · · · · · · · · · · ·					
45	01.27.2023	Sanitary Waste and Vent Piping	The Design Build team requests to change the above grade cast- iron soil pipe and fittings to PVC. This approach will provide increased flexibility on VE options to reach GMP	 Current Text:Section 22 13 16 Sanitary Waste and Vent Piping Part 1 Products 1.2 Hubless, Cast-Iron Soil Pipe and Fittings (above grade only) Proposed Text: Section 22 13 16 Sanitary Waste and Vent Piping Part 1 Products 1.2 Hubless, PVC Soil Pipe and Fittings (above grade only) 	Not signed
46	01.27.2023	No drop down vinyl curtain in 16-person cells	The Design Build team requests to eliminate the automatic drop down vinyl curtain from cells. This approach will provide increased flexibility on VE options to reach GMP	Current Text: RDS E 537 General Notes: Two automatic drop down vinyl curtains from ceiling to cover or block view doors/windows on either side of shared cell. Proposed Text: RDS E 537 General Notes:	Signed/Received on 02.08.2023
47	12.05.2022	Hydronic Piping Proposed Fittings	The Design Build team requests to deviate from the program criteria document and change any reference to fittings in Spec Section 23 21 13 Part 3 section 3.1 to pressed fittings in hot and chilled hydronic piping on joints of 2" or smaller and Grooved or butt weld joints on pipe joints 2-1/2" and larger. This approach will reduce project material costs and will provide increased flexibility on VE options to reach GMP.	Current Text: A. Hot-water heating piping, shall be any of the following: 1. Type L (Type B), drawn-temper copper tubing, wrought-copper fittings, and soldered joints. 2. Schedule 40 steel pipe, wrought-steel fittings and wrought-cast or forged-steel flanges and flange fittings, and welded and flanged joints. B. Chilled-water piping, shall be any of the following: 1. Type L (Type B), drawn-temper copper tubing, wrought-copper fittings, and soldered joints. 2. Schedule 40 steel pipe, wrought-steel fittings and wrought-cast or forged-steel flanges and flange fittings, and welded and flanged joints. 3. Schedule 40 steel pipe; grooved, mechanical joint coupling and fittings; and grooved, mechanical joints. C. Condenser-water piping, shall be any of] the following: 1. Schedule 40 steel pipe; wrought-steel fittings and wrought-cast or forged-steel flanges and flange fittings, and welded and flanged joints. 2. Schedule 40 steel pipe; wrought-steel fittings and wrought-cast or forged-steel flanges and flange fittings, and welded and flanged joints. 2. Schedule 40 steel pipe; grooved, mechanical joint coupling and fittings; and grooved, mechanical joints. 2. Schedule 40 steel pipe; pressed fittings and grooved or butt weld joints. 3. Schedule 40 steel pipe, pressed fittings and grooved or butt weld joints.	Not Approved per current SD
48	01.27.2023	Sloped Floor	The Design Build team requests to eliminate sloped floors from cells. This approach will provide increased flexibility on VE options to reach GMP.	Current Text:2.5.19 Open-Front Cell Floors in the sleeping rooms, cells, and multiple occupancy sleeping rooms shall have a minimal slope toward the dayroom and have a floor drain just outside the sleeping space Proposed Text:2.5.19 Open-Front Cells Floors in the sleeping rooms, cells, and multiple occupancy sleeping rooms shall have a-no slope toward the dayroom and have a floor drain just outside the sleeping space.	Signed/Received on 02.08.2023
49	12.05.2022	Automatic Receptacles	The Design Build team requests to us adjustable automatic receptacle controls. This approach will provide increased flexibility on VE options to reach GMP.	Current Text: 4. Electrical Narrative Energy savings will be addressed with dimming, zone controls, and a watt per square foot basis. Lighting and controls that iares for maintaining the safety and security of personnel will supersede any energy cost-saving measures. Proposed Text: 4. Electrical Narrative Energy savings will be addressed with dimming, zone controls, and a watt per square foot basis. Lighting and controls that iares for maintaining the safety and security of personnel will supersede any energy cost-saving measures. Allow auto receptacles in private offices, admin spaces only.	

50	01.27.2023	Medium/Minimum Housing conversion to Dorm	The Design Build team requests to deviate from the program criteria document and convert (2) Male Medium/Minimum Units into Dormitory Units – 64 beds in each, 128 beds total. This approach will reduce project construction costs and provide increased flexibility on VE options to reach GMP. Ref VE Item H10 per proposed Design Modification Cost List.	Current Text : (Page 22) 2.5.16 Housing Pods Area – Unit 15-Med/Min Male 4-person Occupancy ADA Cell 16 Cells 64 beds 2.5.16 Housing Pods Area – Unit 16-Med/Min Male 4-person Occupancy ADA Cell 16 Cells 64 beds Proposed Text: (Page 22) 2.5.16 Housing Pods Area – Unit 15-Med/Min Male 4-person Occupancy Dorm 6 Cells & 5-person Occupancy Dorm 8 Cells 64 beds 2.5.16 Housing Pods Area – Unit 16-Med/Min Male 4-person Occupancy Dorm 6 Cells & 5-person Occupancy Dorm 8 Cells 64 beds	Signed/Received on 02.08.2023
51	01.27.2023	Snowmelt System at Transporation Drive Lanes, not included inside Vehicle Sallyport	The Design Build team requests to deviate from the program criteria document and eliminate in slab heating for snow melt. This approach will reduce project construction costs and provide increased flexibility on VE options to reach GMP.	Current Text: (Page 294) General Area (SF): 5000 Notes: Accessible Ceiling Height: Open To Sky Area to accommodate vans and buses Accoustics (NIC): Heated slab HVAC Heating: Emergency Power:Cooling: Notes:Schedule: In-slab heating for Snow Melt Proposed Text: (Page 294) General Area (SF): 5000 Notes: Accessible Ceiling Height: Open To Sky Area to accommodate vans and buses Accoustics (NIC): HVAC Heating: Emergency Power:Cooling: Notes:Schedule:	Duplicated see 19 and 31
52	01.27.2023	MC Cabling at Administration Building in lieu of EMT	The Design Build team requests to deviate from the program criteria document and change the EMT conduit out to use MC cabling in the administration building only. This approach will reduce project construction time and provide increased flexibility in cabling runs.	 Current Text: Interior conduit to be minimize 3/4 inch in size EMT with minimum #12 conductors. Exposed conduit subject to damage under ten feet to be RMC. MC cable is not allowed. Conduit below grade to be schedule 80 PVC. Non-linear electronic loads to be served with dedicated separate neutrals. Proposed Text: Interior conduit to be minimize 3/4 inch in size EMT with minimum #12 conductors. Exposed conduit subject to damage under ten feet to be RMC. MC cable is not allowed except in Administration building. Conduit below grade to be schedule 80 PVC. Non-linear electronic loads to be served with dedicated separate neutrals. 	Signed/Received on 02.08.2023





Workforce Plan

JE Dunn | Axiom | DLR Group has had success Building Careers in Construction in Jackson County and beyond for decades. The process comes at **no cost to the project** from recruitment to training. A key element to our past and future success has been the **Unions who will help participants select the right craft.** They also help to mentor workforce candidates to keep them in the construction industry. Additionally, the **Urban League's Project Pathway** program will provide wrap around services and support for the candidates. This winning combination are the key components toward engaging workforce participants for the project.

JE Dunn | Axiom | DLR Group will engage various **outreach forums** to inform the community about employment opportunities. Our partners include not only the Urban League, but also the Full Employment Council, Builder's Association, Second Chance Program, Minority Contractors, Unified Contractors Association, and other community-based organizations.

PHASE | EARLY ENGAGEMENT

Project Outreach Events to MWVBE Trade Partners and Workforce Candidates, Prequal Support, Bid Development Class

PHASE II PRECONSTRUCTION

Right-Size Trade Packages, 1st/2nd Tier Matchmaking Outreach, Workforce Training Certifications, Workforce Matchmaking Outreach, 1:1 Mentor Pairings

PHASE III CONSTRUCTION

Compliance and Reporting, Ensuring Success and Development





Attachment G Contractor Utilization Plan

Bid Number:	7-22
Bid Title:	Jackson County Detention Center, Design Build Services
Contracting Department:	Public Works

Bidder: JE Dunn Construction | Axiom Construction | DLR Group

I, Vance McMillan , of lawful age and upon my oath state as follows:

1. This Affidavit is made for the purpose of complying with the provisions of the MBE/WBE/VBE submittal requirements on the above Invitation to Bid and the MBE/WBE/VBE Program and is given on behalf of the Bidder listed above. It sets out the Bidder's plan to utilize MBE and/or WBE and/or VBE prime and subcontractors on the Bid.

The goals set by Jackson County, Missouri are:

<u>12.3</u> %MBE <u>10.7</u> %WBE

2. Bidder stipulates that it will utilize a minimum of the following percentages of MBE/WBE participation in the above bid:

17.5 %MBE 11 %WBE 0.5 %VBE

3. The following are the MBE/WBE/VBE Contractors to be utilized on the above-named Bid. Bidder maintains that it either has a formal contract or a conditional contract contingent upon award.

Please note:

- a. If Bidder is a certified MBE, WBE, or VBE firm, it may list itself in the appropriate area below.
- b. No contractor may be listed under multiple categories below regardless of certifications

INTERNAL USE ONLY				
CUP RECEIVED:	CUP APPROVED:			
GFW RECEIVED:	GFE APPROVED:			
CUP REVISED:	REVISION APPROVED:			
APPROVED GOALS: MBE	WBEVBE			
RES/ORD:	AMT AWARDED:			
NOTES:				

*Percentages are based on the GMP Value of \$301,162,067

*Values/companies could be subject to change based on future buyout of Component Packages 2 and 3.

MBE SUBCONTRACTORS

А.	MBE Firm:	Cornerstone Axiom JV LLC	INTERNAL USE
	Address line 1:	718 Troost Avenue, KC, Mo	ONLY
	Address line 2-including County:	Jackson County, 64106	Certifying Agency:
	Telephone Number:	816.442.7865	КСМО
	President/Owner:	Daniel Felder	State of MO
	Email Address:	dfelder@axiomcgkc.com	
	Certifying Agency:	City of KC	Approved: Y N
	Expiration Date of Certification:		
	Scopes of Work Utilized:	Cell Modules Concrete	Contract Value:
	Percentage of Contract Awarded:	5.73%	\$

B.	MBE Firm:	Pro-Insulation (Sub to US Engineering)	INTERNAL USE
	Address line 1:	8203 Hickman Mills Drive, KC, Mo	ONLY
	Address line 2-including County:	Jackson, 64132	Certifying Agency:
	Telephone Number:	816.523.0321	КСМО
	President/Owner:	John Olivarez	State of MO
	Email Address:	jolivarez@prometals.com	
	Certifying Agency:	City of KC	Approved: Y N
	Expiration Date of Certification:	12.31.2023	
	Scopes of Work Utilized:	Insulation	Contract Value:
	Percentage of Contract Awarded:	0.96%	\$

C.	MBE Firm:	Alexander Mechanical (Sub to US Engineering)	INTERNAL USE
	Address line 1:	10801 North Pomona Avenue, KC M	Io ONLY
	Address line 2-including County:	Jackson, 64153	Certifying Agency:
	Telephone Number:	816.833.0700	КСМО
	President/Owner:	Bill Alexander	State of MO
	Email Address:	balexander@alexandermechanical.	com
	Certifying Agency:		Approved: Y N
	Expiration Date of Certification:	12.16.2023	
	Scopes of Work Utilized:	Mechanical	Contract Value:
	Percentage of Contract Awarded:	1.31%	\$

MBE SUBCONTRACTORS

А.	MBE Firm:	Vazquez Comm. Contracting (Sub to US Engineering)	INTERNAL USE
	Address line 1:	3303 Gillham Road, KC, Mo	ONLY
	Address line 2-including County:	Jackson, 64109	Certifying Agency:
	Telephone Number:	816.569.6869	KCMO
	President/Owner:		State of MO
	Email Address:	info@vazquezCC.com	
	Certifying Agency:		Approved: Y N
	Expiration Date of Certification:		
	Scopes of Work Utilized:	Mechanical	Contract Value:
	Percentage of Contract Awarded:	1.31%	\$

В.	MBE Firm:	Alpha Energy and Elec. (Sub to Cornerstone and Mark One)	INTERNAL USE
	Address line 1:	1100 East 34th St. KC, MO	ONLY
	Address line 2-including County:	Jackson, 64109	Certifying Agency:
	Telephone Number:	816.421.6767	КСМО
	President/Owner:	Gabriel Okafor	State of MO
	Email Address:	gabriel.okafor@alphaee.com	
	Certifying Agency:	City of KC	Approved: Y N
	Expiration Date of Certification:		
	Scopes of Work Utilized:	Electric	Contract Value:
	Percentage of Contract Awarded:	1.63% (Cornerstone) 1.70% (MOE)`	\$
	•	3.33% Total	•

C. MBE Firm: EJ and Sons Trucking (sub to Kissick) **INTERNAL USE** ONLY Address line 1: 3910 Norton Ave., KC, Mo Address line 2-including County: Jackson, 64130 **Certifying Agency:** Telephone Number: 816.326.8429 KCMO President/Owner: State of MO ejandsonconstructino@gmail.com Email Address: Approved: Y N Certifying Agency: City of KC Expiration Date of Certification: **Contract Value:** Scopes of Work Utilized: Trucking \$ Percentage of Contract Awarded: 0.82%

*Percentages are based on the GMP Value of \$301,162,067

*Values/companies could be subject to change based on future buyout of Component Packages 2 and 3.

MBE SUBCONTRACTORS

А.	MBE Firm:	Rising Construction (Sub of Kissick)	INTERNAL USE
	Address line 1:	1206 NW Baytree Dr. Grain Valley,	Mo ONLY
	Address line 2-including County:	64029	Certifying Agency:
	Telephone Number:	816.867.5255	KCMO
	President/Owner:		State of MO
	Email Address:	kristenr@risingconst.com	
	Certifying Agency:	City of KC	Approved: Y N
	Expiration Date of Certification:	05.26.2024	
	Scopes of Work Utilized:	traffic control and erosion control	Contract Value:
	Percentage of Contract Awarded:	0.07%	\$

B.	MBE Firm:	Maher Oil (Sub of Kissick)	INTERNAL USE
	Address line 1:	401 N. Prospect, KC, Mo	ONLY
	Address line 2-including County:	Jackson, 64120	Certifying Agency:
	Telephone Number:	816.241.2400	КСМО
	President/Owner:		State of MO
	Email Address:	janice@maheroilco.com	
	Certifying Agency:	State of Missouri	Approved: Y N
	Expiration Date of Certification:	08.05.2025	
	Scopes of Work Utilized:	fuel supply and delivery	Contract Value:
	Percentage of Contract Awarded:	0.08%	\$

C.	MBE Firm:	INTERNAL USE
	Address line 1:	ONLY
	Address line 2-including County:	Certifying Agency:
	Telephone Number:	KCMO
	President/Owner:	State of MO
	Email Address:	
	Certifying Agency:	Approved: Y N
	Expiration Date of Certification:	
	Scopes of Work Utilized:	Contract Value:
	Percentage of Contract Awarded:	\$

TOTAL MBE VALUE: \$	5
---------------------	---

*** Add Additional Pages as Necessary ***

WBE SUBCONTRACTORS

А.	WBE Firm:	Mark One Electric	INTERNAL USE
	Address line 1:	1414 Genessee, KC, Mo	ONLY
	Address line 2-including County:	Jackson, 64102	Certifying Agency:
	Telephone Number:	816.842.7023	KCMO
	President/Owner:	Rosana Privitera Biondo	State of MO
	Email Address:	Rosana.priviterabiondo@Markone	.com
	Certifying Agency:	City of KC	Approved: Y N
	Expiration Date of Certification:		
	Scopes of Work Utilized:	Electric, Fire Alarm	Contract Value:
	Percentage of Contract Awarded:	6.77%	\$

B.	WBE Firm:	Blue Chip Roofing (Sub to Flynn)	INTERNAL USE
	Address line 1:	5234 Winner Road, KC, Mo	ONLY
	Address line 2-including County:	Jackson, 64127	Certifying Agency:
	Telephone Number:	816.216.7176	КСМО
	President/Owner:	LaTanya Scott	State of MO
	Email Address:	tanyas@bluechiproofingkc.com	
	Certifying Agency:	City of KC	Approved: Y N
	Expiration Date of Certification:		
	Scopes of Work Utilized:	Roofing	Contract Value:
	Percentage of Contract Awarded:	0.83%	\$

C.	WBE Firm:	Wilkerson (Sub to US Engineering)	INTERNAL USE
	Address line 1:	14101 Gibbs Road, Bonner Springs	, KS ONLY
	Address line 2-including County:	66012	Certifying Agency:
	Telephone Number:	913.238.7030	КСМО
	President/Owner:	Diana Holt	State of MO
	Email Address:	info@wilkersoncranerental.com	
	Certifying Agency:	State of Kansas	Approved: Y N
	Expiration Date of Certification:		
	Scopes of Work Utilized:	Crane Services	Contract Value:
	Percentage of Contract Awarded:	0.08%	\$

TOTAL MBE VALUE:	\$
------------------	----

*** Add Additional Pages as Necessary ***

WBE SUBCONTRACTORS

А.	WBE Firm:	CJ Industries (Sub to US Engineering)	INTERNAL USE
	Address line 1:	610 S. 78th St. Suite 1, KC, KS	ONLY
	Address line 2-including County:	Wyandotte, 66111	Certifying Agency:
	Telephone Number:	913.788.1104	КСМО
	President/Owner:	Mindy Rocha	State of MO
	Email Address:	mindy@cjikc.com	
	Certifying Agency:	City of KC	Approved: Y N
	Expiration Date of Certification:	07.19.2024	
	Scopes of Work Utilized:	Mechanical	Contract Value:
	Percentage of Contract Awarded:	0.69%	\$

B.	WBE Firm:	INTERNAL USE
	Address line 1:	ONLY
	Address line 2-including County:	Certifying Agency:
	Telephone Number:	KCMO
	President/Owner:	State of MO
	Email Address:	
	Certifying Agency:	Approved: Y N
	Expiration Date of Certification:	
	Scopes of Work Utilized:	Contract Value:
	Percentage of Contract Awarded:	\$

C.	WBE Firm:	INTERNAL USE
	Address line 1:	ONLY
	Address line 2-including County:	Certifying Agency:
	Telephone Number:	КСМО
	President/Owner:	State of MO
	Email Address:	
	Certifying Agency:	Approved: Y N
	Expiration Date of Certification:	
	Scopes of Work Utilized:	Contract Value:

VBE SUBCONTRACTORS

А.	VBE Firm:	Midland Marble and Granite	INTERNAL USE
	Address line 1:	2077 NE Rice Rd., Lee Summit, MO	ONLY
	Address line 2-including County:	Jackson, 64064	Certifying Agency:
	Telephone Number:	816.257.2000	КСМО
	President/Owner:		State of MO
	Email Address:	matt.sharp@midlandmarble.com	
	Certifying Agency:		Approved: Y N
	Expiration Date of Certification:		
	Scopes of Work Utilized:	Tile	Contract Value:
	Percentage of Contract Awarded:	0.12%	\$

В.	VBE Firm:	Aquila Industries (sub to Cornerstone)	INTERNAL USE
	Address line 1:	5897 Raytown Rd. Raytown, Mo	ONLY
	Address line 2-including County:	Jackson, 64133	Certifying Agency:
	Telephone Number:	816.595.8600	KCMO
	President/Owner:	Marquis Cannion	State of MO
	Email Address:	info@aquilabuilds.us	
	Certifying Agency:		Approved: Y N
	Expiration Date of Certification:		
	Scopes of Work Utilized:		Contract Value:
	Percentage of Contract Awarded:	0.18%	\$

C.	VBE Firm:	M&T Govt. Solutions (Sub to Kissick)	INTERNAL USE
	Address line 1:	500 East Walnut St. Suite 102	ONLY
	Address line 2-including County:	Columbia, Mo. 65201	Certifying Agency:
	Telephone Number:	573.454.1018	КСМО
	President/Owner:		State of MO
	Email Address:	mtqsllc@gmail.com	
	Certifying Agency:	State of Mo	Approved: Y N
	Expiration Date of Certification:	09.26.2023	
	Scopes of Work Utilized:	Trucking/Hauling	Contract Value:
	Percentage of Contract Awarded:	0.02%	\$


Exhibit 11

Jackson County Detention Center															
Systems Matrix															
2/14/2023															
	Owner	Owner	Electrical	Electrical	Security	Security	Plumbing	Plumbing	Module	Module	Detention	Detention	Comm. HM	Comm. HM	_
	Furnish	Install	Contractor	Contractor	Electronics	Electronics		Contractor	Supplier	Supplier	Contractor	Contractor	Contractor	Contractor	Carp F&I
			Furnish	Install	Contractor	Contractor	Furnish	Install	Furnish	Furnish	Furnish	Install	Furnish	Install	
					Furnish	Install									
Division 26 Electrical															
120 Volt Power to support Low Voltage Systems			Х	Х											
120v Power Conduit and Wire			Х	Х											
Division 27 Tele/Data-Network															
Conduits for communication service providers including innerduct			х	Х											
Provide all cabling for systems as identified on systems drawings															
including fiber optics.			Х	х											
Provide Rack mount enclousres and all associated terminations			Х	х											
Computer Stations	X	Х				<u> </u>									
Wireless Access Points (including patch cables)	Х	Х													
VOIP Telephone head-end	Х	Х													
Fiber LIU			Х	х											
Fiber Patch Cables	Х	Х													
IDF Rooms															
8' Tall Plywood backer at 3 Walls															Х
Vertical and Horizontal Wire Management			Х	Х											
Equipment Racks - Two post and 4 post 36" server racks			Х	Х											
Provide cable management hardware and racks as indicated per															
documents and systems drawings			Х	Х											
Rack Power Distribution (PDUs)			Х	Х											
Patch panels inside of racks			Х	Х											
Patch cables inside of racks'	Х	Х													
Switches mounted in upper portion of racks	Х	Х													
Room to Room SFPs	Х	Х													
General Tele-Data Network Devices															
Data Outlet Jacks including Jack at WAP			Х	Х											
Wireless Access Points	X	Х													
Conduit, junction boxes, & Pull Strings			Х	Х											
Cabling/ Wire			Х	Х											
Fiber Optic Cabling			Х	Х											
Division 27 Cable TV/ CATV System															
CATV Head End Equipment	Х	Х													
CATV Outlets			Х	Х											
Category 6 data cable/Jack at each CATV outlet			Х	Х											
AV cabling required for TVs			Х	Х											
Conduit, junction boxes, & Pull Strings			Х	х											

	Owner Furnish	Owner Install	Electrical Contractor Furnish	Electrical Contractor Install	Security Electronics Contractor Furnish	Security Electronics Contractor Install	Plumbing Contractor Furnish	Plumbing Contractor Install	Module Supplier Furnish	Module Supplier Furnish	Detention Contractor Furnish	Detention Contractor Install	Comm. HM Contractor Furnish	Comm. HM Contractor Install	-
281300 Access Control System															
Ethernet based Network Equipment					Х	Х									-
Managed Network Switches/Routers, Processors					Х	Х									
Low Voltage Conduit & Junction Boxes including pull strings					Х	Х									
Low Voltage Wire/Cabling					Х	Х									
Access Control Software					Х	Х									
Licensing Fees (Controller License)					Х	Х									
Access Control Computer Workstation					Х	Х									
Power Supplies for access control					Х	Х									
Enclosures					X	X									
Identification Cards	Х	Х													
Card Readers/Badge Readers					Х	Х									
Electronic Commercial Door Hardware													Х	Х	
Electronic Door Position Switch-Comm. Doors													X	X	
Electronic Detention Door Hardware											Х	Х	~	X	
Electronic Door Position Switch-Detention Doors											X	X			
282300 Video Management System															
Low Voltage Conduit & Junction Boxes including pull strings					Х	Х									
Low Voltage Wire/Cabling					Х	Х									
Network Servers and Switches for VMS					Х	Х									
System Manager					Х	Х									
120 Day Network Storage					Х	Х									
Recording Software					Х	Х									
Licensing Fees					Х	Х									
Workstations, Joystick Controllers, Keyboards, Display Monitors					Х	Х									-
Server and Storage Devices					Х	Х									
Video Management System and Video Recording Manager					Х	Х									-
Edge Ethernet Switches and Core Ethernet Switches					Х	Х									
Media Converters					Х	Х									-
Power Supplies					Х	Х									
Fast Ethernet over Coax Transceivers					X	X									+
Cameras					Х	Х									+
External Camera Audio					X	X									+
Camera Housings/ Mounting Brackets					X	X									+
283111 Digital, addressable Fire-Alarm System															
Complete			X	х											

	Owner Furnish	Owner Install	Electrical Contractor Furnish	Electrical Contractor Install	Security Electronics Contractor Furnish	Security Electronics Contractor Install	Plumbing Contractor Furnish	Plumbing Contractor Install	Module Supplier Furnish	Module Supplier Furnish	Detention Contractor Furnish	Detention Contractor Install	Comm. HM Contractor Furnish	Comm. HM Contractor Install	Rough Carp F&
284619 Electronics Security Control System															
Low Voltage Conduit & Junction Boxes including pull strings					Х	Х									
Low Voltage Wire/Cabling					Х	Х									
Ethernet based Network					Х	Х									
Managed Network Switches (County to specify exact product)					Х	Х									
PLC and Distributed I/O					Х	Х									
Programming for System Control and Monitoring Functions					Х	Х									
Relay Interface					Х	Х									
Watch Tour System					Х	Х									
Duress Alarm Stations					Х	Х									
Enclosures for equipment					Х	Х									
Power Supplies					Х	Х									
Data interface required for control of systems furnished by others															
(Power Controls, Lighting controls, water shutoffs, etc.)					X	Х									
Control Conduit, wire and terminations for connection to controlled															
equipment (Including equipment furnished by others)					х	х									
120V or greater power including conduit, wire and terminations															
required for controlled equipment (Including equipment furnished by															
others)			Х	х											
Power Control relays			X	X											
Lighting Control Panel/ relay panels			X	X											
Electronic controlled water shutoff valves (Non-Water Management															
System)							х	х							
Electronic Water Management System Valve Controllers							Х	Х	Х	Х					
Electronic Water Management System Computer Control Stations							Х	Х	Х	Х					
Electronic Water Management System - Manufacturers Assistance for															
System startup							х	х	х	х					
Electronic Water Management System -Electronic Plumbing Valves							Х	х	Х	Х					
Electronic Mictor Management Custors, Conduit for control wiring			V	Y											
Electronic Water Management System -Conduit for control wiring Electronic Water Management System -Control wire/cabling			X X	X X											
284623 Touch Screen Control and Management System															
					v	v									
Low Voltage Conduit & Junction Boxes including pull strings					X	X									
Low Voltage Wire/Cabling Touch Screen CPUs					X X	X X									
Touch Screen LCD Monitors															
					X X	X X									
Administration Station Monitor															
System Administration Station and File Server					X	X									
Report Printer					X	X									
Software					X	X									
Touchscreen Presentation and Display System					X	X									
Offender Management System Interface					Х	Х									
Report Generation					Х	Х									

	Owner	Owner	Electrical	Electrical	Security	Security	Plumbing	Plumbing	Module	Module	Detention	Detention	Comm. HM	Comm. HM	Rough
	Furnish	Install	Contractor Furnish	Contractor Install	Electronics Contractor Furnish	Electronics Contractor Install	Contractor Furnish	Contractor Install	Supplier Furnish	Supplier Furnish	Contractor Furnish	Contractor Install	Contractor Furnish	Contractor Install	Carp F&I
285123 Digital Intercom and Paging System															
Low Voltage Conduit & Junction Boxes including pull strings					Х	Х									
Low Voltage Wire/Cabling					Х	Х									
Digital Communications Controlers					Х	Х									
Talkback Expanders					Х	Х									
VOIP Paging/Talkback Amplifiers					Х	Х									
VOIP Desktop Intercom Master Stations					Х	Х									
VOIP Touchscreen Intercom Master Stations					Х	Х									
4 Wire 25V Intercom stations					Х	Х									
Software, Discrete I/O Modules, Network Repeaters					Х	Х									
Call/Door Push Buttons					Х	Х									
Paging Amplifiers					Х	Х									
Paging Horns					Х	Х									
Paging/Intercom Speakers/ Enclosures					Х	Х									
Visitation Handsets					Х	Х									
MFM sensor Vehicle detector					Х	Х									
Exterior Pedistals					Х	Х									
Power Supplies					Х	Х									
Paging horns/ Paging speakers					Х	Х									
Cisco Emergcy Notification															
Head End Equipment	Х	Х													
Cabling and Speakers			Х	Х											
															-
263353 Static Uninteruptible Power Supply															
Low Voltage Conduit & Junction Boxes including pull strings					Х	Х									
Low Voltage Wire/Cabling					Х	Х									
UPS Equipment including make before break Bypass Switches for the															
following systems:			Х	х											
Electronic Controls System				X	Х										
Video Management System (With Data Center Above)			Х	X	X										
Touch Screen Control and Management System				X	X										
Digital Intercom and Paging System				X	X										
					~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~										
Radio/DAS Equipment															
Cabinet	Х	Х													
Antenna Conduit			Х	Х											
Anennas	Х	Х													
Repeaters	Х	Х													
Radio Units	X	Х													

	Owner	Owner	Electrical	Electrical	Security	Security	Plumbing	Plumbing	Module	Module	Detention	Detention	Comm. HM	Comm. HM	Rough
	Furnish	Install	Contractor	Contractor	Electronics	Electronics	Contractor	Contractor	Supplier	Supplier	Contractor	Contractor	Contractor	Contractor	Carp F&I
			Furnish	Install	Contractor	Contractor	Furnish	Install	Furnish	Furnish	Furnish	Install	Furnish	Install	
					Furnish	Install									
End User Equipment AV															
Telephones including licensing and cabling from wall outlet/jack	x	x													
Computers/Workstations for Non-Building Systems-includes software	~	~													
and cabling from wall outlet/jack	Х	Х													
Surge Protectors At workstations/equipment	Х	Х													
TVs	Х	Х													
TV Mounting Brackets	Х	Х													
Cables from Wall Outlets/Jacks to Tvs	Х	Х													
Wbex Room Kit -Including cabling from wall outlet/Jack	Х	Х													







DATE:	Wednesday, November 2, 2022
PROJECT/JOB#:	760.013 Jackson Co. Detention Center
то:	JEDUNN
FROM:	Mark Stainbrook, PE Rick Maniktala, PE
SUBJECT:	HVAC System Life-Cycle-Cost Summary for VE alternatives

BranchPattern utilized IESVE modeling software to simulate base-year energy cost by fuel source. BLCC5 software was then utilized to perform the total building life cycle cost analysis for the HVAC system alternatives. BLCC5 utilized the FEMP methodology over a 40-year life. 40-years is the maximum term allowable per the FEMP methodology.

Summary below and input/output summary from life cycle costing analysis is included on the following pages.

#### 40 Year LCCA Summary:

Alternatives	<u>HVAC Initial</u> Costª	<u>Maintenance</u> Cost ^b	<u>Replacement</u> Cost ^c	<u>Energy Cost</u> (simulated) ^d	<u>Total Life</u> Cycle Cost ^e	<u>Total LCC</u> Difference
WCCH with N.G. Boiler 4- pipe Plant w/ HRC	+\$0, costs included in base	+\$163,837	+\$5,838,246	+\$591,505	\$ 21,697,978	+\$313,263 Over study life
WCCH with N.G. Boiler 4- pipe Plant w/o HRC	Deduct \$577k from Base	+\$157,466	+\$5,373,866	+\$620,113	\$ 21,384,715	Lowest Total Life-Cycle Cost
ACCH with N.G. boiler 4- pipe Plant	Deduct \$690k from Base	+\$126,786	+\$5,058,370	+\$702,956	\$ 22,288,821	+\$904,106 Over study life

Notes:

a) Initial Cost information from JE DUNN, US Engineering, and Mark One. \$690k is added to each option for BLCC5 analysis. Negative initial costs are not permitted by software.

b) Base-year O&M Service Contract Cost estimate information from US Engineering

c) Replacement Cost information from US Engineering. Replacement costs are applied in year 20 for all alternatives.

d) Base-year Energy Cost simulated by fuel source using IESVE

e) Total LCC output from BLCC5 analysis listed by alternative. See input/output reports on pages that follow.



## NIST BLCC 5.3-20: Detailed LCC Analysis

Consistent with Federal Life Cycle Cost Methodology and Procedures, 10 CFR, Part 436, Subpart A General Information

File Name:	\\meg.local\public\Desktops\mark.s\JCDC BLCC\projects\JCDC No DX.xml
Date of Study:	Wed Nov 02 11:35:41 CDT 2022
Analysis Type:	FEMP Analysis, Energy Project
Project Name:	JCDC
Project Location:	Missouri
Analyst:	
Base Date:	October 1, 2022
Service Date:	October 1, 2023
Study Period:	41 years 0 months (October 1, 2022 through September 30, 2063)
Discount Rate:	3%
Discounting Convention:	End-of-Year
Discount and	Escalation Rates are REAL (exclusive of general inflation)

## Alternative: Water Cooled w/HR

#### Initial Cost Data (not Discounted)

#### Initial Capital Costs

#### (adjusted for price escalation)

Initial Capital Costs for All Components: \$690,000

Component:			
Cost-Phasing			
Date	Portion	Yearly Cost	
October 1, 2022	100%	\$690,000	
Total (for Component)		\$690,000	
Energy Costs: Elect (base-year dollars)	tricity		

Average	Average	Average	Average
---------	---------	---------	---------



Annual Usage	Price/Unit	Annual Cost	Annual Demand	Annual Rebate
12,141,222.0 MBtu	\$0.03596	\$436,598	\$0	\$0

Energy Costs: Natural Gas

(base-year dollars)

Average		Average	Average	Average
Annual Usage	Price/Unit	Annual Cost	Annual Demand	Annual Rebate
17,961,501.0 MBtu	\$0.01060	\$190,392	\$0	\$0

## Life-Cycle Cost Analysis

	Present Value	Annual Value
Initial Capital Costs	\$690,000	\$29,473
Energy Costs		
Energy Consumption Costs	\$13,847,973	\$591,505
Energy Demand Charges	\$0	\$0
Energy Utility Rebates	\$0	\$0
Subtotal (for Energy):	\$13,847,973	\$591,505
Water Usage Costs	\$0	\$0
Water Disposal Costs	\$0	\$0
Operating, Maintenance & Repair Costs		
Component:		
Annually Recurring Costs	\$4,021,596	\$171,779
Non-Annually Recurring Costs	\$0	\$0
Subtotal (for OM&R):	\$4,021,596	\$171,779
Replacements to Capital Components		
Component:	\$3,138,408	\$134,055
Subtotal (for Replacements):	\$3,138,408	\$134,055



#### **Residual Value of Original Capital Components**

Component:		\$0	\$0
Subtotal (for	Residual Value):	\$0	\$0
Residual Val	ue of Capital Replace	ements	
Component:		\$0	\$0
Subtotal (for	Residual Value):	\$0	\$0
Total Life-Cy	vcle Cost	\$21,697,978	\$926,812
Emissions S	ummary		
Energy Name	Annual	Life-Cycle	
Electricity:			
CO2	3,203,879,408.26 kg	128,146,404,586.54 kg	
SO2	11,209,228.75 kg	448,338,460.73 kg	
NOx	4,880,818.46 kg	195,219,375.47 kg	
Natural Gas:			
CO2	948,721,517.76 kg	37,946,263,252.32 kg	
SO2	7,656,482.08 kg	306,238,321.09 kg	
NOx	795,970.91 kg	31,836,657.14 kg	
Total:			
CO2	4,152,600,926.01 kg	166,092,667,838.86 kg	
SO2	18,865,710.83 kg	754,576,781.82 kg	
NOx	5,676,789.37 kg	227,056,032.62 kg	

## Alternative: Water Cooled wo/HR

Initial Cost Data (not Discounted) Initial Capital Costs (adjusted for price escalation) Initial Capital Costs for All Components: \$113,000



Component: Cost-Phasing Date October 1, 2022		Yearly Cost \$113,000			
Total (for Component	:)	\$113,000			
Energy Costs: Na (base-year dollars) Average	tural Gas	Average	Average	Avera	ge
Annual Usage	Price/Unit	Annual Cost	Annual Demand	Annual R	ebate
17,640,145.0 MBtu	\$0.01060	\$186,986	\$0		\$0
Energy Costs: Ele (base-year dollars) Average	ctricity	Average	Average	Avera	ge
Annual Usage	Price/Unit	Annual Cost	Annual Demand	Annual R	ebate
13,170,342.0 MBtu	\$0.03596	\$473,605	\$0		\$0
Life-Cycle Cost A	Analysis		Descentil	alua Ann	
Initial Capital Costs				,000	1000 \$4,827
initial Capital Costs			\$113 _.	,000	<b>Φ</b> 4,027
Energy Costs					
Energy Consumptio	n Costs		\$14,517	,727 5	\$620,113
Energy Demand Cha	arges			\$0	\$0
Energy Utility Rebat	es			\$0	\$0
Subtotal (for Energy	<i>י</i> ):		\$14,517		\$620,113
Water Usage Costs				\$0	\$0

#### **Operating, Maintenance & Repair Costs**

Component:



Annually R	ecurring Costs		\$3,865,212	\$165,099
Non-Annua	ally Recurring Costs		\$0	\$0
Subtotal (for	OM&R):		\$3,865,212	\$165,099
Replacemen	ts to Capital Compon	ents		
Component:			\$2,888,776	\$123,392
Subtotal (for	Replacements):		\$2,888,776	\$123,392
Residual Val	ue of Original Capita	l Components		
Component:			\$0	\$0
Subtotal (for	Residual Value):		\$0	\$0
Residual Val	ue of Capital Replace	ements		
Component:			\$0	\$0
Subtotal (for	Residual Value):		\$0	\$0
Total Life-Cy	cle Cost	S	\$21,384,715	\$913,431
Emissions S	ummary			
Energy Name	Annual	Life-Cycle		
Natural Gas:				
CO2	931,747,582.67 kg	37,267,352,320	).90 kg	
SO2	7,519,497.07 kg	300,759,295	5.60 kg	
NOx	1,098,144.37 kg	43,922,768	3.42 kg	
Electricity:				
CO2	3,475,448,149.58 kg	139,008,410,724	ł.65 kg	
SO2	12,159,350.70 kg	486,340,737	7.33 kg	
NOx	5,294,528.70 kg	211,766,652	2.48 kg	
Total:				

## BranchPattern

CO2	4,407,195,732.25 kg	176,275,763,045.54 kg
SO2	19,678,847.77 kg	787,100,032.93 kg
NOx	6,392,673.08 kg	255,689,420.90 kg

## Alternative: Air Cooled

Initial Cost Data (not Discounted)

Initial Capital Costs

(adjusted for price escalation)

Initial Capital Costs for All Components: \$0

Component:

Cost-Phasing

Date	Portion	Yearly Cost
October 1, 2022	100%	\$0

Total (for Component)

#### Energy Costs: Natural Gas

(base-year dollars)

Average		Average	Average	Average
Annual Usage	Price/Unit	Annual Cost	Annual Demand	Annual Rebate
17,638,242.0 MBtu	\$0.01060	\$186,965	\$0	\$0

\$0

#### Energy Costs: Electricity

(base-year dollars)

Average		Average	Average	Average
Annual Usage	Price/Unit	Annual Cost	Annual Demand	Annual Rebate
15,805,611.0 MBtu	\$0.03596	\$568,370	\$0	\$0

#### Life-Cycle Cost Analysis

	Present Value	Annual Value
Initial Capital Costs	\$0	\$0
Energy Costs		
Energy Consumption Costs	\$16,457,197	\$702,956



Energy Demand Charges	\$0	\$0
Energy Utility Rebates	\$0	\$0
Subtotal (for Energy):	\$16,457,197	\$702,956
Water Usage Costs	\$0	\$0
Water Disposal Costs	\$0	\$0
Operating, Maintenance & Repair Costs		
Component:		
Annually Recurring Costs	\$3,112,131	\$132,932
Non-Annually Recurring Costs	\$0	\$0
Subtotal (for OM&R):	\$3,112,131	\$132,932
Replacements to Capital Components		
Component:	\$2,719,493	\$116,161
Subtotal (for Replacements):	\$2,719,493	\$116,161
Residual Value of Original Capital Compo	onents	
Component:	\$0	\$0
Subtotal (for Residual Value):	\$0	\$0
Residual Value of Capital Replacements		
Component:	\$0	\$0
Subtotal (for Residual Value):	\$0	\$0
Total Life-Cycle Cost	\$22,288,821	\$952,049
Emissions Summary		
Energy Name Annual	Life-Cycle	
Natural Gas:		

## BranchPattern

**MEMO** 

CO2	931,647,066.73 kg	37,263,331,958.74 kg
SO2	7,518,685.88 kg	300,726,850.01 kg
NOx	1,098,025.91 kg	43,918,030.08 kg
Electricity:		
CO2	4,170,854,599.14 kg	166,822,764,787.88 kg
SO2	14,592,329.27 kg	583,653,219.31 kg
NOx	6,353,917.09 kg	254,139,287.49 kg
Total:		
CO2	5,102,501,665.87 kg	204,086,096,746.62 kg
SO2	22,111,015.15 kg	884,380,069.32 kg
NOx	7,451,943.00 kg	298,057,317.57 kg

## NIST BLCC 5.3-20: Input Data Listing

Consistent with Federal Life Cycle Cost Methodology and Procedures, 10 CFR, Part 436, Subpart A General Information

File Name:	\\meg.local\public\Desktops\mark.s\JCDC BLCC\projects\JCDC No DX.xml
Date of Study:	Wed Nov 02 13:37:55 CDT 2022
Analysis Type:	FEMP Analysis, Energy Project
Project Name:	JCDC
Project Location:	Missouri
Analyst:	
Base Date:	October 1, 2022
Service Date:	October 1, 2023
Study Period:	41 years 0 months (October 1, 2022 through September 30, 2063)
Discount Rate:	3%
Discounting Convention:	End-of-Year

Discount and Escalation Rates are REAL (exclusive of general inflation)

## Alternative: Water Cooled w/HR



#### Energy: Electricity

Annual Consumption:	12,141,222.0 MBtu
---------------------	-------------------

Price per Unit:	\$0.03596
Demand Charge:	\$0
Utility Rebate:	\$0
Location:	Missouri
Rate Schedule:	Commercial
State:	Missouri

#### Usage Indices

From Date	Duration	Usage Index
October 1, 2023	Remaining	100%

#### Escalation Rates

From Date	Duration	Escalation
April 1, 2020	1 year 0 months	-1.62%
April 1, 2021	1 year 0 months	-1%
April 1, 2022	1 year 0 months	-0.9%
April 1, 2023	1 year 0 months	-0.6%
April 1, 2024	1 year 0 months	-0.04%
April 1, 2025	1 year 0 months	-0.11%
April 1, 2026	1 year 0 months	-0.49%
April 1, 2027	1 year 0 months	-0.75%
April 1, 2028	1 year 0 months	-0.75%
April 1, 2029	1 year 0 months	-0.54%
April 1, 2030	1 year 0 months	-0.76%
April 1, 2031	1 year 0 months	-0.55%
April 1, 2032	1 year 0 months	-0.48%
April 1, 2033	1 year 0 months	-0.41%
April 1, 2034	1 year 0 months	-0.63%
April 1, 2035	1 year 0 months	-0.67%
April 1, 2036	1 year 0 months	-0.6%



April 1, 2037	1 year 0 months	-0.53%
April 1, 2038	1 year 0 months	-0.65%
April 1, 2039	1 year 0 months	-0.57%
April 1, 2040	1 year 0 months	-0.54%
April 1, 2041	1 year 0 months	-0.5%
April 1, 2042	1 year 0 months	-0.74%
April 1, 2043	1 year 0 months	-0.59%
April 1, 2044	1 year 0 months	-0.39%
April 1, 2045	1 year 0 months	-0.47%
April 1, 2046	1 year 0 months	-0.32%
April 1, 2047	1 year 0 months	-0.44%
April 1, 2048	1 year 0 months	-0.6%
April 1, 2049	1 year 0 months	-0.68%
April 1, 2050	Remaining	-0.5%

#### Energy: Natural Gas

Annual Consumption:	17,961,501.0 MBtu
Price per Unit:	\$0.01060
Demand Charge:	\$0
Utility Rebate:	\$0
End-Use:	Commercial Boiler, uncontrolled
Rate Schedule:	Commercial
State:	Missouri

#### Usage Indices

From Date	Duration	Usage Index
October 1, 2023	Remaining	100%

#### Escalation Rates

From Date	Duration	Escalation
April 1, 2020	1 year 0 months	0%
April 1, 2021	1 year 0 months	0.16%



April 1, 2022	1 year 0 months	0.31%
April 1, 2023	1 year 0 months	0.62%
April 1, 2024	1 year 0 months	2.01%
April 1, 2025	1 year 0 months	2.88%
April 1, 2026	1 year 0 months	2.36%
April 1, 2027	1 year 0 months	1.58%
April 1, 2028	1 year 0 months	0.85%
April 1, 2029	1 year 0 months	0.14%
April 1, 2030	1 year 0 months	-0.56%
April 1, 2031	1 year 0 months	0.14%
April 1, 2032	1 year 0 months	0.85%
April 1, 2033	1 year 0 months	0.84%
April 1, 2034	1 year 0 months	0.42%
April 1, 2035	1 year 0 months	0%
April 1, 2036	1 year 0 months	0.41%
April 1, 2037	1 year 0 months	0.55%
April 1, 2038	1 year 0 months	0.27%
April 1, 2039	1 year 0 months	0.14%
April 1, 2040	1 year 0 months	0.27%
April 1, 2041	1 year 0 months	0.41%
April 1, 2042	1 year 0 months	0.27%
April 1, 2043	1 year 0 months	0.27%
April 1, 2044	1 year 0 months	0.54%
April 1, 2045	1 year 0 months	0.53%
April 1, 2046	1 year 0 months	0.66%
April 1, 2047	1 year 0 months	0.53%
April 1, 2048	1 year 0 months	0.66%
April 1, 2049	1 year 0 months	0.52%
April 1, 2050	Remaining	0.58%



### Component:

Initial Investment Initial Cost (base-year \$):	\$690,000	)
Annual Rate of Increase:	0%	)
Expected Asset Life:	20 years 0 months	5
Residual Value Factor:	0%	)
Cost-Phasing Cost Adjustment Factor:	0%	
Years/Months (from Date	) Date	Portion
0 years 0 months	October 1, 2022	100%
Replacement: Wate		
Years/Months:	20 years 0 months	
Amount:	\$5,838,246	1
Annual Rate Of Increase:	0%	1
Expected Asset Life:	20 years 0 months	;
Residual Value Factor:	0%	1
Recurring OM&R: M Amount:	laintenance \$163,837	
Annual Rate of Increase:	0.5%	
Usage Indices From Date Duration	on Factor	

October 1, 2023 Remaining 100%

## Alternative: Water Cooled wo/HR

## Energy: Natural Gas

Annual Consumption:	17,640,145.0 MBtu
Price per Unit:	\$0.01060
Demand Charge:	\$0
Utility Rebate:	\$0



End-Use:	Industrial Boiler, uncontrolled
Rate Schedule:	Commercial
State:	Missouri

#### Usage Indices

From Date	Duration	Usage Index
October 1, 2023	Remaining	100%

#### Escalation Rates

From Date	Duration	Escalation
April 1, 2020	1 year 0 months	0%
April 1, 2021	1 year 0 months	0.16%
April 1, 2022	1 year 0 months	0.31%
April 1, 2023	1 year 0 months	0.62%
April 1, 2024	1 year 0 months	2.01%
April 1, 2025	1 year 0 months	2.88%
April 1, 2026	1 year 0 months	2.36%
April 1, 2027	1 year 0 months	1.58%
April 1, 2028	1 year 0 months	0.85%
April 1, 2029	1 year 0 months	0.14%
April 1, 2030	1 year 0 months	-0.56%
April 1, 2031	1 year 0 months	0.14%
April 1, 2032	1 year 0 months	0.85%
April 1, 2033	1 year 0 months	0.84%
April 1, 2034	1 year 0 months	0.42%
April 1, 2035	1 year 0 months	0%
April 1, 2036	1 year 0 months	0.41%
April 1, 2037	1 year 0 months	0.55%
April 1, 2038	1 year 0 months	0.27%
April 1, 2039	1 year 0 months	0.14%
April 1, 2040	1 year 0 months	0.27%



April 1, 2041	1 year 0 months	0.41%
April 1, 2042	1 year 0 months	0.27%
April 1, 2043	1 year 0 months	0.27%
April 1, 2044	1 year 0 months	0.54%
April 1, 2045	1 year 0 months	0.53%
April 1, 2046	1 year 0 months	0.66%
April 1, 2047	1 year 0 months	0.53%
April 1, 2048	1 year 0 months	0.66%
April 1, 2049	1 year 0 months	0.52%
April 1, 2050	Remaining	0.58%

### Energy: Electricity

Annual Consumption:	13,170,342.0 MBtu
Price per Unit:	\$0.03596
Demand Charge:	\$0
Utility Rebate:	\$0
Location:	Missouri
Rate Schedule:	Commercial
State:	Missouri

#### Usage Indices

From Date	Duration	Usage Index
October 1, 2023	Remaining	100%

#### Escalation Rates

From Date	Duration	Escalation
April 1, 2020	1 year 0 months	-1.62%
April 1, 2021	1 year 0 months	-1%
April 1, 2022	1 year 0 months	-0.9%
April 1, 2023	1 year 0 months	-0.6%
April 1, 2024	1 year 0 months	-0.04%
April 1, 2025	1 year 0 months	-0.11%



April 1, 2026	1 year 0 months	-0.49%
April 1, 2027	1 year 0 months	-0.75%
April 1, 2028	1 year 0 months	-0.75%
April 1, 2029	1 year 0 months	-0.54%
April 1, 2030	1 year 0 months	-0.76%
April 1, 2031	1 year 0 months	-0.55%
April 1, 2032	1 year 0 months	-0.48%
April 1, 2033	1 year 0 months	-0.41%
April 1, 2034	1 year 0 months	-0.63%
April 1, 2035	1 year 0 months	-0.67%
April 1, 2036	1 year 0 months	-0.6%
April 1, 2037	1 year 0 months	-0.53%
April 1, 2038	1 year 0 months	-0.65%
April 1, 2039	1 year 0 months	-0.57%
April 1, 2040	1 year 0 months	-0.54%
April 1, 2041	1 year 0 months	-0.5%
April 1, 2042	1 year 0 months	-0.74%
April 1, 2043	1 year 0 months	-0.59%
April 1, 2044	1 year 0 months	-0.39%
April 1, 2045	1 year 0 months	-0.47%
April 1, 2046	1 year 0 months	-0.32%
April 1, 2047	1 year 0 months	-0.44%
April 1, 2048	1 year 0 months	-0.6%
April 1, 2049	1 year 0 months	-0.68%
April 1, 2050	Remaining	-0.5%

#### Component:

## Initial Investment

Initial Cost (base-year \$):	\$113,000
Annual Rate of Increase:	0%



Expected Asset Life:	20 years 0 months	S
Residual Value Factor:	0%	, 0
Cost-Phasing Cost Adjustment Factor:	0%	
Years/Months (from Date	e) Date	Portion
0 years 0 months	October 1, 2022	100%
Replacement: Wate Years/Months:	er Cooled wo/HF 20 years 0 months	
Amount:	\$5,373,866	
Annual Rate Of Increase:	0%	
Expected Asset Life:	20 years 0 months	5
Residual Value Factor:	0%	, )
Recurring OM&R: N Amount:	1aintenance \$157,466	
Annual Rate of Increase:	0.5%	
Usage Indices	on Factor	

From Date	Duration	Factor
October 1, 2023	Remaining	100%

## Alternative: Air Cooled

Energy: Natural G	as
Annual Consumption:	17,638,242.0 MBtu
Price per Unit:	\$0.01060
Demand Charge:	\$0
Utility Rebate:	\$0
End-Use:	Industrial Boiler, uncontrolled
Rate Schedule:	Commercial
State:	Missouri



#### Usage Indices

Usage Indices		
From Date	Duration	Usage Index
October 1, 20	23 Remaining	100%
Escalation Ra	tes	
From Date	Duration	Escalation
April 1, 2020	1 year 0 months	s 0%
April 1, 2021	1 year 0 months	s 0.16%
April 1, 2022	1 year 0 months	s 0.31%
April 1, 2023	1 year 0 months	s 0.62%
April 1, 2024	1 year 0 months	s 2.01%
April 1, 2025	1 year 0 months	s 2.88%
April 1, 2026	1 year 0 months	s 2.36%
April 1, 2027	1 year 0 months	s 1.58%
April 1, 2028	1 year 0 months	s 0.85%
April 1, 2029	1 year 0 months	s 0.14%
April 1, 2030	1 year 0 months	s -0.56%
April 1, 2031	1 year 0 months	s 0.14%
April 1, 2032	1 year 0 months	s 0.85%
April 1, 2033	1 year 0 months	s 0.84%
April 1, 2034	1 year 0 months	s 0.42%
April 1, 2035	1 year 0 months	s 0%
April 1, 2036	1 year 0 months	s 0.41%
April 1, 2037	1 year 0 months	s 0.55%
April 1, 2038	1 year 0 months	s 0.27%
April 1, 2039	1 year 0 months	s 0.14%
April 1, 2040	1 year 0 months	s 0.27%
April 1, 2041	1 year 0 months	s 0.41%
April 1, 2042	1 year 0 months	s 0.27%
April 1, 2043	1 year 0 months	s 0.27%
April 1, 2044	1 year 0 months	s 0.54%



April 1, 2045	1 year 0 months	0.53%
April 1, 2046	1 year 0 months	0.66%
April 1, 2047	1 year 0 months	0.53%
April 1, 2048	1 year 0 months	0.66%
April 1, 2049	1 year 0 months	0.52%
April 1, 2050	Remaining	0.58%

#### Energy: Electricity

Annual Consumption:	15,805,611.0 MBtu
Price per Unit:	\$0.03596
Demand Charge:	\$0
Utility Rebate:	\$0
Location:	Missouri
Rate Schedule:	Commercial
State:	Missouri

#### Usage Indices

From Date	Duration	Usage Index
October 1, 2023	Remaining	100%

#### Escalation Rates

From Date	Duration	Escalation
April 1, 2020	1 year 0 months	-1.62%
April 1, 2021	1 year 0 months	-1%
April 1, 2022	1 year 0 months	-0.9%
April 1, 2023	1 year 0 months	-0.6%
April 1, 2024	1 year 0 months	-0.04%
April 1, 2025	1 year 0 months	-0.11%
April 1, 2026	1 year 0 months	-0.49%
April 1, 2027	1 year 0 months	-0.75%
April 1, 2028	1 year 0 months	-0.75%
April 1, 2029	1 year 0 months	-0.54%



April 1, 2030	1 year 0 months	-0.76%
April 1, 2031	1 year 0 months	-0.55%
April 1, 2032	1 year 0 months	-0.48%
April 1, 2033	1 year 0 months	-0.41%
April 1, 2034	1 year 0 months	-0.63%
April 1, 2035	1 year 0 months	-0.67%
April 1, 2036	1 year 0 months	-0.6%
April 1, 2037	1 year 0 months	-0.53%
April 1, 2038	1 year 0 months	-0.65%
April 1, 2039	1 year 0 months	-0.57%
April 1, 2040	1 year 0 months	-0.54%
April 1, 2041	1 year 0 months	-0.5%
April 1, 2042	1 year 0 months	-0.74%
April 1, 2043	1 year 0 months	-0.59%
April 1, 2044	1 year 0 months	-0.39%
April 1, 2045	1 year 0 months	-0.47%
April 1, 2046	1 year 0 months	-0.32%
April 1, 2047	1 year 0 months	-0.44%
April 1, 2048	1 year 0 months	-0.6%
April 1, 2049	1 year 0 months	-0.68%
April 1, 2050	Remaining	-0.5%

### Component:

Initial Investment	
Initial Cost (base-year \$):	\$0
Annual Rate of Increase:	0%
Expected Asset Life:	20 years 0 months
Residual Value Factor:	0%

#### Cost-Phasing

Cost Adjustment Factor: 0%



Years/Months (from Date)	Date	Portion
0 years 0 months	October 1, 2022	100%
Replacement: Air Co	oled	
Years/Months:	20 years 0 months	5
Amount:	\$5,058,956	ó
Annual Rate Of Increase:	0%	, D
Expected Asset Life:	20 years 0 months	S
Residual Value Factor:	0%	, D
Recurring OM&R: M	aintenance	
Amount:	\$126,786	
Annual Rate of Increase:	0.5%	
Usage Indices		
From Date Duration	on Factor	
October 1, 2023 Remaini	ng 100%	

## BranchPattern

#### MEMO

## NIST BLCC 5.3-20: Comparative Analysis

Consistent with Federal Life Cycle Cost Methodology and Procedures, 10 CFR, Part 436, Subpart A Base Case: Water Cooled wo/HR

Alternative: Water Cooled w/HR

#### General Information

File Name:	\\meg.local\public\Desktops\mark.s\JCDC BLCC\projects\JCDC No DX.xml
Date of Study:	Wed Nov 02 13:39:25 CDT 2022
Project Name:	JCDC
Project Location:	Missouri
Analysis Type:	FEMP Analysis, Energy Project
Analyst:	
Base Date:	October 1, 2022
Service Date:	October 1, 2023
Study Period:	41 years 0 months(October 1, 2022 through September 30, 2063)
Discount Rate:	3%
Discounting Convention:	End-of-Year

## Comparison of Present-Value Costs

### PV Life-Cycle Cost

	Base Case	Alternative	Savings from Alternative
Initial Investment Costs:			
Capital Requirements as of Base Date	\$113,000	\$690,000	-\$577,000
Future Costs:			
Energy Consumption Costs	\$14,517,727	\$13,847,973	\$669,754
Energy Demand Charges	\$0	\$0	\$0
Energy Utility Rebates	\$0	\$0	\$0
Water Costs	\$0	\$0	\$0
Recurring and Non-Recurring OM&R Costs	\$3,865,212	\$4,021,596	-\$156,385
Capital Replacements	\$2,888,776	\$3,138,408	-\$249,632
Residual Value at End of Study Period	\$0	\$0	\$0



Subtotal (for Future Cost Items)	\$21,271,715 \$21,007,978	\$263,737
Total PV Life-Cycle Cost	\$21,384,715 \$21,697,978	-\$313,263
Net Savings from Alternative	e Compared with Base Case	
PV of Non-Investment Savings \$513,3	69	
- Increased Total Investment \$826,6	32	
Net Savings -\$313,2	63	
Savings-to-Investment Ratio	(SIR)	
<b>SIR =</b> 0.62		
SIR is lower than 1.0; project alterna	tive is not cost effective.	
Adjusted Internal Rate of Re	turn	
<b>AIRR =</b> 1.81%		
AIRR is lower than your discount rate	e; project alternative is not cost effect	tive.

Payback Period

#### Estimated Years to Payback (from beginning of Service Period)

Simple Payback never reached during study period. Discounted Payback never reached during study period.

### Energy Savings Summary

#### Energy Savings Summary (in stated units)

Energy	Average	Annual	Consumption	Life-Cycle
Туре	Base Case	Alternative	Savings	Savings
Electricity	13,170,342.0 MBtu	12,141,222.0 MBtu	1,029,120.0 MBtu	41,161,982.4 MBtu
Natural Gas	17,640,145.0 MBtu	17,961,501.0 MBtu	-321,356.0 MBtu	-12,853,360.2 MBtu

#### Energy Savings Summary (in MBtu)

Energy	Average	Annual	Consumption	Life-Cycle
Туре	Base Case	Alternative	Savings	Savings
Electricity	13,170,342.0 MBtu	12,141,222.0 MBtu	1,029,120.0 MBtu	41,161,982.4 MBtu

## BranchPattern

Natural Gas 17,640,145.0 MBtu 17,961,501.0 MBtu -321,356.0 MBtu -12,853,360.2 MBtu

Emissions Reduction Summary				
Energy	Average	Annual	Emissions	Life-Cycle
Туре	Base Case	Alternative	Reduction	Reduction
Electricity				
CO2	3,475,448,149.58 kg	3,203,879,408.26 kg	271,568,741.32 kg	10,862,006,138.11 kg
SO2	12,159,350.70 kg	11,209,228.75 kg	950,121.95 kg	38,002,276.60 kg
NOx	5,294,528.70 kg	4,880,818.46 kg	413,710.24 kg	16,547,277.01 kg
Natural Gas				
CO2	931,747,582.67 kg	948,721,517.76 kg	-16,973,935.09 kg	-678,910,931.43 kg
SO2	7,519,497.07 kg	7,656,482.08 kg	-136,985.01 kg	-5,479,025.50 kg
NOx	1,098,144.37 kg	795,970.91 kg	302,173.46 kg	12,086,111.27 kg
Total:				
CO2	4,407,195,732.25 kg	4,152,600,926.01 kg	254,594,806.23 kg	10,183,095,206.68 kg
SO2	19,678,847.77 kg	18,865,710.83 kg	813,136.93 kg	32,523,251.10 kg
NOx	6,392,673.08 kg	5,676,789.37 kg	715,883.71 kg	28,633,388.28 kg

## **Emissions Reduction Summary**

## NIST BLCC 5.3-20: Comparative Analysis

Consistent with Federal Life Cycle Cost Methodology and Procedures, 10 CFR, Part 436, Subpart A Base Case: Water Cooled wo/HR

#### Alternative: Air Cooled

#### General Information

File Name:	\\meg.local\public\Desktops\mark.s\JCDC BLCC\projects\JCDC No DX.xml		
Date of Study:	Wed Nov 02 13:40:19 CDT 2022		
Project Name:	JCDC		
Project Location:	Missouri		
Analysis Type:	FEMP Analysis, Energy Project		
Analyst:			
Base Date:	October 1, 2022		

24 of 26



Service Date:	October 1, 2023
Study Period:	41 years 0 months(October 1, 2022 through September 30, 2063)
Discount Rate:	3%
Discounting Convention:	End-of-Year

## Comparison of Present-Value Costs

## PV Life-Cycle Cost

	Base Case	Alternative	Savings from Alternative	
Initial Investment Costs:				
Capital Requirements as of Base Date	\$113,000	\$0	\$113,000	
Future Costs:				
Energy Consumption Costs	\$14,517,727	\$16,457,197	-\$1,939,470	
Energy Demand Charges	\$0	\$0	\$0	
Energy Utility Rebates	\$0	\$0	\$0	
Water Costs	\$0	\$0	\$0	
Recurring and Non-Recurring OM&R Costs	\$3,865,212	\$3,112,131	\$753,081	
Capital Replacements	\$2,888,776	\$2,719,493	\$169,283	
Residual Value at End of Study Period	\$0	\$0	\$0	
Subtotal (for Future Cost Items)	\$21,271,715	\$22,288,821	-\$1,017,106	
Total PV Life-Cycle Cost	\$21,384,715	\$22,288,821	-\$904,106	
Net Savings from Alternative Compared with Base Case				

PV of Non-Investment Savings -\$1,186,389

- Increased Total Investment	-\$282,283

**Net Savings** -\$904,106

## BranchPattern

#### MEMO

NOTE: Meaningful SIR, AIRR and Payback can not be computed unless incremental savings and total savings are both positive.

## **Energy Savings Summary**

Energy Savings Summary (in stated units)

Energy	Average	Annual	Consumption	Life-Cycle
Туре	Base Case	Alternative	Savings	Savings
Electricity	13,170,342.0 MBtu	15,805,611.0 MBtu	-2,635,269.0 MBtu	-105,403,545.0 MBtu
Natural Gas	17,640,145.0 MBtu	17,638,242.0 MBtu	1,903.0 MBtu	76,114.8 MBtu

#### Energy Savings Summary (in MBtu)

Energy	Average	Annual	Consumption	Life-Cycle
Туре	Base Case	Alternative	Savings	Savings
Electricity	13,170,342.0 MBtu	15,805,611.0 MBtu	-2,635,269.0 MBtu	-105,403,545.0 MBtu
Natural Gas	17,640,145.0 MBtu	17,638,242.0 MBtu	1,903.0 MBtu	76,114.8 MBtu

## **Emissions Reduction Summary**

Energy	Average	Annual	Emissions	Life-Cycle
Туре	Base Case	Alternative	Reduction	Reduction
Electricity				
CO2	3,475,448,149.58 kg	4,170,854,599.14 kg	-695,406,449.56 kg	-27,814,354,063.24 kg
SO2	12,159,350.70 kg	14,592,329.27 kg	-2,432,978.58 kg	-97,312,481.98 kg
NOx	5,294,528.70 kg	6,353,917.09 kg	-1,059,388.39 kg	-42,372,635.01 kg
Natural Gas				
CO2	931,747,582.67 kg	931,647,066.73 kg	100,515.93 kg	4,020,362.16 kg
SO2	7,519,497.07 kg	7,518,685.88 kg	811.20 kg	32,445.59 kg
NOx	1,098,144.37 kg	1,098,025.91 kg	118.47 kg	4,738.34 kg
Total:				
CO2	4,407,195,732.25 kg	5,102,501,665.87 kg	-695,305,933.62 kg	-27,810,333,701.08 kg
SO2	19,678,847.77 kg	22,111,015.15 kg	-2,432,167.38 kg	-97,280,036.39 kg
NOx	6,392,673.08 kg	7,451,943.00 kg	-1,059,269.92 kg	-42,367,896.67 kg

HVAC System Life-Cycle-Cost Summary for VE alternatives End of Exhibit 12

26 of 26

BranchPattern.com